

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	*	TAZEWELL	1366	928
STA.		TO STA.		
FED. ROAD DIST. NO. 4		ILLINOIS FED. AID PROJECT		

• (90-111R-2;90113,14,14-11R-1

TRAFFIC BARRIER TERMINAL, TYPE 2	
LOCATION	EACH
STA. 10+515.525, 6.700 m LT. (RAMP L-3) TO STA. 10+519.335, 6.700 m LT. (RAMP L-3)	1
STA. 10+525.000, 2.400 m RT. (RAMP L-3) TO STA. 10+528.810, 2.400 m RT. (RAMP L-3)	1
TOTAL	2

TRAFFIC BARRIER TERMINAL, TYPE 6	
LOCATION	EACH
STA. 153+891.996 TO STA. 153+901.521 m LT. (W.B. I-74)	1
TOTAL	1

TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (TANGENT)	
LOCATION	EACH
STA. 10+431.745 TO STA. 10+446.945, 6.100 m LT. (RAMP L-3)	1
STA. 10+409.800 TO STA. 10+424.800, 6.100 m LT. (RAMP L-3)	1
STA. 153+932.021, 15.409 m LT. TO STA. 153+947.221, 15.713 m LT. (W.B. I-74)	1
TOTAL	3

HANDHOLE	
LOCATION	EACH
STA. 100+129.265 -- 19.55 M RIGHT	1
TOTAL	1

TEMPORARY CONCRETE BARRIER	
LOCATION	EACH
STAGE 3A	
EB PAVEMENT NEAR CENTERLINE STA. 154+300.000 TO STA. 154+500.000	250
EB PAVEMENT NEAR CENTERLINE STA. 154+500.000 TO STA. 154+780.000	280
EB PAVEMENT NEAR CENTERLINE STA. 154+780.000 TO STA. 154+886.500	107
TOTAL	637

RELOCATE TEMPORARY CONCRETE BARRIER (STATE OWNED)	
LOCATION	EACH
STAGE 3A	
FROM WB MEDIAN SHOULDER STA. 153+901.108 TO STA. 154+158.928 TO EB PAVEMENT NEAR CENTERLINE STA. 153+892.180 TO STA. 154+150.000	257.82
FROM WB MEDIAN SHOULDER STA. 154+158.928 TO STA. 154+258.928 TO EB PAVEMENT NEAR CENTERLINE STA. 154+150.000 TO STA. 154+250.000	100.00
FROM CROSSOVER PAVEMENT STA. 154+780.000 TO STA. 154+800.000 TO NORTH SIDE WB X-OVER TRAFFIC LANE STA. 154+780.000 TO STA. 154+800.000	20.00
FROM NORTH SIDE WB X-OVER TRAFFIC LANE STA. 154+800.000 TO STA. 154+830.000 TO MEDIAN SHOULDER WB PAVEMENT STA. 154+780.000 TO STA. 154+830.000	30.00
FROM WB MEDIAN SHOULDER STA. 154+258.928 TO STA. 154+350.000 & FROM X-OVER PAVEMENT STA. 154+830.000 TO STA. 154+895.000 & TO CROSS WB PAVEMENT FROM RIGHT SHOULDER WB PAVEMENT TO WB MEDIAN SHOULDER STA. 154+200.000 TO STA. 154+350.000	156.07
TOTAL	564

CONDUIT IN TRENCH, 30 MM DIA., PVC	
LOCATION	METER
STA. 100+126.967 TO STA. 100+128.804 (RIGHT)	2.5
STA. 100+127.241 TO STA. 100+128.804 (RIGHT)	2.5
TOTAL	5.0

DETECTOR LOOP, TYPE I	
LOCATION	METER
STA. 100+113.100, 4.55 M RIGHT	25.4
STA. 100+113.100, 8.14 M RIGHT	23.7
TOTAL	49.0

REMOVE TEMPORARY CONCRETE BARRIER (STATE OWNED)	
LOCATION	EACH
STAGE 3B	
WB STA. 154+200.000 TO STA. 154+500.000	306
WB STA. 154+500.000 TO STA. 154+780.000	280
STAGE 3C	
CENTERLINE EB PAVEMENT STA. 153+892.180 TO STA. 154+150.000	258
CENTERLINE EB PAVEMENT STA. 154+150.000 TO STA. 154+250.000	100
TOTAL	944

CONCRETE BARRIER, DOUBLE FACE (SPECIAL)	
LOCATION	EACH
STA. 10+123.117 TO STA. 10+217.189 (RAMP L-4)	44.68
TOTAL	44.7

TEMPORARY CONCRETE BARRIER (TO REMAIN PERMANENTLY)	
LOCATION	EACH
STAGE 3C	
X-OVER CENTERLINE STA. 154+780.000 TO STA. 154+886.500	106.75
TOTAL	106.75

REMOVE TEMPORARY CONCRETE BARRIER	
LOCATION	EACH
STAGE 3C	
CENTERLINE EB PAVEMENT STA. 154+250.000 TO STA. 154+500.000	250
CENTERLINE EB PAVEMENT STA. 154+500.000 TO STA. 154+780.000	280
CENTERLINE EB PAVEMENT STA. 154+780.000 TO STA. 154+886.500	107
TOTAL	637

CLEAN EXISTING PAVEMENT EDGE JOINT	
LOCATION	UNIT
STA. 154+780.000 TO STA. 154+970 LT. (CROSSOVER)	1
1 UNIT = 30 m	6.3
TOTAL	6.3

IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW) TEST LEVEL 2	
LOCATION	EACH
STA. 10+118.039, 6.100 m LT. (RAMP L-4) TO STA. 10+123.117, 6.100 m LT. (RAMP L-4)	1
TOTAL	1

IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE) TEST LEVEL 2	
LOCATION	EACH
STA. 154+812.567 (EB I-74) TO STA. 154+820.464 (EB I-74)	1
STA. 154+887.000 (EB I-74) TO STA. 154+894.836 (EB I-74)	1
TOTAL	2

REMOVAL AND REINSTALLATION OF EXISTING IMPACT ATTENUATORS	
LOCATION	EACH
STA. 154+885.000, 3.5 m RT. (E.B. I-74)	1
TOTAL	1

SHEET 6 OF 7



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 F.A.I. ROUTE 74 (I-74)  
 SCHEDULE OF QUANTITIES  
 (FOR INFORMATION ONLY)  
 DRAWN BY  
 CHECKED BY  
 DATE 01/14/2005

01/14/2005 09:18:05 AM  
 c:\data\5589-74\dwg\confr\cch\sc0106-6a.dgn

CONTRACT 11: PLAN SET 2 OF 4 FINAL PLANS 01/05