

FAP ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
664	*	SANGAMON	61	3
STA.		TO STA.		
EXISTING CONDITIONS:				
* D-6 RESURFACING 2005-1				
CONTRACT NO. 72790				

**SUMMARY OF QUANTITIES**

CODE	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE TYPE															
				1000-2A	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F						
				(Spring St.) 80% FED 20% STATE 10% CITY	(S. GRAND AVE.) (2nd St.) 80% FED 5% STATE 15% CITY	(Walnut St.) 80% FED 10% STATE 10% CITY	(RobInhood Ln.) 80% FED 10% STATE 10% CITY	(WABASH AVE.) (Kirkley) 80% FED 10% STATE 10% CITY	(Drawbridge Rd.) 80% FED 13.33% STATE 6.67% CITY	(White Oaks East) (Wall Entr.) 100% SIMON PRIVATE	(S. Grand Ave.) 80% FED 10% CITY	(Iles Ave.) 80% FED 13.33% STATE 6.67% CITY							
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	50.3	50.3															
40600300	AGGREGATE (PRIME COAT)	TON	264	264															
40600895	CONSTRUCTING TEST STRIP	EACH	2	2															
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	2,762	2,762															
40600990	TEMPORARY RAMP	SQ YD	1,841	1,841															
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	754	754															
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	190	190															
44000007	BITUMINOUS SURFACE REMOVAL 2"	SQ YD	129,265	129,265															
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	89	89															
44000500	COMBINATION CONCRETE CURB AND GUTTER REMOVAL	FOOT	6,827	6,827															
44201377	CLASS C PATCHES, TYPE II, 12 INCH	SQ YD	677	677															
44201381	CLASS C PATCHES, TYPE III, 12 INCH	SQ YD	40	40															
44201383	CLASS C PATCHES, TYPE IV, 12 INCH	SQ YD	308	308															
60260100	INLETS TO BE ADJUSTED	EACH	43	43															
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	500	500															
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	1,532	1,532															
60611600	COMBINATION CONCRETE CURB AND GUTTER, (SPECIAL)	FOOT	4,167	4,167															
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	13,558	13,558															
60623200	CONCRETE MEDIAN, TYPE SM-6.24	SQ FT	2,781	2,781															
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	7	7															
67100100	MOBILIZATION	L SUM	1	1															
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1															
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1															
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1															
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DAY	210	210															
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	13,448	13,448															
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	3,536	3,536															
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	47,174	47,174															
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	15,571	15,571															
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	1,212	1,212															
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	414	414															
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	1,722	1,722															
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4,483	4,483															
* 78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	27,236	27,236															
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	32	32															
78003100	PERFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS	SQ FT	3,536	3,536															

\* SPECIALTY PAY ITEM

DATE \_\_\_\_\_  
BY \_\_\_\_\_  
PLAN \_\_\_\_\_  
NOTE BOOK \_\_\_\_\_  
NO. \_\_\_\_\_  
SURVEYED \_\_\_\_\_  
CHECKED \_\_\_\_\_  
ALIGNED \_\_\_\_\_  
BY \_\_\_\_\_  
DATE \_\_\_\_\_  
BY \_\_\_\_\_  
DATE \_\_\_\_\_

**HOMER L. CHASTAIN & ASSOCIATES, LLP**  
CONSULTING ENGINEERS  
DECATUR (217) 423-8544  
CHICAGO (773) 714-0050  
184-001397

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
FAP ROUTE 664  
(WABASH AVE. & MACARTHUR BLVD)  
SECTION D-6 RESURFACING 2005-1  
SANGAMON COUNTY  
**SUMMARY OF QUANTITIES**  
DRAWN BY: DLB CHECKED BY:

\*DATE\$  
\*DRAW\$  
\*CHK\$  
\*REF\$  
\*REV\$