

SECTION	COUNTY	TOTAL SHEETS	SHEET NO
664	SANGAMON	61	11

**PAVING SCHEDULE**

STA. \* TO STA.  
 EXISTING CONDITIONS:  
 \* D-6 RESURFACING 2005-1  
 CONTRACT NO. 72790

STATION TO STATION	MAINLINE BITUMINOUS MATERIALS (PRIME COAT) TON	SIDEROAD BITUMINOUS MATERIALS (PRIME COAT) TON	MAINLINE AGGREGATE (PRIME COAT) TON	SIDEROAD AGGREGATE (PRIME COAT) TON	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE SUPERPAVE MIX E, N70 TON	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE SUPERPAVE MIX D, N70 TON	INCIDENTAL BITUMINOUS SURFACING TON
<b>WABASH</b>							
521+87 WB TO 604+71 WB	11.3		59.4		3,328.4		
521+87 EB TO 604+71 EB	10.1		52.7		2,950.5		
526+28 EAST WHITE OAKS		0.22		1.14			64.1
526+28 SHERWOOD PLAZA		0.08		0.42			23.7
528+68 DRAWBRIDGE RD		0.10		0.52			29.2
535+70 WEST COLONY BLVD		0.20		1.05			58.6
540+00 WABASH MEDICAL		0.04		0.19			10.9
548+00 KIRKLEY LANE		0.08		0.41			22.8
548+18 MONTVALE DR		0.12		0.62			34.7
559+60 ROBINHOOD LANE		0.12		0.61			34.1
559+63 ROBINHOOD LANE		0.11		0.59			33.3
564+00 ENTRANCE		0.07		0.36			20.1
573+50 ENTRANCE		0.06		0.30			17.0
577+78 CORBIN ST		0.06		0.33			18.7
586+38 NORTH LEONARD ST		0.05		0.26			14.8
586+38 SOUTH LEONARD ST		0.01		0.07			7.9
595+01 FILMORE ST		0.04		0.21			11.5
<b>WABASH SUBTOTAL</b>	<b>21.4</b>	<b>1.3</b>	<b>112</b>	<b>7</b>	<b>6,279</b>		<b>401</b>
<b>CHATHAM</b>							
CHATHAM & WABASH INTER	2.0		10.6		596.3		
83+00 NB TO 84+94 NB	1.3		6.6		368.5		
83+00 SB TO 84+94 SB	0.2		1.1		64.3		
219+33 NB TO 222+00 NB	0.4		2.0		111.7		
219+33 SB TO 222+00 SB	0.5		3.1		167.1		
<b>CHATHAM SUBTOTAL</b>	<b>4.4</b>		<b>23</b>		<b>1,308</b>		<b>0.0</b>
<b>MACARTHUR</b>							
639+27 NB TO 687+05 NB	5.0		26.1		1,463.0		
639+27 SB TO 687+05 SB	5.6		29.3		1,639.6		
641+35 ILES AVE		0.01		0.05			5.2
643+10 LENOX AVE		0.03		0.17			9.7
649+15 TOWN & COUNTRY		0.07		0.37			20.6
656+80 OUTER PARK DRIVE		0.07		0.36			20.1
656+90 OUTER PARK DRIVE		0.10		0.53			29.7
660+00 ENTRANCE		0.04		0.20			11.1
663+15 CHERRY RD		0.05		0.24			13.6
669+82 ASH ST		0.01		0.09			5.3
683+09 LAUREL		0.01		0.11			6.0
683+40 LAUREL		0.01		0.10			5.4
0+00 NB TO 11+00 NB	1.1		5.8		326.9		
0+00 SB TO 11+00 SB	1.1		5.8		326.5		
1+09 CAMPBELL AVE		0.01		0.08			4.5
4+23 LELAND AVE		0.01		0.09			4.9
6+57 CONKLIN AVE		0.01		0.09			5.0
MACARTHUR & S GRAND INTER	1.2		6.2		357.3		
<b>MACARTHUR SUBTOTAL</b>	<b>14.0</b>	<b>0.4</b>	<b>73</b>	<b>3</b>	<b>4,113</b>		<b>141</b>
<b>SOUTH GRAND</b>							
2+00 EB TO 40+90 EB	4.0		20.7			1,161.6	
2+00 WB TO 40+90 WB	4.0		21.1			1,187.5	
3+81 STATE ST		0.02		0.13			7.0
7+70 GLENWOOD ST		0.03		0.15			8.2
7+77 GLENWOOD ST		0.03		0.15			8.2
11+60 WALNUT ST		0.02		0.13			7.4
14+47 WALNUT ST		0.06		0.29			16.3
15+42 HOLMES ST		0.02		0.12			6.8
19+65 LOWELL ST		0.06		0.29			16.3
21+21 HENRIETTA ST		0.04		0.19			10.9
23+87 WHITTER ST		0.02		0.12			6.8
27+72 PASFIELD ST		0.02		0.12			6.6
27+94 PASFIELD ST		0.03		0.15			8.2
31+17 COLLEGE ST		0.02		0.12			6.6
31+36 COLLEGE ST		0.03		0.15			8.3
34+31 SPRING ST		0.10		0.53			29.8
34+31 SPRING ST		0.10		0.50			28.0
37+30 FIRST ST		0.02		0.12			6.8
37+64 FIRST ST		0.02		0.10			5.5
<b>SOUTH GRAND SUBTOTAL</b>	<b>8.0</b>	<b>0.6</b>	<b>42</b>	<b>3</b>		<b>2,349</b>	<b>188</b>
<b>MAINLINE TOTAL</b>	<b>47.8</b>		<b>251</b>		<b>11,700</b>	<b>2,349</b>	
<b>SIDEROAD TOTAL</b>		<b>2.4</b>		<b>13</b>			<b>730</b>
<b>ENTRANCE TOTAL</b>		<b>0.1</b>					<b>24</b>
<b>PROJECT TOTAL</b>	<b>50.3</b>		<b>264</b>		<b>11,700</b>	<b>2,349</b>	<b>754</b>

PLAN NO. \_\_\_\_\_  
 DATE \_\_\_\_\_  
 BY \_\_\_\_\_  
 CHECKED \_\_\_\_\_  
 DATE \_\_\_\_\_

DATE: 11/11/05  
 TIME: 10:55 AM

**HOMER L. CHASTAIN & ASSOCIATES, LLP**  
 CONSULTING ENGINEERS  
 DECATUR (217) 422-8544  
 CHICAGO (773) 714-0050  
 184-001397

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 FAP ROUTE 664  
 (WABASH AVE. & MACARTHUR BLVD)  
 SECTION D-6 RESURFACING 2005-1  
 SANGAMON COUNTY  
 SCHEDULES OF QUANTITIES  
 DRAWN BY: SSB CHECKED BY: CAS