

FAP ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
664	*	SANGAMON	61	12
STA. TO STA.				
EXISTING CONDITIONS:				
* D-6 RESURFACING 2005-1 CONTRACT NO. 72790				

PAVEMENT MARKING SCHEDULE

STATION TO STATION	THERMOPLASTIC PAVEMENT MARKING - LINE (FOOT)			PREFORMED PLASTIC PAVEMENT MARKING, TYPE B								RAISED REFLECTIVE PAVEMENT MARKER (EACH)		RAISED REFLECTIVE PAVEMENT MARKER REMOVAL
	5"		12"	LETTERS & SYMBOLS (SF)				LINE (FT)				1 WAY CRYSTAL		2 WAY AMBER
	WHITE	YELLOW	WHITE	WHITE	WHITE	YELLOW	WHITE	WHITE	WHITE	YELLOW	WHITE	1 WAY CRYSTAL	2 WAY AMBER	REMOVAL
WABASH														
521+87 WB TO 604+71 WB		6,884		592.8	1,850							182		
521+87 EB TO 604+71 EB		6,663		514.8	1,870							181		
535+70 WEST COLONY BLVD		126												
521+87 TO 604+71		860		312.0		2,274	7,976			36	816		80	
526+52 WB TO 529+44 WB	292													
529+41 WB TO 530+28 WB							174							
EAST WHITE OAKS ENTRANCE	75													
564+30 WB TO 565+50 WB			32											
WABASH SUBTOTAL	367	14,533	32	1,419.6	3,720	2,274	7,976	174		36	816	363	80	443
CHATHAM														
82+17 NB TO 84+94 NB		260		145.6	70		635					7		
82+17 SB TO 84+94 SB		299			70					6	70	6		
CHATHAM & WABASH INTER							838	730						
219+32 NB TO 222+64 NB		316		15.6	80			30				8		
219+32 SB TO 222+64 SB		316		109.2	90		547				72	8		
CHATHAM SUBTOTAL		1,191		270.4	310		2,020	730	30	6	142	29		29
MACARTHUR														
639+27 NB TO 687+00 NB		2,219		280.8	1,070	212		22				105		
639+27 SB TO 687+00 SB		2,219		332.8	1,050	264		130				103		
639+27 TO 687+00		1,060		405.6		4,366	2776				263	393	90	
0+00 NB TO 13+53 NB		304		88.4	330							56		
0+00 SB TO 13+53 SB		211			310							31		
0+00 TO 11+67						1,870	280					29		
MACARTHUR SUBTOTAL		6,013		1,108	2,760	6,712	3,056	152		263	449	268	90	358
SOUTH GRAND														
49+46 WB TO 50+29 WB		83										1		
49+46 EB TO 50+29 EB		83										1		
S GRAND & MACARTHUR INTER							411	156						
1+02 WB TO 40+90 WB		2,155		223.6	860							71		
1+02 EB TO 40+90 EB		1,911		140.4	850							71		
S GRAND & SPRING INTER							515							
1+20 TO 40+90		900		374.4		2,452	1593			47	267		66	
SOUTH GRAND SUBTOTAL		5,132		738.4	1,710	2,452	2,519	156		47	315	144	66	210
TOTAL WHITE	367		32	3,536	8,500	15,571	1,212	30		1,722	804			
TOTAL YELLOW		26,869				11,438				352		236		
PROJECT TOTAL	27,236		32	3,536	19,938	15,571	1,212	382		1,722	1,040		1,040	

TEMPORARY PAVEMENT MARKING SCHEDULE

STATION TO STATION	SHORT-TERM PAVEMENT MARKING - LINE (FOOT)		WORK ZONE PAVEMENT MARKING REMOVAL	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	TEMPORARY PAVEMENT MARKING LINE 5" (FOOT)		TEMPORARY PAVEMENT MARKING LINE 6" (FOOT)		TEMPORARY PAVEMENT MARKING LINE 8" (FOOT)		TEMPORARY PAVEMENT MARKING LINE 12" (FOOT)		TEMPORARY PAVEMENT MARKING LINE 24" (FOOT)	
	WHITE	YELLOW			WHITE	YELLOW	WHITE	YELLOW	WHITE	YELLOW	WHITE	YELLOW	WHITE	YELLOW
WABASH SUBTOTAL	4,376	968	1,782	1,420	4,087	16,807	7,976		174		32		36	816
CHATHAM SUBTOTAL	512		171	270	310	1,191	2,020		730		30		6	142
MACARTHUR SUBTOTAL	2,944	1,656	1,533	1,108	2,760	12,725	3,056		152				263	449
SOUTH GRAND SUBTOTAL	1,856	1,136	997	738	1,710	7,584	2,519		156				47	315
TOTAL WHITE	9,688				8,867		15,571		1,212		62			1,722
TOTAL YELLOW		3,760				38,307					352			
PROJECT TOTAL	13,448		4,483	3,536	47,174		15,571		1,212		414		352	1,722

PLAN SURVEYED BY DATE
 ALIGNED CHECKED BY DATE
 RT. OF WAY CHECKED BY DATE
 PLOTTED FILE NAME NO.

HOMER L. CHASTAIN & ASSOCIATES, LLP
 CONSULTING ENGINEERS
 DECATUR (217) 422-8544
 CHICAGO (773) 714-0050
 184-001397

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 FAP ROUTE 664
 (WABASH AVE. & MACARTHUR BLVD)
 SECTION D-6 RESURFACING 2005-1
 SANGAMON COUNTY
 SCHEDULES OF QUANTITIES
 DRAWN BY: SSB CHECKED BY: CAS

PLOT DATE: *DATE* *TIME* *FILENAME*

SCHEDULES OF QUANTITIES