

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SCHUYLER		4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
* 310 (US 67)/317 (US 24)		** (87-1)I-1, TS-2		

PAY CODES	ITEMS	UNITS	TOTAL	Resurfacing	Signals
				RURAL 90% FED 10% STATE	RURAL 90% FED 10% STATE
				I000-1A	Y031-1F
44000500	COMBINATION CURB & GUTTER REMOVAL	FOOT	456	456	
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	519	519	
44200140	PAVEMENT PATCHING, TYPE I, 12 INCH	SQ YD	10	10	
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SQ YD	155	155	
44200148	PAVEMENT PATCHING, TYPE III, 12 INCH	SQ YD	20	20	
44200150	PAVEMENT PATCHING, TYPE IV, 12 INCH	SQ YD	147	147	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	291	291	
48202000	BITUMINOUS SHOULDERS SUPERPAVE	TON	416	416	
54200430	PIPE CULVERTS, TYPE 1 RCCP 15"	FOOT	20	20	
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	2	2	
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	3	3	
60600605	CONCRETE CURB, TYPE B	FOOT	37	37	
60605000	CONCRETE CURB & GUTTER, TYPE B-6. 24	FOOT	394	394	
60608600	CONCRETE CURB & GUTTER, TYPE M-6. 06	FOOT	45	45	
60610400	CONCRETE CURB & GUTTER, TYPE M-6. 24	FOOT	164	164	
60618300	CONCRETE MEDIAN SURFACE, 4 IN.	SQ FT	398	398	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	

PLOT DATE = 4/15/2005
 PLOT SCALE = 50.0000 / IN.
 USER NAME = boj

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SUMMARY OF QUANTITIES
NAME	DATE	
		FAP 310 (US 67)/317 (US 24) SECTION (87-1)I-1, TS-2 SCHUYLER COUNTY SCALE: VERT. : NONE HORIZ. : NONE DATE : MARCH 2005
DRAWN BY		CHECKED BY