

CONTRACT NO. 74035				
F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
327	(2,2)IN	LAWRENCE	38	8
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

STATION TO STATION	LENGTH	PROCESSING MODIFIED SOILS 12"	SLAG-MODIFIED PORTLAND CEMENT	SUB-BASE GRANULAR MATERIAL, TYPE C	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	BITUMINOUS SURFACE REMOVAL-BUTT JOINT	TEMPORARY RAMP	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	PAVEMENT REMOVAL	PAVED SHOULDER REMOVAL	AGGREGATE SHOULDERS, TYPE B	AGGREGATE SHOULDERS, TYPE B 6"	BITUMINOUS SHOULDERS SUPERPAVE 6 1/2"	BITUMINOUS BASE COURSE SUPERPAVE 12 1/2"	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N90, 1 1/2"
	LIN FT	SQ YD	TON	TON	GALLON	TON	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	TON	SQ YD	SQ YD	SQ YD	TON
US 50																
STA 349+86.00 TO 355+37.84	551.84	704	7.1	54	226	5	90	15	1565		184	22	307	184	422	190
STA 355+37.84 TO 356+08.70	70.86	659	6.7	32	70	2			213		48	3	19	111	503	59
STA 356+08.70 TO 357+83.80	175.10	731	7.4	46	129	2			467		279		12	158	505	109
STA 357+83.80 TO 359+06.66	122.86	772	7.7	57	100	2			328		130		92	178	513	83
STA 359+06.66 TO 360+42.15	135.49	281	2.9	8	66	1			406		45	6	75	45	211	56
STA 360+42.15 TO 366+02.00	559.85	728	7.3	55	230	5	90	15	1590		187	22	311	187	441	193
BRIDGEPORT ROAD																
STA 11+73.80 TO 13+16.60	142.80				38	1				391					381	32
STA 13+54.60 TO 14+99.90	145.30				39	1				346					387	32
STA 14+99.90 TO 15+19.90	20.00				6	0				48					50	5
TOTALS		3875	39.1	252	904	19	180	30	4569	785	873	53	816	863	3413	759

• INCLUDES QUANTITIES FOR BRIDGEPORT ROAD

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION	
NAME	DATE	<p align="center">PAVING SCHEDULE</p> <p>SCALE: VERT. _____ HORIZ. _____</p> <p>DRAWN BY _____ CHECKED BY _____</p>	

teosleyck
5/9/2005
c:\projects\74035d\02004.psdgn
PVS

PLOT DATE = 5/9/2005
 FILE NAME = #FILE#
 PLOT SCALE = #SCALE#
 REFERENCE = #REF#