teasleuck
4/1/2005
c:\projects\74059d\d03904pa.dgn

SOQ

FAS RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8736	(110) RS-4	JEFFERSON		3
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT NO.		

CONTRACT NO. 74059

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE I000 80% FED. 20% STATE	Y025 STATE/CITY 50%/50%	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1106	864	242	
40600300	AGGREGATE (PRIME COAT)	TON	21	17	4	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		
40600990	TEMPORARY RAMP	SQ YD	59	59		
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	11059	8641	2418	
44201811	CLASS D PATCHES, TYPE I, 14 INCH	SQ YD	21	21		
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	73	73		
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	17	17		
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	3	3		
67100100	MOBILIZATION	L SUM	1	1		
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	550	550		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	92	92		
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	104	104		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1088	1088		
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1176	1176		
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	45	45		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	61	61		
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	930	726	204	

*SPECIALTY ITEMS

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ.
DATE
DRAWN BY
CHECKED BY