

# SUMMARY OF QUANTITIES

MAP ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
600	51RS-3		347	5
STA.		TO STA.		
CONTRACT : 76563				
• ST. CLAIR & MONROE COUNTIES				

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	1000-2A 100% STATE ST. CLAIR COUNTY	1000-2A 100% STATE MONROE COUNTY	X028-2A 100% STATE ST. CLAIR COUNTY	Y007 100% STATE ST. CLAIR COUNTY	<del>Y025 50% STATE 50% VILLAGE ST. CLAIR COUNTY</del>	Y025 50% STATE 50% VILLAGE MONROE COUNTY	SFTY-3N 100% STATE ST. CLAIR COUNTY
M2800400	PERIMETER EROSION BARRIER	METER	2101	2101						
M2810105	STONE RIPRAP, CLASS A3	SQ M	6.1	6.1						
M2810107	STONE RIPRAP, CLASS A4	SQ M	2322	2322						
* * M2810109	STONE RIPRAP, CLASS A5	SQ M	1082	1082						
M2820200	FILTER FABRIC	SQ M	3404	3404						
M3511150	AGGREGATE BASE COURSE, TYPE B 150MM	SQ M	790	678	112					
M3511200	AGGREGATE BASE COURSE, TYPE B 200MM	SQ M	233	194	39					
M4020150	AGGREGATE SURFACE COURSE, TYPE A 150MM	SQ M	1575	1537	38					
M4020200	AGGREGATE SURFACE COURSE, TYPE A 200MM	SQ M	224	224						
M4060200	BITUMINOUS MATERIALS (PRIME COAT)	M TON	29	26	3					
M4060300	AGGREGATE (PRIME COAT)	M TON	122	109.31	12.69					
M4060895	CONSTRUCTING TEST STRIP	EACH	1	1						
M4060980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ M	14	14						
M4060990	TEMPORARY RAMP	SQ M	15	15						
M4080200	BITUMINOUS MATERIALS (PRIME COAT)	M TON	1.7	1.4	0.3					
M4080300	AGGREGATE (PRIME COAT)	M TON	3	2.7	0.3					
M4080400	INCIDENTAL BITUMINOUS SURFACING	M TON	190	162	28					
M4200200	PORTLAND CEMENT CONCRETE PAVEMENT 200MM	SQ M	513	513						
M4230150	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 150MM	SQ M	87	87						
M4230200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 200MM	SQ M	231	231						
M4240100	PORTLAND CEMENT CONCRETE SIDEWALK 100MM	SQ M	3.9	3.9						
M4400020	BITUMINOUS SURFACE REMOVAL 20MM	SQ M	73,171	67,677	5,494					
M4402000	PAVEMENT REMOVAL	SQ M	1217	725	168	173	151			
M4402010	DRIVEWAY PAVEMENT REMOVAL	SQ M	1036	786	250					
M4402020	CURB REMOVAL	METER	27.5	27.5						
M4402030	GUTTER REMOVAL	METER	430	430						
M4402040	COMBINATION CURB AND GUTTER REMOVAL	METER	149	149						
M4402050	SIDEWALK REMOVAL	SQ M	3.9	3.9						
M4402220	BITUMINOUS SHOULDER REMOVAL	SQ M	7609	5267	2342					
M4422350	PAVEMENT PATCHING, TYPE II 350MM	SQ M	509	473	36					
M4423350	PAVEMENT PATCHING, TYPE III 350MM	SQ M	132	113	19					
M4424350	PAVEMENT PATCHING, TYPE IV 350MM	SQ M	495	495						
M4430020	STRIP REFLECTIVE CRACK CONTROL TREATMENT	METER	21842	20202	1640					
M4810150	AGGREGATE SHOULDERS, TYPE A 150MM	SQ M	16785	16316	469					

6/4/2005 8:44:05 AM  
 C:\p\projects\ndf\387\plan\cover.dgn LV1-83

\*\* SFTY-2A 100% STATE ST. CLAIR COUNTY SN 082-0072

△ Rev. 6-7-05