F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2652	00-00069-00-PV	DUPAGE	146	4
STA. 10+70.70		TO STA. 66+16.00		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 83781

FAU RTE 2652 – SOUTH VILLA AVENUE
FROM ROOSEVELT ROAD TO MADISON STREET
SECTION 00-00069-00-PV

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	H23 ROADWAY I000-2A	Q40 SIDEWALK I000-1B	H23 LIGHTING Y030-1E	PARTICIPATING QUANTITIY		O7C NON-PART. QUANTITY Y060
							STP QUANTITY	CMAQ QUANTITY	
55034400	STORM SEWERS, TYPE 1, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 34, RISE 22	FOOT	55	55			55		
55034500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 38, RISE 24	FOOT	60	60			60		
55035600	STORM SEWERS, TYPE 2, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 38, RISE 24	FOOT	362	362			362		
55035700	STORM SEWERS, TYPE 2, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 45, RISE 29	FOOT	442	442			442		
55035800	STORM SEWERS, TYPE 2, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 53, RISE 34	FOOT	485	485			485		
55035900	STORM SEWERS, TYPE 2, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 60, RISE 38	FOOT	734	734			734		
55036000	STORM SEWERS, TYPE 2, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 68, RISE 43	FOOT	170	170			170		
55100200	STORM SEWER REMOVAL 6"	FOOT	10	10			10		
55100300	STORM SEWER REMOVAL 8"	FOOT	935	935			935		
55100400	STORM SEWER REMOVAL 10"	FOOT	404	404			404		
55100500	STORM SEWER REMOVAL 12"	FOOT	644	644			644		
55100700	STORM SEWER REMOVAL 15"	FOOT	41	41			41		
55100900	STORM SEWER REMOVAL 18"	FOOT	49	49			49		
56103000	DUCTILE IRON WATER MAIN 6"	FOOT	45						45
56103200	DUCTILE IRON WATER MAIN 10"	FOOT	2,037						2,037
56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	9	9			9		
56400600	FIRE HYDRANTS	EACH	5						5
60107600	PIPE UNDERDRAINS 4"	FOOT	300	300			300		
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	100	100			100		
60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	2	2			2		
60201110	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 11V FRAME AND GRATE	EACH	99	99			99		
60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	13	13			13		
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	10	10			10		
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	5	5			5		
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	10	10			10		
60224446	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	23	23			23		
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	23	23			23		
60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	1	1			1		
60240312	INLETS, TYPE B, TYPE 11V FRAME AND GRATE	EACH	8	8			8		
60249100	VALVE VAULTS	EACH	7						7
60250200	CATCH BASINS TO BE ADJUSTED	EACH	6	6			6		

PLAN
SURVEYED
PLOTTED
ALIGNMENT CHECKED
GRADES CHECKED
AS-BUILT CHECKED
CADD FILE NAME
NOTE BOOK
NO.
BY
DATE

PROFILE
SURVEYED
PLOTTED
GRADES CHECKED
AS-BUILT CHECKED
STRUCTURE NO(TAT)NG CHKD
NOTE BOOK
NO.
BY
DATE

Stanley Consultants INC.
850 West Higgins Road
Suite 730
Chicago, Illinois 60630-2801 Illinois Firm Registration No: 184-00633

REVISIONS NAME	DATE

VILLAGE OF VILLA PARK, ILLINOIS

SOUTH VILLA AVENUE
SUMMARY OF QUANTITIES
SHEET 2 OF 5

SCALE: NONE
DATE: 11-NOV-2004
DRAWN BY: E.D.
CHECKED BY: J.T.G.