

SUMMARY OF QUANTITIES

F.A.P. ROUTE	COUNTY SECTION	COUNTY	TOTALS SHTS.
336	99-00243-00-PV	KANE	268
CONTRACT NO. 83782			
SUMMARY OF QUANTITIES			
F.H.W.A. REG.5 ILLINOIS PROJECT F-0336(0)			

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE													
				J000-2A ROADWAY STA	J000-2A ROADWAY STU	Y003-TEA LANDSCAPING STU	Y003-TEA LANDSCAPING CITY NON-PART.	Y030-1E LIGHTING STU	Y030-1E LIGHTING CITY NON-PART.	Y031-1F SIGNALS DEAN STREET STU (1)	Y031-1F SIGNALS IL ROUTE 64 STU (2)	Y031-1F SIGNALS INTERCONNECT STU (3)	Y045-BTPW.TEA UNDERPASS STU	Y060 SANITARY CITY NON-PART (1)	Y060 WATER MAIN CITY NON-PART (2)		
Z0013825	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	1,000		1,000												
Z0019600	DUST CONTROL WATERING	UNIT	400		400												
Z0022800	FENCE REMOVAL	FOOT	50		50												
Z0030280	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	4		4												
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	3		3												
Z0048685	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1		1												
* Z0056600	SANITARY SEWER, TYPE 2 8"	FOOT	394														394
* Z0060800	SANITARY SEWER, TYPE 3 6"	FOOT	164														164
* Z0060900	SANITARY SEWER, TYPE 3 8"	FOOT	204														204
Δ Z0076600	TRAINEES	HOUR	3,000		3,000												
	STABILIZED BICYCLE PATH	SQ YD	670		670												
XX006095	HIGH-EARLY-STRENGTH PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	3,609		3,609												
* XX006055	BITUMINOUS SURFACE REMOVAL FOR RECESSED PAVEMENT MARKING, 0.025 INCH DEPTH	SQ FT	10,184		10,184												
* XX006056	CONCRETE SURFACE REMOVAL FOR RECESSED PAVEMENT MARKING, 0.025 INCH DEPTH	SQ FT	6,693		6,693												
* XX006056	RECESSED REFLECTIVE PAVEMENT MARKER	EACH	727		727												
* XX006057	STEEL CASING PIPE 18"	FOOT	125														125
* XX006058	STEEL CASING PIPE 20"	FOOT	368														368
* XX006059	STEEL CASING PIPE AUGURED AND JACKED 18"	FOOT	60														60
* XX006060	STEEL CASING PIPE AUGURED AND JACKED 20"	FOOT	632														632
* XX006061	STEEL CASING PIPE AUGURED AND JACKED 24"	FOOT	250														250
* XX006062	STEEL CASING PIPE AUGURED AND JACKED 30"	FOOT	25														25
* XX006063	DUCTILE IRON RAW WATER DISTRIBUTION MAIN 6"	FOOT	10														10
* XX006064	DUCTILE IRON RAW WATER DISTRIBUTION MAIN 12"	FOOT	2,756														2,756
* XX006065	CURB STOP & BOX 1 1/2 INCHES	EACH	1														1
* XX006066	LIGHT POLE, ALUMINUM, 40 FT. M.H., 15 FT. MAST ARM WITH FESTOON OUTLET	EACH	8					8									
* XX006067	UNDERPASS CONTROL INSTALLATION, SPECIAL	EACH	1														1
* XX006068	MAINTAIN EXISTING TRAFFIC SIGNAL INTERCONNECT	L SUM	1														1
* XX006069	ELECTRIC CABLE IN CONDUIT, COMMUNICATION NO. 16, 5 1/2 PAIR	FOOT	2,260							1,120	1,140						
* XX006070	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 34 FT. WITH 15 FT. LIGHTING ARM AT 40 FT. MOUN HEIGHT	EACH	1														1
* XX006071	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 38 FT. WITH 15 FT. LIGHTING ARM AT 40 FT. MOUN HEIGHT	EACH	1														1
* XX006072	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 44 FT. WITH 15 FT. LIGHTING ARM AT 40 FT. MOUN HEIGHT	EACH	2														2
* XX006073	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 48 FT. WITH DUAL 15 FT. LIGHTING ARM AT 45 FT. MOUNTING HEIGHT	EACH	1														1
* XX006074	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 60 FT. WITH DUAL 15 FT. LIGHTING ARM AT 45 FT. MOUNTING HEIGHT	EACH	1														1
* XX006075	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 55 FT. WITH DUAL 15 FT. LIGHTING ARM AT 45 FT. MOUNTING HEIGHT	EACH	2														2
* XX006076	VIDEO DETECTION SYSTEM (COMPLETE INTERSECTION)	EACH	2														2
* XX006077	REMOTE CONTROLLED VIDEO SYSTEM	EACH	1														1
* XX006078	STORM SEWERS, CLASS A, PRESSURE PIPE, TYPE 3 80"	FOOT	418		418												
* XX006079	TEMPORARY SEDIMENT TRAP	EACH	1		1												
* XX006080	STORM SEWERS, PVC, TYPE 1 6"	FOOT	20		20												
* XX006081	STORM SEWERS, PVC, TYPE 1 8"	FOOT	35		35												
* XX006082	PERIMETER EROSION BARRIER WITH WIRE SUPPORT	FOOT	367		367												
* XX006083	STORM SEWERS, DUCTILE IRON, TYPE 1 10"	FOOT	9		9												
* XX006084	STORM SEWERS, DUCTILE IRON, TYPE 1 12"	FOOT	170		170												
* XX006085	STORM SEWERS, DUCTILE IRON, TYPE 2 12"	FOOT	168		168												
* XX006086	STORM SEWERS, DUCTILE IRON, TYPE 2 18"	FOOT	122		122												
* XX006087	PERIMETER EROSION BARRIER (SPECIAL)	FOOT	2,395		2,395												
* XX006088	SPLIT FLOW JUNCTION STRUCTURE	EACH	1		1												
* XX006089	PERFORATED RISER	L SUM	1		1												
* XX006090	DRAINAGE STRUCTURES, TYPE 3 (MODIFIED)	EACH	1		1												
* XX006091	FRAMES AND GRATES, SPECIAL (SPL1)	EACH	3		3												
* XX006092	MANHOLES, TYPE A, 7-DIAMETER	EACH	14		14												
* XX006093	FRAMES AND GRATES, SPECIAL	EACH	2		2												
* XX006094	FRAXINUS AMERICANA 'AUTUMN APPLAUSE' (AUTUMN APPLAUSE WHITE ASH)	EACH	6														6
* XX006095	GINKGO BILOBA 'AUTUMN GOLD' (AUTUMN GOLD MAIDENHAIR TREE)	EACH	1														1
* XX006096	QUERCUS BICOLOR (SWAMP WHITE OAK)	EACH	4														4
* XX006097	QUERCUS ROBUR (ENGLISH OAK)	EACH	4														4

Revised 6-8-05
 CODE NO. SEQUENCE

* SPECIALTY ITEM