

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	URBAN			CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	URBAN			FED. ROAD DIST. NO. 1	ILLINOIS	HIGHWAY PROJECT	CONTRACT #	837B3
				ROADWAY	BRIDGE	LIGHTING					ROADWAY	BRIDGE	LIGHTING					
				80% FEDERAL 20% LOCAL 1000-2A	80% FEDERAL 20% LOCAL X080-2A	80% FEDERAL 20% LOCAL Y030-1E				80% FEDERAL 20% LOCAL 1000-2A	80% FEDERAL 20% LOCAL X080-2A	80% FEDERAL 20% LOCAL Y030-1E						
20101000	TEMPORARY FENCE	FOOT	430	430	-	-	55100400	STORM SEWER REMOVAL 10"	FOOT	20	20	-	-					
* 20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	48	48	-	-	55100500	STORM SEWER REMOVAL 12"	FOOT	89	89	-	-					
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	2,053	2,053	-	-	55100900	STORM SEWER REMOVAL 18"	FOOT	18	18	-	-					
20400800	FURNISHED EXCAVATION	CU YD	99	99	-	-	55101200	STORM SEWER REMOVAL 24"	FOOT	468	468	-	-					
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	909	909	-	-	△ 56103000	DUCTILE IRON WATER MAIN 6"	FOOT	77	77	-	-					
20800150	TRENCH BACKFILL	CU YD	334	334	-	-	△ 56103100	DUCTILE IRON WATER MAIN 8"	FOOT	412	412	-	-					
20900110	POROUS GRANULAR BACKFILL	CU YD	106	-	106	-	56103400	DUCTILE IRON WATER MAIN 16"	FOOT	23	23	-	-					
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	3,100	3,100	-	-	△ 56104900	WATER VALVES 6"	EACH	4	4	-	-					
* 21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	1,113	1,113	-	-	△ 56105000	WATER VALVES 8"	EACH	2	2	-	-					
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	21	21	-	-	56105300	WATER VALVES 16"	EACH	5	5	-	-					
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	21	21	-	-	△ 56200700	WATER SERVICE LINE 2"	FOOT	125	125	-	-					
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	21	21	-	-	△ 56201800	CORPORATION STOPS 2"	EACH	5	5	-	-					
* 25200110	SODDING, SALT TOLERANT	SQ YD	1,113	1,113	-	-	△ 56400500	FIRE HYDRANTS TO BE REMOVED	EACH	2	2	-	-					
28000400	PERIMETER EROSION BARRIER	FOOT	265	265	-	-	△ 56400820	FIRE HYDRANTS WITH AUXILIARY VALVE AND VALVE BOX	EACH	3	3	-	-					
28000500	INLET AND PIPE PROTECTION	EACH	11	11	-	-	58700200	BRIDGE SEAT SEALER	SQ FT	346	-	346	-					
28000510	INLET FILTERS	EACH	11	11	-	-	59000100	EPOXY CRACK SEALING	FOOT	107	-	107	-					
28100105	STONE RIP RAP, CLASS A3	SQ YD	33	-	33	-	59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	39	-	39	-					
28200200	FILTER FABRIC	SQ YD	33	-	33	-	60100915	PIPE DRAINS, 6"	FOOT	196	-	196	-					
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	2,739	2,739	-	-	60201105	CATCH BASINS, TYPE A, 4'-DIA, TYPE 11 FRAME AND GRATE	EACH	4	4	-	-					
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	274	274	-	-	60207905	CATCH BASINS, TYPE C, 2'-DIA, TYPE 11 FRAME AND GRATE	EACH	3	3	-	-					
40600300	AGGREGATE (PRIME COAT)	TON	4	4	-	-	60218400	MANHOLES, TYPE A, 4'-DIA, TYPE 1 FRAME, CLOSED LID	EACH	1	1	-	-					
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	207	207	-	-	60221100	MANHOLES, TYPE A, 5'-DIA, TYPE 1 FRAME, CLOSED LID	EACH	6	6	-	-					
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	42	42	-	-	60236800	INLETS, TYPE A, TYPE 11 FRAME AND GRATE	EACH	4	4	-	-					
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	364	364	-	-	△ 60248700	VALVE VAULTS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	8	8	-	-					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	11,762	11,762	-	-	△ 60248900	VALVE VAULTS, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4	4	-	-					
44000100	PAVEMENT REMOVAL	SQ YD	3,753	3,753	-	-	60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1	-	-					
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	193	193	-	-	△ 60265900	VALVE VAULTS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	6	6	-	-					
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	567	567	-	-	△ 60266300	VALVE VAULTS TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1	-	-					
44000600	SIDEWALK REMOVAL	SQ FT	6,065	6,065	-	-	△ 60266500	VALVE VAULTS TO BE REMOVED	EACH	4	4	-	-					
44200108	PAVEMENT PATCHING, TYPE II, 9 INCH	SQ YD	30	30	-	-	60500040	REMOVING MANHOLES	EACH	3	3	-	-					
50101600	REMOVAL OF EXISTING SUPERSTRUCTURES	L SUM	1	-	1	-	60500060	REMOVING INLETS	EACH	10	10	-	-					
50102400	CONCRETE REMOVAL	CU YD	94.7	-	94.7	-	60600605	CONCRETE CURB, TYPE B	FOOT	134	134	-	-					
50200100	STRUCTURE EXCAVATION	CU YD	204	-	204	-	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	1,858	1,858	-	-					
50300120	PREFORMED JOINT SEAL 2 1/2"	FOOT	96	-	96	-	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	15	15	-	-					
50300225	CONCRETE STRUCTURES	CU YD	199.7	-	199.7	-	72000100	SIGN PANEL - TYPE 1	SQ FT	45	45	-	-					
50300255	CONCRETE SUPERSTRUCTURE	CU YD	53.6	-	53.6	-	72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	6	6	-	-					
50300260	BRIDGE DECK GROOVING	SQ YD	618	-	618	-	72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	1	1	-	-					
50300300	PROTECTIVE COAT	SQ YD	237	-	237	-	72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	4	4	-	-					
50301245	FORMED CONCRETE REPAIR (<= 5" DEPTH)	SQ FT	7	-	7	-												
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ FT	7,687	-	7,687	-												
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	64,100	-	64,100	-												
51500100	NAME PLATES	EACH	1	-	1	-												
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	1	1	-	-												
54247150	GRATING FOR CONCRETE FLARED END SECTION 30"	EACH	1	1	-	-												
550A2320	STORM SEWER, RUBBER GASKET, CLASS A, TYPE 1, 12"	FOOT	53	53	-	-												
550A2330	STORM SEWER, RUBBER GASKET, CLASS A, TYPE 1, 15"	FOOT	12	12	-	-												
550A2340	STORM SEWER, RUBBER GASKET, CLASS A, TYPE 1, 18"	FOOT	18	18	-	-												
550A2380	STORM SEWER, RUBBER GASKET, CLASS A, TYPE 1, 30"	FOOT	295	295	-	-												
550A2520	STORM SEWER, RUBBER GASKET, CLASS A, TYPE 2, 12"	FOOT	124	124	-	-												
550A2570	STORM SEWER, RUBBER GASKET, CLASS A, TYPE 2, 27"	FOOT	160	160	-	-												
55100300	STORM SEWER REMOVAL 8"	FOOT	68	68	-	-												

PLOT FILE: STANDARD
 USER: CLE-J
 COMP: FILE: 0401271.dwg

* SPECIALTY ITEM
 △ NON-PARTICIPATING ITEM - 100% LOCAL

REVISIONS	
NO.	DATE
7.	
6.	
5.	
4.	
3.	
2.	
1.	TEH 4-11-05

SMITH ENGINEERING CONSULTANTS, INC.
 CIVIL/STRUCTURAL ENGINEERS AND SURVEYORS
 4500 PRIME PARKWAY, SUITE 201
 McHENRY, ILLINOIS 60050
 PH: 815-385-1778 FAX: 815-385-1781
 www.smithengineering.com E-MAIL: seo@smithengineering.com
 McHENRY HUNTLEY YORKVILLE
 ILLINOIS PROFESSIONAL DESIGN FIRM # 184-000108

ILLINOIS DEPARTMENT OF TRANSPORTATION
 VILLAGE OF CARPENTERSVILLE
 MAIN STREET OVER THE FOX RIVER
 SUMMARY OF QUANTITIES
 SCALE: "NTS"
 DATE 02-25-2005
 DRAWN BY WJH
 CHECKED BY TEH