June 1, 2005

SUBJECT: FAU Route 2670

Project M-8003(442)

Section 03-00095-00-RS (Libertyville)

Lake County

Contract No. 83784

Item 107A

June 17, 2005 Letting

TO PROSPECTIVE BIDDERS:

To clarify information it is necessary to revise the following:

SPECIAL PROVISIONS – PAGE 1, PROJECT COMPLETION DATE HAS BEEN REVISED FROM OCTOBER 14, 2005 PLUS 10 WORKING DAYS TO MAY 31, 2006 PLUS 10 WORKING DAYS.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal. Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Since the proposal sheets are printed back to back, bidders are cautioned to exercise care when inserting revised and/or added special provisions into their proposals.

Please call 217-782-7806 if any of the above-described material is not included in this transmittal.

Very truly yours,

Michael L. Hine Engineer of Design and Environment

By: Ted B. Walschleger, P. E.

Tette Valuebye BE.

Engineer of Project Management

SPECIAL PROVISIONS FOR VILLAGE OF LIBERTYVILLE FOURTH AVENEUE REHABILITATION

The following Special Provisions supplement the "Standard Specifications for Road and Bridge Construction," adopted January 1, 2002, (hereinafter referred to as the Standard Specifications); the "Manual on Uniform Traffic Control Devices for Streets and Highways", the Manual of Test Procedures of Materials in effect on the date of invitation for bids; and the "Supplemental Specifications and Recurring Special Provisions"; adopted March 1, 2005; the Standard Specifications for Water & Sewer Main Construction in Illinois. In case of conflict with any part or parts of said specifications, the said Special Provisions shall take precedence and shall govern.

LOCATION OF PROJECT

The work on Fourth Avenue begins at the north edge of pavement of Valley Park Drive and extends northerly for a distance of 3,224 feet to 225 feet south of East Park Avenue (Illinois Route 176).

DESCRIPTION OF IMPROVEMENT

The work included in this Contract shall consist of furnishing all the materials, labor, equipment and incidentals required for drainage structures; storm sewers; pavement removal, bituminous surface removal; curb and gutter; driveway removal and replacement; full-depth bituminous pavement; bituminous resurfacing; adjustment of drainage structures; restoration and all other incidental work necessary to complete this improvement according the Plans, Standard Specifications and Special Provisions.

PROJECT COMPLETION DATE

The completion date for all work shall be 11:59 pm on May 31, 2006

The Contractor will be allowed to complete all clean-up work and punch list items within 10 guaranteed working days after May 31, 2,006. Under extenuating circumstances the Engineer may direct that certain items of work, not affecting the safe opening of the roadway to traffic, may be completed within the guaranteed working days allowed for clean up work and punch list items. Temporary lane closures for this work may be allowed at the discretion of the Engineer.

Article 108.09 of the Standard Specifications or the Special Provision for Failure to Complete the Work on Time, if included in this contract, shall apply to both the completion date and the number of working days.

* Revised 6-1-05