

**GENERAL NOTES:**

- THE CONTRACTOR SHALL MAINTAIN ALL ROADWAYS OPEN TO TRAFFIC AS SHOWN PER THE MAINTENANCE OF TRAFFIC DETAILS.
- BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL J.U.L.I.E. AT (800) 892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE, CABLE, AND GAS FACILITIES (48 HOURS NOTIFICATION IS REQUIRED). CONTACT VILLAGE ENGINEER, VILLAGE OF LAKE BLUFF AT (847) 234-0774 FOR WATER, SEWER AND VILLAGE ELECTRIC LOCATIONS.
- THE CONTRACTOR SHALL NOT BE ALLOWED TO ERECT A YARD OR FIELD OFFICE ON VILLAGE RIGHT-OF-WAY OR PROPERTY WITHOUT WRITTEN PERMISSION FROM THE VILLAGE.
- THE ENGINEER SHALL BE THE SOLE JUDGE CONCERNING THE PROPER CURING TIME FOR THE VARIOUS BITUMINOUS LIFTS.
- ALL ELEVATIONS REFER TO U.S.G.S. MEAN SEA LEVEL DATUM 1929.
- NO WORK SHALL COMMENCE UNTIL TRAFFIC CONTROL REQUIREMENTS AND EROSION CONTROL MEASURES ARE MET.
- ALL UTILITIES, SCHOOL DISTRICTS, PARK DISTRICT, LOCAL POLICE, AND FIRE DEPARTMENTS SHALL BE NOTIFIED BY THE CONTRACTOR PRIOR TO THE START OF CONSTRUCTION.
- UNLESS AUTHORIZED BY THE ENGINEER, ALL EXISTING ACCESS POINTS SHALL BE MAINTAINED AT ALL TIMES BY THE CONTRACTOR.
- BOXED ITEMS ARE INCLUDED IN THIS CONTRACT AND SHALL NOT BE PAID FOR SEPARATELY UNDER ANY ITEM OF WORK.
- TREES NOT MARKED FOR REMOVAL SHALL BE CONSIDERED AS DESIGNATED TO BE SAVED AND SHALL BE PROTECTED UNDER THE PROVISIONS OF ARTICLE 201.05 OF THE STANDARD SPECIFICATIONS.
- ALL LIMBS, BRANCHES, AND OTHER DEBRIS RESULTING FROM THIS WORK SHALL BE DISPOSED OF BY THE CONTRACTOR AT HIS OWN EXPENSE OUTSIDE THE LIMITS OF THE RIGHT-OF-WAY.
- ALL CLEARING, REMOVAL OF BUSHES, HEDGES AND TREES UNDER SIX (6) INCHES IN DIAMETER WILL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR EARTH EXCAVATION.
- DURING THE CONSTRUCTION, THE CONTRACTOR WILL BE REQUIRED, AT HIS EXPENSE, TO HAVE AVAILABLE A WATER TRUCK OR SIMILAR EQUIPMENT TO CONTROL DUST. IF NECESSARY, THE CONTRACTOR SHALL BE REQUIRED TO CONTROL DUST DURING NON-WORKING HOURS.
- THE CONTRACTOR MUST MAKE PRIOR ARRANGEMENTS WITH THE VILLAGE OF LAKE BLUFF WATER DEPARTMENT PRIOR TO THE USE OF ANY FIRE HYDRANT. HYDRANT METERS AND RPZ'S MUST BE USED. CONTACT THE ENGINEERING DEPARTMENT AT (847) 234-0774.
- ALL OPEN EXCAVATIONS MUST BE ADEQUATELY COVERED (STEEL PLATED) OR FILLED IN AT THE END OF EACH DAY. NO OPEN EXCAVATIONS ARE ALLOWED OVERNIGHT. THE COST OF THIS WORK SHALL BE INCLUDED IN THE COST OF THE ITEM REQUIRING EXCAVATION.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REMOVAL AND CLEAN UP OF MUD AND OTHER DEBRIS TRACKED ON ALL STREETS LEADING TO THE PROJECT SITE CAUSED BY THE CONSTRUCTION OPERATIONS. THE CLEAN UP IS AT THE DISCRETION OF AND MUST BE DONE TO THE SATISFACTION OF THE VILLAGE ENGINEER.
- WORKING HOURS. THE CONTRACTOR SHALL OBSERVE WORKING HOURS PER VILLAGE ORDINANCES:
  - 7 AM TO 7 PM MONDAY TO FRIDAY
  - 8 AM TO 5 PM SATURDAY
  - NO WORK SUNDAYS OR NATIONAL HOLIDAYS

PER VILLAGE CODE NO WORK BEFORE 7 AM INCLUDES NO STARTUP, ENGINE WARMUP OR IDLE, GENERATOR OR COMPRESSOR RUNNING OR ANY OTHER ACTIVITY. THIS ORDINANCE WILL BE STRICTLY ENFORCED BY THE VILLAGE.
- STARTING DATE: UNDER NO CIRCUMSTANCES WILL THE CONTRACTOR BE ALLOWED ACCESS TO THE SITE PRIOR TO JULY 5, 2005. THIS INCLUDES NO SITE PREPARATION, TEMPORARY FENCING, FIELD OFFICES, TRAILERS, ETC.

**INDEX OF STATE STANDARDS**


STD. NO.	TITLE
000001-04	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
280001-02	TEMPORARY EROSION CONTROL SYSTEM
420401-05	BRIDGE APPROACH PAVEMENT
424001-03	CURB RAMPS FOR SIDEWALKS
515001-02	NAME PLATE FOR BRIDGES
601101-00	CONCRETE HEADWALL FOR PIPE DRAIN
602001-00	CATCH BASIN, TYPE A
602401-00	MANHOLE, TYPE A
602701-00	CAST IRON STEPS
604001-02	FRAME AND LIDS, TYPE 1
604036-01	GRATE, TYPE 8
604051-01	FRAME AND GRATE, TYPE 11
606001-02	CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER
701801-03	LANE CLOSURE MULTILANE 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE
702001-05	TRAFFIC CONTROL DEVICES
704001-02	TEMPORARY CONCRETE BARRIER
720001-00	SIGN PANEL MOUNTING DETAILS
720006-00	SIGN PANEL ERECTION DETAILS
720011-00	METAL POSTS FOR SIGNS, MARKERS & DELINEATORS
729001-00	APPLICATION OF TYPE A AND TYPE B METAL POSTS
BLR-21-6	TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES FOR CONSTRUCTION ON RURAL LOCAL HIGHWAYS

**INDEX OF SHEETS**

SHEET NO.	SHEET TITLE
1	COVER SHEET
2	GENERAL NOTES, STATE STANDARDS AND INDEX OF SHEETS
3	SUMMARY OF QUANTITIES
4	EXISTING AND PROPOSED TYPICAL SECTIONS
5	MAINTENANCE OF TRAFFIC, DETOUR PLAN
6	REMOVAL PLAN AND DETAILS
7	PROPOSED PLAN AND PROFILE
8	PROPOSED DRAINAGE PLAN AND PROFILE
9	EROSION CONTROL PLAN/LANDSCAPING PLAN
10	CONCRETE HEADWALL SPECIAL DETAIL
11- 40	STRUCTURAL PLANS

DATE	BY	SURVEYED	ALIGNED	CHECKED
PLAN	NOTE BOOK	NO.	NO.	NO.

DATE	BY	SURVEYED	ALIGNED	CHECKED
PROFILE	NOTE BOOK	NO.	NO.	NO.

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION	MOFFETT ROAD BRIDGE OVER DRAINAGE RAVINE
NAME	DATE		
		 <p>GENERAL NOTES, STATE STANDARDS AND INDEX OF SHEETS</p>	<p>SCALE: NONE</p> <p>DATE: 02-02-05</p>
DRAWN BY: BK		CHECKED BY: DAJ	