

SUMMARY OF QUANTITIES

F.P. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
345	00-00086-00-1L	DUPAGE	58	4
SUMMARY OF QUANTITIES				
FED. ROAD DISTRICT			ILLINOIS	
			FED. AID PROJECT	
CONTRACT NO. 83794				

ITEM NUMBER	CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	U.S. ROUTE 20 (LAKE STREET) AND SWIFT ROAD					
					J000-2R	Y003	SFTY-1D	Y030-1E	Y031-1F	
					ROADWAY	LAND-SCAPING	PAVEMENT MARKING	HIGHWAY ILLUMINATION	TRAFFIC CONTROL SIGNALS	
1	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	36	36					
2	20101000	TEMPORARY FENCE	FOOT	600	600					
3	20200100	EARTH EXCAVATION	CU YD	2,196	2,196					
4	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	200	200					
5	20400800	FURNISHED EXCAVATION	CU YD	311	311					
6	20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	200	200					
7	20800150	TRENCH BACKFILL	CU YD	200	200					
8	21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	600	600					
* 9	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	3,377		3,377				
* 10	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	42		42				
* 11	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	42		42				
* 12	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	42		42				
* 13	25200110	SODDING, SALT TOLERANT	SQ YD	3,377		3,377				
14	25200200	SUPPLEMENTAL WATERING	UNIT	10	10					
* 15	25300600	TRANSPLANTED SALVAGED TREES	EACH	27		27				
16	28000400	PERIMETER EROSION BARRIER	FOOT	1,898	1,898					
17	28000500	INLET AND PIPE PROTECTION	EACH	7	7					
18	28000510	INLET FILTERS	EACH	20	20					
19	28100105	STONE RIPRAP, CLASS A3	SQ YD	3	3					
20	28200200	FILTER FABRIC	SQ YD	3	3					
21	31101100	SUB-BASE GRANULAR MATERIAL, TYPE B	CU YD	81	81					
22	31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	1,221	1,221					
23	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	1,026	1,026					
24	40600300	AGGREGATE (PRIME COAT)	TON	11	11					
25	40600400	MIXTURE FOR CRACKS, JOINTS AND FLANGWAYS	TON	1	1					
26	40600980	BITUMINOUS SURFACE REMOVAL, BUTT JOINT	SQ YD	75	75					
27	42000511	PORTLAND CEMENT CONCRETE PAVEMENT 10 1/2" (JOINTED)	SQ YD	1,919	1,919					
28	42001300	PROTECTIVE COAT	SQ YD	1,177	1,177					
29	42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8"	SQ YD	101	101					
30	44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	4,721	4,721					
31	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	199	199					
32	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	3,252	3,252					
33	44201796	CLASS D PATCHES, TYPE IV, 12"	SQ YD	33	33					
34	44300900	STRIP REFLECTIVE CRACK CONTROL TREATMENT, SYSTEM A	FOOT	733	733					
35	50800205	REINFORCING BARS, EPOXY COATED	POUND	2,239	2,239					
36	54213680	PRECAST REINFORCED CONCRETE END SECTIONS, 15"	EACH	2	2					
37	54247100	GRATING FOR CONCRETE FLARED END SECTION, 15"	EACH	2	2					
38	550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	926	926					
39	550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	65	65					
40	550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	1	1					
41	550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	13	13					
42	550A0480	STORM SEWERS, CLASS A, TYPE 2 48"	FOOT	125	125					

ITEM NUMBER	CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	U.S. ROUTE 20 (LAKE STREET) AND SWIFT ROAD					
					J000-2R	Y003	SFTY-1D	Y030-1E	Y031-1F	
					ROADWAY	LAND-SCAPING	PAVEMENT MARKING	HIGHWAY ILLUMINATION	TRAFFIC CONTROL SIGNALS	
43	55100200	STORM SEWER REMOVAL, 6"	FOOT	275	275					
44	55100500	STORM SEWER REMOVAL, 12"	FOOT	170	170					
45	60100915	PIPE DRAINS 6"	FOOT	12	12					
46	60109510	PIPE UNDERDRAIN, FABRIC LINED TRENCH, 4"	FOOT	120	120					
47	60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	6	6					
48	60208230	CATCH BASINS, TYPE C, TYPE 23 FRAME AND GRATE	EACH	1	1					
49	60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	EACH	4	4					
50	60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2					
51	60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1					
52	60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3					
53	60236200	INLETS, TYPE A, TYPE B GRATE	EACH	1	1					
54	60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	4	4					
55	60300105	FRAME AND GRATES TO BE ADJUSTED	EACH	16	16					
56	60404940	FRAME AND GRATES, TYPE 23	EACH	1	1					
57	60404950	FRAME AND GRATES, TYPE 24	EACH	1	1					
58	60406100	FRAME AND LIDS, TYPE 1, CLOSED LID	EACH	6	6					
59	60500040	REMOVING MANHOLES	EACH	2	2					
60	60500050	REMOVING CATCH BASINS	EACH	7	7					
61	60500060	REMOVING INLETS	EACH	3	3					
62	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	1,054	1,054					
63	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	2,212	2,212					
64	60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	967	967					
65	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3					
66	67100100	MOBILIZATION	L SUM	1	1					
67	70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	1					
68	70300100	SHORT TERM PAVEMENT MARKING	FOOT	4,614	4,614					
* 69	70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	125			125			
* 70	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	6,628			6,628			
* 71	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	500			500			
* 72	70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	73			73			
* 73	70300520	PAVEMENT MARKING TAPE, TYPE III, 4"	FOOT	385			385			
* 74	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3,411			3,411			
75	72000100	SIGN PANEL - TYPE 1	SQ FT	8	8					
76	72000200	SIGN PANEL - TYPE 2	SQ FT	10	10					
77	72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	8	8					
78	72400600	RELOCATE SIGN PANEL ASSEMBLY-TYPE B	EACH	1	1					
* 79	72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	39						39

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

VILLAGE OF ADDISON
SUMMARY OF QUANTITIES
LAKE STREET/SWIFT ROAD

DATE: 4/01/05
DESIGNED BY: S.J.C.
CHECKED BY: D.W.B.

