

SCHEDULES OF QUANTITIES

P&E SHEET	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
345	00-00086-00-TL	DUPAGE	58	6
SUMMARY OF QUANTITIES				
FED. ROAD DISTRICT		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 83794				

SCHEDULE OF CURB AND GUTTER			
STATION		CONC. C&G	
FROM	TO	TYPE B-6.12 (FT.)	TYPE B-6.24 (FT.)
LAKE STREET			
122+02	123+00	98	
123+00	124+00	100	54
124+00	125+00	100	100
125+00	126+00	100	100
126+00	127+00	100	100
127+00	128+00	10	100
128+00	129+00		100
129+00	130+00		119
130+00	131+00		54
131+00	132+00		17
132+00	133+00		
133+00	134+00	84	
134+00	135+00	100	
135+00	136+00	100	
136+00	137+00	101	
137+00	138+00	101	
138+00	138+25	25	
SUBTOTAL LAKE STREET		1,019	744
SWIFT ROAD			
791+50	792+00		101
792+00	793+00		200
793+00	794+00		200
794+00	795+00		200
795+00	796+00	35	200
796+00	797+00		200
797+00	798+00		201
798+00	798+82.9		166
SUBTOTAL SWIFT ROAD		35	1,468
TOTAL		1,054	2,212

SCHEDULE OF CLASS D PATCHES		
STATION		CLASS D PATCHES
FROM	TO	TYPE IV, 12" (SY)
SWIFT ROAD		
796+01	796+07	33
TOTAL		33

SCHEDULE OF TREE RELOCATION	
INITIAL LOCATION	
STATION	OFFSET (FT.)
LAKE STREET	
123+20	14 RT.
123+64	14 RT.
124+28	13 RT.
124+60	13 RT.
124+92	13 RT.
125+23	11 RT.
125+64	9 RT.
126+12	8 RT.
126+36	7 RT.
134+68	11 RT.
134+78	16 RT.
134+87	9 RT.
134+97	15 RT.
135+07	8 RT.
135+18	14 RT.
135+28	5 RT.
135+37	14 RT.
135+47	4 RT.
135+57	14 RT.
135+67	5 RT.
135+77	13 RT.
135+87	4 RT.
136+22	13 RT.
136+40	4 RT.
136+57	12 RT.
136+75	4 RT.
137+47	7 RT.
TOTAL = 27 EA	

SCHEDULE OF TREE REMOVAL		
STATION		OVER 15 UNITS
STATION	OFFSET (FT.)	DIAMETER
SWIFT RD.		
793+01	38 RT.	36
TOTAL = 36 UNITS		

REVISIONS	
NAME	DATE

VILLAGE OF ADDISON

SCHEDULES OF QUANTITIES

LAKE STREET/SWIFT ROAD

DATE: 4/01/05
DESIGNED BY: S.J.C.
CHECKED BY: D.W.B.

