

ITEM#	IDOT PAY ITEM CODE#	PAY ITEM	UNIT	TOTAL QUANTITY	HRRP		VILLAGE SPONSORED NON-PARTICIPATING
					Bridge Approaches X281-2A	Bridge Rehabilitation X281	
1	42001165	BRIDGE APPROACH PAVEMENT	SQ YD	482	482		
2	44000700	APPROACH SLAB REMOVAL	SQ YD	413	413		
3	44001000	BITUMINOUS CONCRETE SURFACE REMOVAL	SQ YD	861		861	
4	50102400	CONCRETE REMOVAL	CU YD	90.3		90.3	
5	50104000	BRIDGE RAIL REMOVAL	FOOT	251			
6	50104720	REMOVAL OF EXISTING CONCRETE DECK	EACH	1			
7	50300120	PREFORMED JOINT SEAL 2-1/2"	FOOT	170.0		170.0	
8	50300225	CONCRETE STRUCTURES	CU YD	24.0	16.7	7.3	
9	50300255	CONCRETE SUPERSTRUCTURE	CU YD	365.0	9.7	355.3	
10	50300260	BRIDGE DECK GROOVING	SQ YD	1682		1682	
11	50300300	PROTECTIVE COAT	SQ YD	2930	505	2425	
12	50301245	FORMED CONCRETE REPAIR (DEPTH EQUAL TO OR LESS THAN 5")	SQ FT	17.5		17.5	
13	50301250	FORMED CONCRETE REPAIR (DEPTH GREATER THAN 5")	SQ FT	11.4		11.4	
14	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	74810	3940	70870	
15	50900810	PEDESTRIAN RAILING SPECIAL	FOOT	251			251
16	51500100	NAME PLATES	EACH	1		1	
17	59000100	EPOXY CRACK SEALING	FOOT	13		13	
18	67100100	MOBILIZATION	L SUM	1		1	
19	70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1		1	
20	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3281		3281	
21	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	550		550	
22	70400100	TEMPORARY CONCRETE BARRIER	FOOT	460		460	
23	78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1416		1416	
24	78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	24		24	
25	78200305	PRISMATIC BARRIER REFLECTORS	EACH	20		20	
26	81306100	JUNCTION BOX (SPECIAL)	EACH	4	4		
27	X0322185	BRIDGE DECK LATEX CONCRETE OVERLAY (2-1/4")	SQ YD	861.3		861.3	
28	X0006798	IMPACT ATTENUATOR, TEMPORARY	EACH	1		1	
29	X6700405	ENGINEER'S FIELD OFFICE, TYPE A (MODIFIED)	CAL MO	11		11	
30	Z0001050	AGGREGATE SUBGRADE, 12"	SQ YD	40	40		
31	Z0002600	BAR SPLICERS	EACH	152		152	
32	Z0003800	BEARING REPOSITIONING	EACH	1		1	
33	Z0012100	CONCRETE BRIDGE DECK SCARIFICATION (1/4")	SQ YD	861.3		861.3	
34	Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	49		49	
35	Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	151		151	
36	Z0017900	DRAINAGE SCUPPERS	EACH	2		2	
37	Z0047300	PROTECTIVE SHIELD	SQ YD	1257		1257	
38	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	20		20	
39	40600760	BITUMINOUS CONCRETE BINDER COURSE, MIXTURE B, TYPE 2	TON	17		17	

* INDICATES SPECIALTY ITEM

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
CONCRETE MEDIAN REMOVAL ADDED	5-27-05	<p align="center">SUMMARY OF QUANTITIES</p> <p align="right">DESIGNED BY MTK CHECKED BY RAL</p> <p align="center">DATE 04/14/05</p>