

| | | | | |
|-----------------------|----------|------------------|--------------|-----------|
| F.A.U. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 2585 05-00068-02-BR | | COOK | 30 | 2 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |
| CONTRACT NUMBER 83800 | | | | |

GENERAL NOTES

- BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 1-800-892-0123, ILLINOIS DEPARTMENT OF TRANSPORTATION, THE VILLAGE OF SCHAUMBURG, AND COOK COUNTY FOR FIELD LOCATIONS OF BURIED UTILITIES (48 HOURS NOTIFICATION REQUIRED).
 - THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES, GOVERNMENT AGENCIES, AND ADJACENT MEACHAM ROAD ROADWAY CONTRACTOR. FOR FURTHER INFORMATION REGARDING THE MEACHAM ROADWAY PROJECT, CONTACT THE VILLAGE OF SCHAUMBURG.
 - THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON VILLAGE OR PRIVATE PROPERTY WITHOUT WRITTEN CONSENT FROM THE VILLAGE OR OWNER.
 - WHEN ARTIFICIAL LIGHTING IS UTILIZED IN NIGHT OPERATIONS, THE CONTRACTOR SHALL EXERCISE THE UTMOST PRECAUTIONS PREVENTING ADVERSE VISIBILITY TO THE MOTORING PUBLIC AND ADJOINING RESIDENTIAL AREAS.
 - IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO ORDERING MATERIALS AND BEGINNING CONSTRUCTION.
 - THE CONTRACTOR SHALL PROVIDE AND INSTALL TWO (2) WEIGHTED SAND BAGS ON EACH TYPE I OR II BARRICADE USED, ONE (1) SAND BAG ACROSS EACH BOTTOM RAIL. TYPE III BARRICADES SHALL HAVE FOUR (4) WEIGHTED SANDBAGS.
- SEE SHEET S-2 OF BRIDGE PLANS FOR BRIDGE PLANS GENERAL NOTES.

STATE STANDARDS INCLUDED

- | | |
|-----------|--|
| 000001-04 | STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS |
| 420401-05 | BRIDGE APPROACH PAVEMENT |
| 631026-02 | TRAFFIC BARRIER TERMINAL, TYPE 5 & 5A |
| 631031-05 | TRAFFIC BARRIER TERMINAL, TYPE 6 |
| 635006-02 | REFLECTOR AND TERMINAL MARKER PLACEMENT |
| 635011-01 | REFLECTOR MARKER AND MOUNTING DETAILS |
| 701206-01 | LANE CLOSURE, 2L, 2W, NIGHT ONLY, FOR SPEEDS > 45 MPH |
| 701301-02 | LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS |
| 701321-08 | LANE CLOSURE, 2L, 2W, BRIDGE REPAIR WITH BARRIER |
| 701421-01 | LANE CLOSURE, MULTILANE, DAY OPERATION ONLY, FOR SPEEDS ≥ 45 MPH TO 55 MPH |
| 701423-01 | LANE CLOSURE, MULTILANE, WITH BARRIER, FOR SPEEDS ≥ 45 MPH TO 55 MPH |
| 701601-04 | URBAN LANE CLOSURE, MULTILANE, 1W OR 2W WITH NONTRAVERSABLE MEDIAN |
| 701801-03 | LANE CLOSURE MULTILANE 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE |
| 702001-05 | TRAFFIC CONTROL DEVICES |
| 704001-02 | TEMPORARY CONCRETE BARRIER |
| 780001-01 | TYPICAL PAVEMENT MARKINGS |
| 781001-02 | TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS |

INDEX OF SHEETS

- | | |
|-------|---|
| 1 | COVER SHEET |
| 2 | INDEX OF SHEETS, GENERAL NOTES, STATE STANDARDS, BENCHMARKS |
| 3 | SUMMARY OF QUANTITIES |
| 4 | ALIGNMENT & TIES |
| 5-7 | MAINTENANCE OF TRAFFIC |
| 8 | PAVEMENT MARKING PLANS |
| 9 | TRAFFIC SIGNAL INTERCONNECT AND LIGHTING PLANS |
| 10-30 | BRIDGE PLANS |

BENCHMARKS

BM#1130:
 SET ALUMINUM CAP IN CONCRETE WITH STATION 1130.
 LOCATION: NORTHWEST CORNER LOT 1 IN WINDY POINT OF SCHAUMBURG. (SOUTH OF I-90, EAST OF MEACHAM ROAD, 39.34' NORTH OF NE CORNER OF PUMP HOUSE, 38.75' NORTH OF NW CORNER OF PUMP HOUSE)
 DATA: ILLINOIS EAST STATE PLANE
 NORTHING 1964219.26
 EASTING 1062685.45
 ELEVATION 741.30 (NGVD 1929)

BM#1009:
 2" ALUMINUM CAP GROUTED IN CONCRETE, MARKED "1009"
 LOCATION: APPROXIMATE CENTER OF EXISTING MEDIAN ALONG MEACHAM ROAD, 308.5' NORTH OF EXISTING BRIDGE OVER NORTHWEST TOLLWAY.
 DATA: ILLINOIS EAST STATE PLANE
 NORTHING 1964863.446
 EASTING 1062611.343
 ELEVATION 757.53 (NGVD 1929)

FURTHER BENCHMARK INFORMATION AVAILABLE FROM THE VILLAGE OF SCHAUMBURG.

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION

GENERAL NOTES AND STATE STANDARDS

DESIGNED BY MTK
 CHECKED BY RAL
 DATE 04/14/05