F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2585	05-00068-02-BR	COOK	30	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NUMBER 83800

	ITEM#	IDOT PAY ITEM CODE#	PAY ITEM	UNIT	TOTAL QUANTITY	HBRRP		VILLAGE SPONSORED NON-PARTICIPATING
						Bridge Approaches X281-2A SEQ 1	Bridge Rehabilitation X281-2A SEQ 2	
	1	42001165	BRIDGE APPROACH PAVEMENT	SQ YD	482	482		
*	2	44000700	APPROACH SLAB REMOVAL	SQ YD	413	413		
*	3	44001000	BITUMINOUS CONCRETE SURFACE REMOVAL	SQ YD	1349		1349	
	4	50102400	CONCRETE REMOVAL	CU YD	42.2		42.2	
	5	50104000	BRIDGE RAIL REMOVAL	FOOT	251		251	
	6	50104720	REMOVAL OF EXISTING CONCRETE DECK	EACH	1		1	
	7	50300120	PREFORMED JOINT SEAL 2-1/2"	FOOT	170.0		170.0	
	8	50300225	CONCRETE STRUCTURES	CU YD	24.0	16.7	7.3	
	9	50300255	CONCRETE SUPERSTRUCTURE	CU YD	365.0	9.7	355.3	
	10	50300260	BRIDGE DECK GROOVING	SQ YD	1682		1682	
	11	50300300	PROTECTIVE COAT	SQ YD	2930	505	2425	
	12	50301245	FORMED CONCRETE REPAIR (DEPTH EQUAL TO OR LESS THAN 5")	SQ FT	17.5		17.5	
	13	50301250	FORMED CONCRETE REPAIR (DEPTH GREATER THAN 5")	SQ FT	11.4		11.4	
	14	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	74810	3940	70870	
*	15	50900810	PEDESTRIAN RAILING SPECIAL	FOOT	251			251
	16	51500100	NAME PLATES	EACH	1		1	
	17	59000100	EPOXY CRACK SEALING	FOOT	13		13	
	18	67100100	MOBILIZATION	L SUM	1		1	
	19	70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1		1	
	20	70300500	PAVEMENT MARKING TAPE, TYPE III	FOOT	2482		2482	
	21							
	22	70400100	TEMPORARY CONCRETE BARRIER	FOOT	460		460	
	23	78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1416		1416	
	24	78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	24		24	
	25	78200305	PRISMATIC BARRIER REFLECTORS	EACH	20		20	
*	26	81306100	JUNCTION BOX (SPECIAL)	EACH	4	4		
	27	X0322185	BRIDGE DECK LATEX CONCRETE OVERLAY (2-1/4 ")	SQ YD	861.3		861.3	
	28	X5006198	IMPACT ATTENUATOR, TEMPORARY	EACH	1		1	
	29	X6700405	ENGINEER'S FIELD OFFICE, TYPE A (MODIFIED)	CAL MO	11		11	
*	30	Z0001050	AGGREGATE SUBGRADE, 12"	SQ YD	40	40		
	31	Z0002600	BAR SPLICERS	EACH	152		152	
*	32	Z0003800	BEARING REPOSITIONING	EACH	1		1	
	33	Z0012100	CONCRETE BRIDGE DECK SCARIFICATION (1/4")	SQ YD	861.3		861.3	
	34	Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	49		49	
	35	Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	151		151	
	36	Z0017900	DRAINAGE SCUPPERS	EACH	2		2	
	38	Z0047300	PROTECTIVE SHIELD	SQ YD	1257		1257	

* INDICATES SPECIALTY ITEM

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

DESIGNED BY MTK

CHECKED BY RAL

DATE 04/14/05