



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 10, 2005

SUBJECT: West Access Road
Project HD-000S(462)
Section 04-00001-00-PV (Northern Ill. University)
DeKalb County
Contract No. 85360
Item 188
June 17, 2005 Letting
Addendum (A)

TO PROSPECTIVE BIDDERS:

Due to clarify information necessary to revise the following:

Proposal – Schedule of Prices, Special Provision pg. 1.

Plans – Sheets 2, 3, 4, 7, 8, 9, 10, 11, 14

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal. Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Since the proposal sheets are displayed back to back, bidders are cautioned to exercise care when inserting revised and/or added special provisions into their proposals.

Please call 217-782-7806 if any of the above-described material is not included in this transmittal.

Very truly yours,

Michael L. Hine
Engineer of Design and Environment

A handwritten signature in black ink, appearing to read 'Ted B. Walschleger DE'.

By: Ted B. Walschleger
Engineer of Project Development
and Implementation

STATE JOB # - C-92-006-05
 PPS NBR - 2-10091-0000

COUNTY NAME	CODE	DIST	SECTION NUMBER	PROJECT NUMBER	ROUTE
DEKALB	037	02	04-00001-00-PV (NIU)	HD-000S/462/000	W. ACCESS ROAD

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
XX003952	TEMP EROS CONTR COMPL	L SUM	1.000 X	=	=	=	=
XX004731	CON TO EX WM	EACH	1.000 X	=	=	=	=
XX005106	PVC CASING PIPE, 18	FOOT	85.000 X	=	=	=	=
XX005887	SANITARY MH TIE-IN	EACH	1.000 X	=	=	=	=
XX006217	SAN SEWER SERVICE 8	FOOT	20.000 X	=	=	=	=
XX006218	SS D I 6 CL 51	FOOT	27.000 X	=	=	=	=
XX006219	JUN BOX AT ST 10X8X4	EACH	1.000 X	=	=	=	=
XX006220	LUM MET HAL CURV 400W	EACH	14.000 X	=	=	=	=
XX006221	LT P S 20MH SH-BKT 8	EACH	15.000 X	=	=	=	=
XX006222	CON ENC RC 5 PVC 3X2	FOOT	75.000 X	=	=	=	=
X0323927	MAINTAIN LIGHTING SYS	EACH	1.000 X	=	=	=	=
X0976500	END SECTIONS REMOVED	EACH	4.000 X	=	=	=	=
X4066414	BC SC SUPER "C" N50	TON	1,234.000 X	=	=	=	=
X4066426	BC SC SUPER "D" N70	TON	212.000 X	=	=	=	=
X4066614	BCBC SUP IL-19.0 N50	TON	1,996.000 X	=	=	=	=

W. ACCESS
 04-00001-00-PV (NIU)
 DEKALB

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 85360

ECMS002 DTGECM03 ECMR003 PAGE 2
 RUN DATE - 06/09/05
 RUN TIME - 183230

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
X4066770	LEV BIND MM SUPER N70	TON	106.000 X				
X7240600	REM RE-ERECT EX SIGN	EACH	2.000 X				
X8440102	RELOC EX LUMINAIRE	EACH	1.000 X				
X8950130	MOD EX LTG CONTROLLER	EACH	1.000 X				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.000 X				
Z0057100	SAN SEW 12	FOOT	632.000 X				
20200100	EARTH EXCAVATION	CU YD	29,935.000 X				
20201200	REM & DISP UNS MATL	CU YD	4,162.000 X				
20201500	SUB GRAN MAT B	TON	4,527.000 X				
20400100	BORROW EXCAV	CU YD	24,187.000 X				
20800150	TRENCH BACKFILL	CU YD	2,714.000 X				
21101615	TOPSOIL F & P 4	SQ YD	26,017.000 X				
21101645	TOPSOIL F & P 12	SQ YD	2,317.000 X				
25000200	SEEDING CL 2	ACRE	5.850 X				
25000400	NITROGEN FERT NUTR	POUND	527.000 X				

W. ACCESS
 04-00001-00-PV (NIU)
 DEKALB

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 85360

ECMS002 DTGECM03 ECMR003 PAGE 3
 RUN DATE - 06/09/05
 RUN TIME - 183230

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
25000500	PHOSPHORUS FERT NUTR	POUND	527.000 X			=	
25000600	POTASSIUM FERT NUTR	POUND	527.000 X			=	
25100115	MULCH METHOD 2	ACRE	5.850 X			=	
35100100	AGG BASE CSE A	TON	56.000 X			=	
40600100	BIT MATLS PR CT	GALLON	4,005.000 X			=	
40600980	BIT SURF REM BUTT JT	SQ YD	654.000 X			=	
42400200	PC CONC SIDEWALK 5	SQ FT	2,206.000 X			=	
44000100	PAVEMENT REM	SQ YD	1,053.000 X			=	
44000500	COMB CURB GUTTER REM	FOOT	681.000 X			=	
44000920	BIT CONC SHLD REM	SQ YD	95.000 X			=	
44300200	STRIP REF CR CON TR	FOOT	769.000 X			=	
48100100	AGGREGATE SHLDS A	TON	34.000 X			=	
54213657	PRC FLAR END SEC 12	EACH	1.000 X			=	
54213681	PRC FLAR END SEC 36	EACH	1.000 X			=	
550A0340	STORM SEW CL A 2 12	FOOT	257.000 X			=	

W. ACCESS
 04-00001-00-PV (NIU)
 DEKALB

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 85360

ECMS002 DTGECM03 ECMR003 PAGE 4
 RUN DATE - 06/09/05
 RUN TIME - 183230

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
550A0380	STORM SEW CL A 2 18	FOOT	82.000 X	=		=	
550A0430	STORM SEW CL A 2 30	FOOT	113.000 X	=		=	
550A0450	STORM SEW CL A 2 36	FOOT	411.000 X	=		=	
550A0640	STORM SEW CL A 3 12	FOOT	312.000 X	=		=	
550B0330	STORM SEW CL B 2 10	FOOT	34.000 X	=		=	
55100500	STORM SEWER REM 12	FOOT	32.000 X	=		=	
55100900	STORM SEWER REM 18	FOOT	29.000 X	=		=	
55101200	STORM SEWER REM 24	FOOT	22.000 X	=		=	
56103000	D I WATER MAIN 6	FOOT	89.000 X	=		=	
56103300	D I WATER MAIN 12	FOOT	586.000 X	=		=	
56104900	WATER VALVES 6	EACH	1.000 X	=		=	
56105200	WATER VALVES 12	EACH	2.000 X	=		=	
56400710	FIRE HYDNT & VAL SPL	EACH	1.000 X	=		=	
60200305	CB TA 4 DIA T3F&G	EACH	1.000 X	=		=	
60204005	CB TA 5 DIA T3F&G	EACH	1.000 X	=		=	

W. ACCESS
 04-00001-00-PV (NIU)
 DEKALB

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 85360

ECMS002 DTGECM03 ECMR003 PAGE 5
 RUN DATE - 06/09/05
 RUN TIME - 183230

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
60207105	CB TC T3F&G	EACH	1.000 X	=		=	
60207605	CB TC T8G	EACH	3.000 X	=		=	
60218400	MAN TA 4 DIA T1F CL	EACH	1.000 X	=		=	
60218500	MAN TA 4 DIA T3F&G	EACH	6.000 X	=		=	
60221100	MAN TA 5 DIA T1F CL	EACH	2.000 X	=		=	
60223800	MAN TA 6 DIA T1F CL	EACH	3.000 X	=		=	
60228100	MAN SAN T1F CL	EACH	4.000 X	=		=	
60235700	INLETS TA T3F&G	EACH	2.000 X	=		=	
60240220	INLETS TB T3F&G	EACH	1.000 X	=		=	
60255500	MAN ADJUST	EACH	7.000 X	=		=	
60500040	REMOV MANHOLES	EACH	3.000 X	=		=	
60603800	COMB CC&G TB6.12	FOOT	4,673.000 X	=		=	
60605000	COMB CC&G TB6.24	FOOT	100.000 X	=		=	
67000400	ENGR FIELD OFFICE A	CAL MO	3.500 X	=		=	
70101700	TRAF CONT & PROT	L SUM	1.000 X	=		=	

W. ACCESS
 04-00001-00-PV (NIU)
 DEKALB

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 85360

ECMS002 DTGECM03 ECMR003 PAGE 6
 RUN DATE - 06/09/05
 RUN TIME - 183230

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
70300200	TEMP PAVT MARKING	FOOT	132.000 X			=	
70301000	WORK ZONE PAVT MK REM	SQ FT	66.000 X			=	
72000100	SIGN PANEL T1	SQ FT	60.000 X			=	
72000200	SIGN PANEL T2	SQ FT	10.000 X			=	
73000100	WOOD SIN SUPPORT	FOOT	110.000 X			=	
78000100	THPL PVT MK LTR & SYM	SQ FT	110.000 X			=	
78000200	THPL PVT MK LINE 4	FOOT	1,542.000 X			=	
78000500	THPL PVT MK LINE 8	FOOT	115.000 X			=	
78000600	THPL PVT MK LINE 12	FOOT	61.000 X			=	
78000650	THPL PVT MK LINE 24	FOOT	99.000 X			=	
80600200	GRNDING ELECTRODE BG	EACH	15.000 X			=	
81012400	CON T 1 1/4 PVC	FOOT	1,310.000 X			=	
81012500	CON T 1 1/2 PVC	FOOT	445.000 X			=	
81018300	CON P 1 1/4 GALVS	FOOT	250.000 X			=	
81018400	CON P 1 1/2 GALVS	FOOT	40.000 X			=	

78000200

78300105 deleted

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
81500200	TR & BKFIL F ELECT WK	FOOT	1,760.000 X	=			
81702130	EC C XLP USE 1C 6	FOOT	6,350.000 X	=			
81702140	EC C XLP USE 1C 4	FOOT	4,800.000 X	=			
83600100	LIGHT POLE FDN	EACH	15.000 X	=			
84200500	REM EX LT UNIT SALV	EACH	1.000 X	=			
84200700	LIGHTING FDN REMOV	EACH	1.000 X	=			

TOTAL \$

- NOTE:
1. EACH PAY ITEM SHOULD HAVE A UNIT PRICE AND A TOTAL PRICE.
 2. THE UNIT PRICE SHALL GOVERN IF NO TOTAL PRICE IS SHOWN OR IF THERE IS A DISCREPANCY BETWEEN THE PRODUCT OF THE UNIT PRICE MULTIPLIED BY THE QUANTITY.
 3. IF A UNIT PRICE IS OMITTED, THE TOTAL PRICE WILL BE DIVIDED BY THE QUANTITY IN ORDER TO ESTABLISH A UNIT PRICE.
 4. A BID MAY BE DECLARED UNACCEPTABLE IF NEITHER A UNIT PRICE NOR A TOTAL PRICE IS SHOWN.

SPECIAL PROVISIONS

The following Special Provisions supplement the "Standard Specifications for Road and Bridge Construction," adopted January 1, 2002, the latest edition of the "Illinois Manual for Uniform Traffic Control Devices for Streets and Highways", the "Standard Specifications for Traffic Control Items," in effect on the date of invitation for bids, the "Standard Specifications for Water & Sewer Main Construction in Illinois, fifth edition", the City of DeKalb Sanitary District Standards, and the Supplemental Specifications and Recurring Special Provisions" indicated on the Check Sheet included herein which apply to and govern the construction of the Northern Illinois University West Access Boulevard, HD-0005C 4623 Section 04-00001-00-PV, in DeKalb County, Illinois, and in case of conflict with any part or parts of said specifications, the said Special Provisions shall take precedence and shall govern.

LOCATION OF PROJECT

At the Northern Illinois University Campus in DeKalb County, Illinois, north of Illinois Route 38.

West Access Boulevard is located in the City of Dekalb, Illinois, west of Annie Glidden Road and north of Lincoln Highway/State Route-38. It currently serves as the western edge of the developed portions of the Northern Illinois University (NIU) Campus. The western terminus of existing Convocation Center Drive North is its intersection with existing West Access Boulevard.

DESCRIPTION OF WORK

The work under this contract consists of construction of two southbound lanes west of the existing West Access Road, associated intersection improvements to the new West Access Boulevard at IL 38, relocation of an existing stormwater retention facility, and construction of a boulevard to extend Convocation Center Drive North. Construction of the roadways will include bituminous pavement with curb and gutter, a 16-foot median, associated storm sewer, sanitary sewer, earth excavation, construction of embankment, roadway lighting, sidewalk, and resurfacing and pavement marking on IL 38. The resurfacing on IL 38 will require coordination with the contractor performing an IDOT resurfacing project in the vicinity.

COMPLETION DATE

A completion date, as defined in Article 108.05 (a) of the Standard Specifications, will be utilized for this project. All work included in this contract, including removal of all traffic control devices, completion of the punch list, and opening West Access Boulevard and Convocation Center Drive North to through traffic, shall be completed by 3:30 PM local time on Tuesday, November 22, 2005.