

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	...	FULTON	684	8
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			
... 181,188BRY&188BRY-1BR,188-1 CONTRACT# 88753				

SUMMARY OF QUANTITIES				TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
					H05	H10				
CODE NO	ITEM	UNIT		NHS STATE FED - STATE 80 - 20 I000-2A ROADWAY	BRRP RURAL FED - STATE 80 - 20 X071-2A ROADWAY	BRRP RURAL FED - STATE 80 - 20 X081-2A OVERFLOW	BRRP RURAL FED - STATE 80 - 20 X071-2A SPOON RIVER	BRRP RURAL FED - STATE 80 - 20 X081-2A TRIBUTARY	BRRP RURAL FED - STATE 80 - 20 Y007 WALLS	
31101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	1,032	212	820					
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	4,199		4,199					
35300200	PORTLAND CEMENT CONCRETE BASE COURSE 7"	SQ YD	2,288	320	1,968					
35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SQ YD	16	16						
35500500	BITUMINOUS BASE COURSE 8"	SQ YD	3,341	1,902	1,439					
35600500	BITUMINOUS CONCRETE BASE COURSE WIDENING 10"	SQ YD	105	105						
40200100	AGGREGATE SURFACE COURSE, TYPE A	TON	2,138	942	1,196					
40300400	BITUMINOUS MATERIALS (COVER AND SEAL COATS)	TON	9	1	8					
40300500	COVER COAT AGGREGATE	TON	60	7	53					
40300600	SEAL COAT AGGREGATE	TON	60	7	53					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	15.0	4.6	10.4					
40600300	AGGREGATE (PRIME COAT)	TON	91	58	33					
40600895	CONSTRUCTING TEST STRIP	EACH	1	0.58	0.42					
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	340	253	87					
40600990	TEMPORARY RAMP	SQ YD	171	82	89					
40700520	BITUMINOUS CONCRETE BINDER COURSE, TYPE 1 8"	SQ YD	7,925	7,925						
40700530	BITUMINOUS CONCRETE BINDER COURSE, TYPE 1 9"	SQ YD	12,903		12,903					
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	33	33						
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	641	241	400					
42001200	PAVEMENT FABRIC	SQ YD	2,288	320	1,968					
42001300	PROTECTIVE COAT	SQ YD	4,557			481	3,776	300		
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	138		138					
44000001	BITUMINOUS SURFACE REMOVAL 1/4"	SQ YD	26,669	26,669						
44000100	PAVEMENT REMOVAL	SQ YD	17,896	3,418	14,478					
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1,154	1,154						
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	111	111						
44001000	BITUMINOUS CONCRETE SURFACE REMOVAL	SQ YD	32.8				32.8			
44002805	ISLAND REMOVAL	SQ FT	128	128						
44201815	CLASS D PATCH, TYPE II, 14 INCH	SQ YD	56	28	28					
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	SQ YD	16,098	16,098						
48101200	AGGREGATE SHOULDERS, TYPE B	TON	5,126	3,418	1,708					
48202400	BITUMINOUS SHOULDERS SUPERPAVE 6"	SQ YD	1,033		1,033					

X SPECIALTY ITEM