

# SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	...	FULTON	604	9
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
*** 181,188RY&188RY-11BR,188-1 CONTRACT# 88753				

SUMMARY OF QUANTITIES					H05	H10 - CONSTRUCTION TYPE CODE				
					NHS STATE FED - STATE 80 - 20 1000-2A ROADWAY	BRRP RURAL FED - STATE 80 - 20 X071-2A ROADWAY	BRRP RURAL FED - STATE 80 - 20 X081-2A OVERFLOW	BRRP RURAL FED - STATE 80 - 20 X071-2A SPOON RIVER	BRRP RURAL FED - STATE 80 - 20 X081-2A TRIBUTARY	BRRP RURAL FED - STATE 80 - 20 Y007 WALLS
CODE NO	ITEM	UNIT	TOTAL QUANTITIES							
	48202410	BITUMINOUS SHOULDERS SUPERPAVE 6 1/2 "	SQ YD	1,185	939	246				
	50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1			1			
	50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1				1		
	50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1					1	
	50100600	REMOVAL OF EXISTING STRUCTURES NO. 4	EACH	1	1					
	50104400	CONCRETE HEADWALL REMOVAL	EACH	18	12	6				
	50105210	REMOVE EXISTING CULVERTS	FOOT	673	494	179				
	50200100	STRUCTURE EXCAVATION	CU YD	1,771			89	820	380	482
X	50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	14.3				14.3		
	50300100	FLOOR DRAINS	EACH	11			5		6	
	50300225	CONCRETE STRUCTURES	CU YD	813.5			44.4	552	33.8	183.3
	50300255	CONCRETE SUPERSTRUCTURE	CU YD	1,182.4			151.6	930.4	100.4	
	50300260	BRIDGE DECK GROOVING	SQ YD	3,607			384	2,990	233	
	50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ FT	1,239				1,239		
	50400905	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I - BEAMS, 42"	FOOT	366					366	
	50401105	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I - BEAMS, 54"	FOOT	537			537			
	50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1				1		
	50500505	STUD SHEAR CONNECTORS	EACH	6,867				6,066		801
X	50700209	UNTREATED TIMBER LAGGING	SQ FT	4,365						4,365
	50700215	FURNISHING SOLDIER PILES (W SECTION)	FOOT	1,842						1,842
	50800105	REINFORCEMENT BARS	POUND	30,714	134			30,580		
	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	383,820			34,100	295,160	26,440	28,120
	50900105	ALUMINUM RAILING TYPE L	FOOT	168				168		
	51100100	SLOPE WALL 4"	SQ YD	133				133		
	51201500	FURNISHING STEEL PILES HP 10 X 57	FOOT	560				560		
	51201600	FURNISHING STEEL PILES HP 12 X 53	FOOT	415					415	
	51201700	FURNISHING STEEL PILES HP 12 X 74	FOOT	2,124			825	1,299		
	51202700	DRIVING STEEL PILES	FOOT	3,099			825	1,859	415	
	51203500	TEST PILE STEEL HP 10 X 57	EACH	1				1		
	51203600	TEST PILE STEEL HP 12 X 53	EACH	1					1	

X SPECIALTY ITEM