

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	...	FULTON	684	13
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
*** 181, (18BRY&18BRY-1)BR, 18B-1 CONTRACT# 88753				

SUMMARY OF QUANTITIES					H05	← H10 CONSTRUCTION TYPE CODE →				
					NHS STATE FED - STATE 80 - 20 I000-2A ROADWAY	BRRP RURAL FED - STATE 80 - 20 X071-2A ROADWAY	BRRP RURAL FED - STATE 80 - 20 X081-2A OVERFLOW	BRRP RURAL FED - STATE 80 - 20 X071-2A SPOON RIVER	BRRP RURAL FED - STATE 80 - 20 X081-2A TRIBUTARY	BRRP RURAL FED - STATE 80 - 20 Y007 WALLS
CODE NO	ITEM	UNIT	TOTAL QUANTITIES							
	78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	51,548	33,000	18,548				
X	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	197	142	55				
	78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	64	62	2				
	78200200	BIDIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	113		113				
	78200410	GUARDRAIL MARKERS, TYPE A	EACH	12	6	6				
	78200530	BARRIER WALL MARKERS, TYPE C	EACH	22	4	18				
	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	8	2	6				
	78300105	PAVEMENT MARKING REMOVAL	FOOT	14,946	11,546	3,400				
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	3	3					
X	80500100	SERVICE INSTALLATION, TYPE A	EACH	1	1					
X	81012600	CONDUIT IN TRENCH, 2" DIA. PVC	FOOT	31	31					
X	81021330	CONDUIT PUSHED, 2" DIA. PVC	FOOT	19	19					
X	81100500	CONDUIT ATTACHED TO STRUCTURE, 1 1/2" DIA. GALV.	FOOT	49	49					
X	81500200	TRENCH & BACKFILL FOR ELECTRICAL WORK	FOOT	31	31					
X	82104250	LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, PHOTO-CELL CONTROL, 250 WATT	EACH	2	2					
X	85800100	FLASHER CONTROLLER	EACH	1	1					
X	86600010	GULFBOX JUNCTION	EACH	2	2					
X	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	74	74					
X	88000110	SIGNAL HEAD, 1 FACE, 1 SECTION, POST MOUNTED	EACH	1	1					
	Z0000990	AGGREGATE FOR TEMPORARY ACCESS	TON	1,171		1,171				
	Z0002600	BAR SPLICERS	EACH	380			80	84	216	
	Z0002750	BARRICADES, TYPE III	EACH	5		5				
X	Z0007601	BUILDING REMOVAL NO. 1	L SUM	1	1					
X	Z0008236	DRILLED SHAFT IN SOIL 36"	FOOT	145				145		
X	Z0008324	DRILLED SHAFT IN ROCK 24"	FOOT	72				72		
X	Z0008330	DRILLED SHAFT IN ROCK 30"	FOOT	80				80		
	Z0008336	DRILLED SHAFT IN ROCK 36"	FOOT	184				184		
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.58	0.42				
	Z0022400	FABRIC REINFORCED ELASTOMERIC TROUGH	FOOT	87				87		
	Z0022800	FENCE REMOVAL	FOOT	11,048	6,879	4,169				
	Z0023500	FILLING EXISTING CULVERTS	CU YD	11	11					

X SPECIALTY ITEM