

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	***	FULTON	694	25
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
*** 181,18BRY&18BRY-1)BR,18B-1				

# SCHEDULE OF QUANTITIES

FENCE REMOVAL		
LOCATION	LT/RT	FOOT
US 24		
STA 149+19 TO 3+34	RT	436
STA 4+00 TO 13+15	LT	931
STA 5+26 TO 11+91	RT	766
STA 15+75 TO 21+45	RT	588
STA 27+80 TO 34+00	RT	625
STA 32+60 TO 33+61	LT	167
STA 33+71 TO 38+80	LT	602
STA 35+11	LT	54
STA 39+20 TO 45+45	LT	867
STA 43+64 TO 44+06	RT	99
STA 78+92 TO 82+46	LT	417
STA 79+24 TO 82+66	RT	343
STA 82+62 TO 84+15	LT	181
STA 84+25	RT	44
STA 84+33 TO 86+92	RT	150
STA 85+11 TO 86+93	RT	281
STA 86+93 TO 87+26	RT	237
STA 87+57 TO 88+46	LT	90
STA 88+71 TO 90+78	LT	208
STA 95+97 TO 102+28	RT	652
STA 96+44 TO 102+72	LT	675
STA 103+64 TO 106+59	RT	323
STA 120+18 TO 122+67	RT	723
STA 122+67 TO 129+20	RT	369
CH 11 WEST		
STA 7+27 TO 9+56	RT	265
STA 7+65 TO 9+00	LT	134
CH 11 EAST		
STA 10+49 TO 18+73	RT	823
<b>TOTAL</b>		<b>11,048</b>

DRIVEWAY PAVEMENT REMOVAL		
LOCATION	LT/RT	SQ YD
US 24		
STA 26+19	LT	103.80
STA 87+50	RT	1,050.50
<b>TOTAL</b>		<b>1,154</b>

REMOVING INLETS		
LOCATION	LT/RT	EACH
US 24		
STA 89+12	RT	1
CH 11 EAST		
STA 17+30	LT	1
<b>TOTAL</b>		<b>2</b>

ISLAND REMOVAL		
LOCATION	LT/RT	SQ FT
US 24		
RT STA 87+88	RT	112.40
RT STA 88+86	RT	15.60
<b>TOTAL</b>		<b>128</b>

COMBINATION CURB AND GUTTER REMOVAL		
LOCATION	LT/RT	FOOT
US 136		
STA 660+04 TO 660+54	RT	64.50
STA 660+82 TO 661+24	RT	46.50
<b>TOTAL</b>		<b>111</b>

REMOVAL OF EXISTING STRUCTURES NO. 4	
LOCATION	EACH
US 24 - STAGE V	
TEMPORARY BRIDGE	
STA 84+00 TO 84+41 RT	1
<b>TOTAL</b>	<b>1</b>

GUARDRAIL REMOVAL		
LOCATION	LT/RT	FOOT
US 24		
STA 0+66 TO 2+68	RT	202
STA 55+22 TO 63+32	RT	810
STA 57+00 TO 62+88	LT	588
STA 63+20 TO 63+31	LT	11
STA 66+18 TO 68+55	RT	237
STA 66+18 TO 73+30	LT	712
STA 69+00 TO 73+30	RT	430
STA 78+20 TO 78+63	RT	43
STA 78+20	LT	62
STA 82+72 TO 87+61	LT	489
STA 82+90 TO 87+00	RT	362
STA 100+46 TO 103+24	LT	278
STA 100+65 TO 103+15	RT	250
STA 122+16 TO 122+92	RT	76
STA 122+22 TO 123+00	LT	78
<b>TOTAL</b>		<b>4,628</b>

UNDERGROUND STORAGE TANK REMOVAL		
LOCATION	LT/RT	EACH
US 24		
STA 89+00 TO 90+10	1 TO 70 FT RT	1
US 136		
STA 659+00 TO 660+85	1 TO 100 FT RT	1
<b>TOTAL</b>		<b>2</b>

TREE REMOVAL		
LOCATION	LT/RT	ACRE
US 24		
STA 2+00	RT	0.39
STA 38+00	LT	0.08
STA 60+00	LT	0.56
STA 64+00	LT	0.18
STA 75+00	LT	0.44
STA 80+50	RT	0.05
STA 81+00	LT	0.10
STA 81+50	RT	0.02
STA 83+00	LT	0.17
STA 86+00	LT	0.19
STA 93+00	LT	0.45
STA 99+00	LT	0.82
STA 99+00	RT	0.12
STA 100+50	LT	0.02
STA 121+50	RT	0.19
CH 11 EAST		
STA 15+00	RT	0.47
<b>TOTAL</b>		<b>4.25</b>

CONCRETE HEADWALL REMOVAL		
LOCATION	LT/RT	EACH
US 24		
STA 28+00	LT/RT	2
STA 44+19	RT	1
STA 44+58	RT	1
STA 45+45	LT	1
STA 45+77	LT	1
STA 101+45	LT	1
STA 102+34	RT	1
STA 122+57	LT/RT	2
STA 129+67	LT	1
STA 129+86	LT	1
US 136		
STA 658+61	RT	1
STA 658+98	RT	1
BACK RD		
STA 10+21	LT/RT	2
CH 11 WEST		
STA 7+27	LT/RT	2
<b>TOTAL</b>		<b>18</b>

PAVEMENT REMOVAL			
LOCATION	LT/RT	WIDTH (FT)	SQ YD
US 24			
STA 4+73 TO 9+62	LT	6.50	353
STA 4+96 TO 11+09	RT	5.75	392
STA 30+00 TO 63+32	LT/RT	24.00	8885
STA 66+18 TO 73+30	LT/RT	24.00	1899
STA 78+18 TO 82+60	LT/RT	24.00	1179
STA 82+60 TO 84+96	LT/RT	24.00	630
STA 97+60 TO 111+86	LT	6.50	1030
STA 96+00 TO 111+86	RT	5.75	1013
STAGE V			
TEMPORARY CROSSOVER	RT		390
DETOUR RUNAROUND	RT		2125
<b>TOTAL</b>			<b>17,896</b>

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	
LOCATION	EACH
US 136	
STA 658+00 TO 661+00	3
<b>TOTAL</b>	<b>3</b>

BUILDING REMOVAL NO.1	
LOCATION	L SUM
NORTHWEST CORNER OF THE US 24 & US 136 INTERSECTION	1
<b>TOTAL</b>	<b>1</b>

REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO. 1	
LOCATION	L SUM
NORTHWEST CORNER OF THE US 24 & US 136 INTERSECTION	1
<b>TOTAL</b>	<b>1</b>

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SCHEDULE OF QUANTITIES

SCALE: VERT. HORIZ. DATE

DRAWN BY CHECKED BY