

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS
317	***	FULTON	684 30
STA.	TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT	
*** 181,18BRY&18BRY-1)BR,18B-1			

SCHEDULE OF QUANTITIES

TEMPORARY CONCRETE BARRIER	
LOCATION	FOOT
STAGE I - US 24	
STA 82+90 TO 84+51.98	162
STA 85+00 TO 85+78.02	78
STAGE IA - US 24	
72+50 TO 77+80	530
STAGE III - US 24	
STA 77+80 TO 78+70	90
STA 82+30.43 TO 84+51.98	222
STA 85+00 TO 85+78.45	78
TOTAL	1,160

TRAFFIC CONTROL AND PROTECTION						
STAGE	STD 701201	STD 701321	STD 701316	STD 701306	STD 701326	(SPECIAL)
	L SUM	EACH	EACH	L SUM	L SUM	EACH
STAGE I	1				0.34	
STAGE IA & IB		1				
STAGE II					0.33	
STAGE IIA, IIB, & IIC					0.33	
STAGE III			1			1
STAGE IV						
STAGE V			1	1		
TOTAL	1	1	2	1	1	1

MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	
LOCATION	EACH
STAGE I - US 24	
82+90 TO 84+51.98	14
85+00 TO 85+78.02	6
STAGE III - US 24	
82+30.43 TO 84+51.98	18
85+00 TO 85+78.45	6
82+80 TO 84+51.98	14
85+00 TO 68.02	6
TOTAL	64

RELOCATE TEMPORARY CONCRETE BARRIER	
LOCATION	FOOT
STAGE IB - US 24	
STA 72+50 TO 77+80	530
STAGE III - US 24	
STA 72+50 TO 77+80	530
STA 82+80 TO 84+51.98	171.98
STA 85+00 TO 85+68.02	68.02
STAGE IV - US 24	
STA 78+00 TO 78+50	50
TOTAL	1,350

IMPACT ATTENUATORS, TEMPORARY, (NON-REDIRECTIVE), TEST LEVEL 3	
LOCATION	EACH
STAGE IA - US 24	
RT STA 72+00	1
RT STA 78+00	1
TOTAL	2

IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	
LOCATION	EACH
STAGE IB - US 24	
RT STA 72+00	1
RT STA 78+00	1
STAGE III - US 24	
RT STA 72+00	1
TOTAL	3

CONSTRUCTION LAYOUT	
LOCATION	L SUM
JOBSITE	1
TOTAL	1

TRAINEES	
LOCATION	HOURLY
JOBSITE	2000
TOTAL	2,000

PORTABLE TEMPORARY BARRIER SYSTEM	
LOCATION	FOOT
STAGE III - US 24	
STA 78+00 TO 81+51	351
STA 82+01 TO 83+50.50	149.5
STA 85+00 TO 88+31.50	331.5
STAGE IV - US 24	
STA 79+79.50 TO 84+51.98	472.48
STA 85+00 TO 87+03.52	203.52
TOTAL	1,508

IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE NARROW), TEST LEVEL 3	
LOCATION	EACH
STAGE I - US 24	
RT STA 82+90	1
RT STA 85+78.02	1
STAGE IA - US 24	
RT STA 72+50	1
RT STA 77+80	1
TOTAL	4

IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	
LOCATION	EACH
STAGE IB - US 24	
RT STA 72+50	1
RT STA 77+80	1
STAGE III - US 24	
RT STA 72+50	1
RT STA 82+30.47	1
RT STA 85+78.45	1
TOTAL	5

ENGINEER'S FIELD OFFICE, TYPE A	
LOCATION	CAL MO
JOBSITE	27
TOTAL	27

CONSTRUCTING TEST STRIP	
LOCATION	EACH
JOBSITE	1
TOTAL	1

RELOCATE PORTABLE TEMPORARY BARRIER SYSTEM	
LOCATION	FOOT
STAGE IV - US 24	
STA 78+00 TO 82+03	403
STA 82+51 TO 84+00.50	149.5
STA 77+00 TO 79+79.50	279.5
TOTAL	832

BARRICADES, TYPE III	
LOCATION	EACH
STAGE III - US 24	
STA 30+00	1
STA 34+43	1
STAGE IV - US 24	
STA 67+10	1
STA 69+15	1
STAGE V - US 24	
STA 66+90	1
TOTAL	5

TEMPORARY BRIDGE TRAFFIC SIGNALS	
LOCATION	EACH
STAGE IA - US 24	
STA 70+74 TO 79+96	1
STAGE III - US 24	
STA 28+90 TO 37+50	1
TOTAL	2

ENGINEER'S FIELD LABORATORY	
LOCATION	CAL MO
JOBSITE	27
TOTAL	27

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. DATE: HORIZ.

DRAWN BY: CHECKED BY: