

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	...	FULTON	684	32
STA. TO STA.				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
... 181,18BRY&18BRY-18B-1				

SCHEDULE OF QUANTITIES

STONE DUMPED RIPRAP			
LOCATION	LT/RT	STONE DUMPED RIPRAP	
		CLASS A3	CLASS B3
		TON	TON
STAGE I - US 24			
STA 2+60	RT		113.1
STA 10+00 TO 19+00	LT		469.1
STA 10+00 TO 22+00	RT		636.0
STA 27+00 TO 27+50	LT		20.9
STA 28+00.62	LT		11.2
STA 38+00 TO 49+65	LT		527.6
STA 89+50 TO 101+00	RT		591.9
STA 97+00 TO 108+00	LT		571.7
STA 101+91.12	LT		26.3
STA 102+72 TO 109+00	RT		250.1
STA 122+57.4	RT		11.3
STAGE III - US 24			
STA 64+32	LT	45.8	
STA 70+25	LT	48.2	
STA 79+30 TO 79+40	LT		5.1
82+40 TO 83+75	LT		52.4
STA 83+61	LT	16.3	
STA 85+00	LT	37.7	
STAGE III - CH 11 EAST			
STA 17+30.18	LT		41.3
STAGE V - US 24			
STA 38+00 TO 48+00	RT		691.4
STA 83+25 TO 83+75	RT		22.2
STA 83+61	RT	29.2	
STA 85+00	RT	18.1	
STAGE V - CH 11 WEST			
STA 13+27	RT		49.8
TOTAL		195	4,091

TERMINAL MARKERS - DIRECT APPLIED		
LOCATION	LT/RT	EACH
US 24		
STA 61+36	RT	1
STA 63+53	LT	1
STA 82+42	LT	1
STA 82+42	RT	1
STA 86+15	RT	1
STA 87+90	LT	1
CH 11 WEST		
STA 10+75	RT	1
CH 11 EAST		
STA 11+17	LT	1
TOTAL		8

PIPE CULVERTS, CLASS D, TYPE 1, 12" (TEMPORARY)	
LOCATION	FOOT
US 24	
LIDWELL ACCESS DRIVE	22
TOTAL	22

MANHOLE TYPE A, 5' DIAMETER, TYPE 1 FRAME, CLOSED LID		
LOCATION	LT/RT	EACH
STAGE I - US 24		
STA 1+25	52.2' RT	1
STA 1+75	83.2' RT	1
STA 2+25	120.0' RT	1
STA 102+40	46.79' RT	1
STA 122+57.40	26' RT	1
TOTAL		5

FABRIC FORMED CONCRETE REVETMENT MAT		
LOCATION	LT/RT	SQ YD
STAGE I - US 24		
STA 0+95	RT	28.1
STA 101+90	RT	31.8
STA 102+60	RT	26.1
TOTAL		86

PIPE DRAINS 12"		
LOCATION	LT/RT	FOOT
STAGE III - US 24		
STA 64+32	LT	7.68
STA 70+25	LT	7.68
STA 83+61	LT	6.8
STA 85+00	LT	6.8
STAGE V - US 24		
STA 83+61	RT	6.8
STA 85+00	RT	6.8
TOTAL		43

TYPE B INLET BOX STANDARD 609001		
LOCATION	LT/RT	EACH
STAGE III - US 24		
STA 83+61	LT	1
STA 85+00	LT	1
STAGE V - US 24		
STA 83+61	RT	1
STA 85+00	RT	1
TOTAL		4

EXPANSION BOLTS 3/4 IN		
LOCATION	LT/RT	EACH
STAGE I - US 24		
STA 28+00.62	LT/RT	16
STA 101.91.12	LT/RT	16
STA 122+57.40	LT/RT	16
TOTAL		48

CONCRETE COLLAR		
LOCATION	LT/RT	CU YD
STAGE I - US 24		
STA 28+00.62	LT/RT	0.64
STA 101.91.12	LT/RT	0.64
STA 122+57.40	LT/RT	0.52
TOTAL		1.8

CONCRETE GUTTER, TYPE A (MODIFIED)		
LOCATION	LT/RT	FOOT
STAGE I - US 24		
STA 2+82 TO 4+00	LT	118
STAGE III - US 24		
STA 79+50 TO 81+60	LT	210
TOTAL		328

BOX CULVERT SCHEDULE					
LOCATION	PRECAST CONCRETE BOX CULVERT 2' X 2'	PRECAST CONCRETE BOX CULVERT 2' X 3'	BOX CULVERT END SECTION CULVERT NO. 1	BOX CULVERT END SECTION CULVERT NO. 2	BOX CULVERT END SECTION CULVERT NO. 3
	FOOT	FOOT	EACH	EACH	EACH
STAGE I - US 24					
STA 28+00.62		29	2		
STA 101+91.12		72		1	
STA 122+57.40	40				1
TOTAL	40	101	2	1	1

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p>SCHEDULE OF QUANTITIES</p> <p>SCALE: VERT. HORIZ. DATE</p> <p>DRAWN BY CHECKED BY</p>