

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	***	FULTON	684	34
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

*** 181,18BRY&18BRY-18R,18B-1

SCHEDULE OF QUANTITIES

PIPE CULVERT SCHEDULE (CONT)								
LOCATION	LT/RT	PRECAST REINFORCED CONCRETE FLARED END SECTION			END SECTION			
		18"	24"	36"	12"	15"	18"	24"
		EACH	EACH	EACH	EACH	EACH	EACH	EACH
STAGE I - US 24								
STA 1+11	RT		1					
STA 1+25	RT		1					
STA 1+50	RT							
STA 2+00	RT							
STA 2+51	RT			1				
STA 21+07.53	RT					2		
STA 24+69.79	RT						2	
STA 29+26.40	RT							2
STA 39+09.73	LT							2
STA 45+61.60	LT							2
STA 88+49.31	LT							2
STA 90+84.65	RT							2
STA 102+19	RT		1					
STA 102+35	RT							
STA 102+46	RT			1				
STA 118+75.21	RT							2
STA 129+44.16	RT		2					
STA 129+44.16	LT		2					
STAGE I - US 136 N								
STA 658+75	RT							2
STA 658+93.69	LT							2
STA 659+75.05	RT							2
STAGE I - CH 11 EAST								
STA 17+30.18			2					
STAGE I - BACK RD								
STA 11+50	RT					2		
STAGE III - US 24								
STA 64+32	LT				1			
STA 70+25	LT				1			
STA 77+72	LT				1			
STA 82+02.34	LT						2	
STA 83+61	LT				1			
STA 85+00	LT				1			
STAGE V - US 24								
STA 83+61	RT				1			
STA 85+00	RT				1			
STA 44+37.41	RT							2
STAGE V - CH 11 WEST								
STA 12+90.25		2						
STA 13+25	LT						2	
TOTAL		2	9	2	7	4	6	20

GEOTECHNICAL FABRIC FOR GROUND STABILIZATION		
LOCATION	LT/RT	SQ YD
US 24		
STA 2+50 TO 3+50	LT/RT	80
STA 5+50 TO 6+50	LT/RT	150
STA 8+50 TO 9+50	LT/RT	150
STA 14+50 TO 15+50	LT/RT	139
STA 98+50 TO 100+00	LT/RT	225
STA 103+25 TO 107+50	LT/RT	638
TOTAL		1382

BRIDGE APPROACH PAVEMENT (SPECIAL)	
LOCATION	SQ YD
STAGE III - US 24	
SPOON RIVER (S. ABUT)	138
STA 77+67 TO 77+97	
TOTAL	138

BRIDGE APPROACH PAVEMENT	
LOCATION	SQ YD
STAGE III - US 24	
SPOON RIVER OVERFLOW	
STA 64+24 TO 64+54	133.33
STA 65+45 TO 65+75	133.33
SPOON RIVER (N. ABUT)	
STA 70+21 TO 70+51	133.33
SPOON RIVER TRIBUTARY	
STA 83+56 TO 83+86	120
STA 84+48 TO 85+26	121
TOTAL	641

INLETS, TYPE A, WITH MEDIAN INLET (604101) SPECIAL		
LOCATION	LT/RT	EACH
US 24		
STA 81+96	RT	1
TOTAL		1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. DATE: HORIZ. DRAWN BY: CHECKED BY:

PLOT DATE = 4/7/2005
 FILE NAME = c:\p\o\keta\us24\spoon.ch.2\schedule.of.quantities.dgn
 PLOT SCALE = 90.0000 / IN.
 USER NAME = heglind