

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	***	FULTON	684	36
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
*** 181,18BRY&18BRY-1BR,18B-1				

SCHEDULE OF QUANTITIES

SCHEDULE OF EARTHWORK QUANTITIES STAGES III & IV				
LOCATION	EARTH EXCAVATION (CUT)	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT (FILL)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CU YD	CU YD	CU YD	CU YD
US 24				
STA 0+00 to 30+00	0	0	0	0
STA 30+00 TO 64+00	0	0	0	0
STA 65+44 TO 70+51	0	0	0	0
STA 77+70 TO 82+60	2361	1771	496	1275
STA 82+60 TO 85+26	644	483	901	-418
STA 85+26 TO 113+00	1170	878	1377	-499
STA 113+00 TO 132+00	0	0	0	0
**CH 11 EAST				
STA 10+50 TO 25+50	6328	4746	1357	3389
TOTAL	10,503	7,877	4,130	3,747

SCHEDULE OF EARTHWORK QUANTITIES STAGE V				
LOCATION	EARTH EXCAVATION (CUT)	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT (FILL)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CU YD	CU YD	CU YD	CU YD
US 24				
STA 0+00 to 30+00	0	0	0	0
STA 30+00 TO 64+00	20800	15600	10132	5469
STA 65+44 TO 70+51	4210	3158	10006	-6848
STA 77+70 TO 82+60	143	107	292	-185
STA 82+60 TO 85+26	1454	1090	13	1077
STA 85+26 TO 113+00	1283	963	0	963
STA 113+00 TO 132+00	0	0	0	0
LIDWELL STA 0+25 TO 2+00	0	0	545	-545
HAZLANE STA 0+00 TO 2+90	766	575	4	571
CH 11 WEST				
STA 10+75 TO 14+00	367	275	776	-501
TOTAL	29,024	21,768	21,767	1

NOTES:

SHRINKAGE FACTOR: 25%
DENOTES PAY QUANTITY

NOTES:

SHRINKAGE FACTOR: 25%
DENOTES PAY QUANTITY

PERIMETER EROSION BARRIER		
LOCATION	LT/RT	FOOT
US 24		
STA 19+00 TO 24+00	LT	491.2
STA 49+00 TO 51+00	LT	200
STA 54+60 to 57+17	RT	283.47
STA 63+30 TO 64+52	RT	260
STA 64+06 TO 64+52	LT	200
STA 65+26 TO 75+35	LT	1171
65+26 TO 75+35	RT	1482
STA 84+47	RT	66.41
STA 84+84	RT	66.1
STA 84+55	LT	60.87
STA 84+83	LT	80.42
CH 11 WEST		
STA 7+87 to 10+06	LT	250.37
CH 11 EAST		
STA 10+75 TO 17+83	LT	720.16
HAZZARD TEMP ACCESS		
0+40 TO 2+50	RT	210
TOTAL		5,542

EROSION CONTROL BLANKET	
LOCATION	SQ YD
US 24	
STA 0+00 TO 30+00	6,836
STA 30+00 TO 64+00	5,488
STA 65+44 TO 70+51	16,822
STA 77+70 TO 85+25	1,177
STA 85+25 TO 113+00	13,305
STA 113+00 TO 132+00	4,536
BACK ROAD	
STA 8+25 TO 11+75	628
US 136	
STA 657+50 TO 659+25	158
CH 11 WEST	
STA 10+75 TO 14+00	202
CH 11 EAST	
STA 10+50 TO 25+50	3,945
HAZLANE (TEMP)	
STA 0+00 TO 2+90	448
LIDWELL (TEMP)	
STA 0+25 TO 2+00	396
TOTAL	53,941

INLET PROTECTION SPECIAL		
LOCATION	LT/RT	EACH
US 24		
STA 1+28	LT	1
STA 2+00	RT	1
STA 28+00	RT	1
STA 39+15	LT	1
STA 46+31	LT	1
STA 102+40	RT	1
STA 119+00	RT	1
STA 120+55	RT	1
STA 129+00	LT/RT	2
CH 11 WEST		
STA 12+80	LT	1
CH 11 EAST		
STA 17+38	LT	1
TOTAL		12

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. HORIZ. DATE

DRAWN BY CHECKED BY