

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE						
PAY CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	1000-2A		X071-2A		X000-2A	Y007	
				RURAL	URBAN	RURAL	URBAN	RURAL	RURAL	URBAN
2010010	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	685	657	28					
2010020	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	739	504	235					
20100500	TREE REMOVAL, ACRES	ACRE	3.9	0.3	3.6					
20101000	TEMPORARY FENCE	FOOT	1500	1500						
20200100	EARTH EXCAVATION	CU YD	57,101	28,226	28,985					
20200300	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	356	12	344					
20200400	EARTH EXCAVATION (SPECIAL)	CU YD	15,497						15,497	△
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	2,282	2,282						
20300100	CHANNEL EXCAVATION	CU YD	3,724	3,724						
20400800	FURNISHED EXCAVATION	CU YD	217	217						△
20700220	POROUS GRANULAR EMBANKMENT	CU YD	1,077			568	509			
20800150	TRENCH BACKFILL	CU YD	200	97	103					
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	9925		9925					
<del>21015000</del>	<del>TOP SOIL EXCAVATION AND PLACEMENT</del>	<del>CU YD</del>	<del>15,812</del>	<del>13,839</del>	<del>2,273</del>					
25000210	SEEDING, CLASS 2A	ACRE	12.7	9.3	3.4					
25000312	SEEDING, CLASS 4A	ACRE	5.4	4.0	1.4					
25000314	SEEDING, CLASS 4B	ACRE	2.4	2.4						
25000320	SEEDING, CLASS 5	ACRE	5.4	4.0	1.4					
25000324	SEEDING, CLASS 5B	ACRE	2.4	2.4						
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1,845	1,413	432					
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1,845	1,413	432					
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1,845	1,413	432					
25000700	AGRICULTURAL GROUND LIMESTONE	TON	41.0	31.4	9.6					
25100120	MULCH, METHOD 2	TON	41.0	31.4	9.6					
25100630	EROSION CONTROL BLANKET	SQ YD	1922	110	1812					△
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	2,050	1,570	480					
28000300	TEMPORARY DITCH CHECKS	EACH	152	99	53					
28000400	PERIMETER EROSION BARRIER	FOOT	2008	2228	580					
28000500	INLET AND PIPE PROTECTION	EACH	30	15	15					
28100107	STONE RIPRAP, CLASS A4	SQ YD	7188	2,812	1,071	2,295	1,010			
28200200	FILTER FABRIC	SQ YD	7683	2,812	1,566	2,295	1,010			
28400100	GABIONS	CU YD	247		247					△
30200650	PROCESSING MODIFIED SOILS 12"	SQ YD	39,407	35,442	3965					△
30201500	LIME	TON	993.6	893.6	100.0					
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4'	SQ YD	1999	971	1,028					
31100500	SUB-BASE GRANULAR MATERIAL, TYPE A 6'	SQ YD	9925		9925					
31101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	3407	2,528	879					
35101400	AGGREGATE BASE COURSE, TYPE B	TON	312	193	119					
40200700	AGGREGATE SURFACE COURSE, TYPE A, 8"	SQ YD	510	510						
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	252	227	25					
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	32,129	23,138	8,991					
40600300	AGGREGATE (PRIME COAT)	TON	146	97	49					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2						
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	209	209						
<del>20201400</del>	<del>WATER</del>	<del>UNIT</del>	<del>310</del>	<del>254</del>	<del>56</del>					

NOTE:  
RURAL STA. 942+50.00 TO STA. 1016+00.00  
URBAN STA. 1016+00.00 TO STA. 46+80.05  
\* DENOTES SPECIALTY ITEM

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	

SUMMARY OF QUANTITIES  
SHEET 1 OF 6

DRAWN BY ASB  
CHECKED BY SJK

DATE 8/02

△ Rev. 6-3-05 Rev.