

stef fenmk
3/29/2005
c:\projects\94860d\04301pa.dgn



SUMMARY OF QUANTITIES

FBI	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	*	JEFFERSON	19	4

FBI PROJ. DIST. NO. 7
BLANKET
FBI. AD. PROJECT NO.
CONTRACT NO. 94860
* (41-6,41-6-1)RS-1

SUMMARY OF QUANTITIES			90% FED. 10% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		1000		
60100077	SHOULDER REMOVAL AND REPLACEMENT 11. 1/4"	FOOT	115555	115555		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	15299	15299		
40600300	AGGREGATE (PRIME COAT)	TON	306	306		
40600895	CONSTRUCTING TEST STRIP	EACH	2	2		
40600990	TEMPORARY RAMP	SQ YD	320	320		
44000004	BITUMINOUS SURFACE REMOVAL 1"	SQ YD	102434	102434		
44200553	CLASS A PATCHES, TYPE II, 10 INCH	SQ YD	611	611		
44200557	CLASS A PATCHES, TYPE III, 10 INCH	SQ YD	1090	1090		
44200559	CLASS A PATCHES, TYPE IV, 10 INCH	SQ YD	1899	1899		
44213000	PATCHING REINFORCEMENT	SQ YD	3600	3600		
44213200	SAW CUTS	FOOT	13062	13062		
45000130	RELIEF JOINT 4"	FOOT	192	192		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1721	1721		
48202000	BITUMINOUS SHOULDERS SUPERPAVE	TON	8765	8765		
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	256	256		
60107700	PIPE UNDERDRAINS 6"	FOOT	114743	114743		
60108200	PIPE UNDERDRAINS 6" (SPECIAL)	FOOT	5120	5120		
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	1325	1325		
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4		
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	14	14		
63200310	GUARDRAIL REMOVAL	FOOT	1007.5	1007.5		
63500105	DELINEATORS	EACH	144	144		
63500120	DELINEATOR REMOVAL	EACH	186	186		
64200105	SHOULDER RUMBLE STRIP	FOOT	114743	114743		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	10	10		
67100100	MOBILIZATION	L SUM	1	1		
70100305	TRAFFIC CONTROL AND PROTECTION, STANDARD 701400	L SUM	1	1		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1		
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	37	37		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	20654	20654		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	114744	114744		

SUMMARY OF QUANTITIES			90% FED. 10% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		1000		
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	14343	14343		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3442	3442		
78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	14343	14343		
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	114744	114744		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1436	1436		
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	70	70		
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	14	14		
* X0300247	REMOVE WOOD POST	EACH	3	3		
X0322729	MATERIAL TRANSFER DEVICE	TON	32128	32128		
X0349800	CONCRETE HEADWALL FOR PIPE UNDERDRAIN REMOVAL	EACH	216	216		
X4066530	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N105	TON	12851	12851		
X4066660	POLYMERIZED BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N105	TON	19277	19277		
X4409420	BITUMINOUS SURFACE REMOVAL 3 1/4"	SQ YD	152991	152991		
Z0075310	TIE BARS 3/4"	EACH	676	676		
⊙ Z0076600	TRAINEES	HOUR	500	500		
Z0077800	WOOD POST	EACH	30	30		

⊙ Y080
* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. _____
HORIZ. _____
DATE _____
DRAWN BY _____
CHECKED BY _____