

teasleyck  
3/31/2005  
c:\projects\94905d\04201pa.dgn  
SOQ1

# SUMMARY OF QUANTITIES

FBI NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	(41-7)RS-1	JEFFERSON	98	4

CONTRACT NO. 94905

SUMMARY OF QUANTITIES			90% FED. 10% STATE TOTAL	CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	QUANTITIES	1000		X771-2A 041-0069	X771-2A 041-0080
<del>04100049</del>	<del>SHOULDER REMOVAL AND REPLACEMENT 11' 11'</del>	FOOT	121287	121287			
20400800	FURNISHED EXCAVATION	CU YD	50	50			
25000200	SEEDING, CLASS 2	ACRE	0.1	0.1			
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	9	9			
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	9	9			
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	9	9			
25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.2	0.2			
25100115	MULCH, METHOD 2	ACRE	0.1	0.1			
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	201	201			
35400300	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 8"	SQ YD	29			29	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	27387	27321		48	18
40600300	AGGREGATE (PRIME COAT)	TON	555	547		4	4
40600895	CONSTRUCTING TEST STRIP	EACH	2	2			
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	920	640			280
40600990	TEMPORARY RAMP	SQ YD	320	214		70	36
44000004	BITUMINOUS SURFACE REMOVAL 1"	SQ YD	111757	111757			
44000007	BITUMINOUS SURFACE REMOVAL 2"	SQ YD	364	364			
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	464			464	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	145			145	
44000910	BITUMINOUS CONCRETE REMOVAL (DECK)	SQ YD	1414			1414	
44003100	MEDIAN REMOVAL	SQ FT	582			582	
44200553	CLASS A PATCHES, TYPE II, 10 INCH	SQ YD	1345	1345			
44200557	CLASS A PATCHES, TYPE III, 10 INCH	SQ YD	617	617			
44200559	CLASS A PATCHES, TYPE IV, 10 INCH	SQ YD	1199	1199			
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	464	464			
44213000	PATCHING REINFORCEMENT	SQ YD	3161	3161			
44213200	SAW CUTS	FOOT	16267	16267			
45000130	RELIEF JOINT 4"	FOOT	96	96			
48101200	AGGREGATE SHOULDERS, TYPE B	TON	5430	5430			
48202000	BITUMINOUS SHOULDERS SUPERPAVE	TON	9683	9683			

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SUMMARY OF QUANTITIES

SCALE: VERT.  
HORIZ.  
DATE

DRAWN BY  
CHECKED BY

Rev. 5-31-05