

teesleyck
3/31/2005
c:\projects\94905d\04201pa.dgn
SOQ3

SUMMARY OF QUANTITIES

FAI NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	(41-7)RS-1	JEFFERSON	48	6
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT NO.	
CONTRACT NO. 94905				

SUMMARY OF QUANTITIES			90% FED. 10% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		I000	X771-2A 041-0069	X771-2A 041-0080		
70100900	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316 (SPECIAL)	EACH	1		1			
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	5	1	4		
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1			1		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	19824	19497	327			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	121573	120919	654			
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	13739	13739				
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	1917	1917				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	48	48				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3786	3250	488	48		
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	654		654			
78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	13739	13739				
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	120919	120919				
* 78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	1917	1917				
* 78005180	EPOXY PAVEMENT MARKING - LINE 24"	FOOT	48	48				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1519	1519				
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	71	69		12		
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	16	12		4		
86301010	TERMINAL FACILITY REMOVAL	EACH	1	1				
X0300247	REMOVE WOOD POST	EACH	54	54				
X0320887	POLYMER CONCRETE	CU FT	13.3		8.8	4.5		
X0321468	PLUG EXISTING DECK DRAINS	EACH	8		4	4		
X0322729	MATERIAL TRANSFER DEVICE	TON	30841	30841				
X0322932	SILICONE JOINT SEALER, 1.5"	FOOT	204		144	60		
X0349800	CONCRETE HEADWALL FOR PIPE UNDERDRAIN REMOVAL	EACH	249	249				
X0712400	TEMPORARY PAVEMENT	SQ YD	92		92			
X4066416	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N70	TON	52		24	28		
X4066530	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N105	TON	13637	13637				
X0047300	PROTECTIVE SHIELD	SQ YD	952		672	280		

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ. DATE

DRAWN BY CHECKED BY

Rev. 5-31-05