

SUMMARY OF QUANTITIES

| CODE NUMBER | ITEM DESCRIPTION | UNIT | COUNTY: SALINE | |
|-------------|---|--------|-----------------------|--------|
| | | | RURAL | |
| | | | FUNDING: 100% STATE | |
| | | | WORK TYPE: ROADWAY | |
| | | | CONST TYPE CODE: I000 | |
| | | | TOTAL QUANTITY | |
| 48100500 | AGGREGATE SHOULDERS, TYPE A 6" | SQ YD | | 2,907 |
| 50105220 | PIPE CULVERT REMOVAL | FOOT | | 48 |
| 542A0223 | PIPE CULVERTS, CLASS A, TYPE 1 18" | FOOT | | 38 |
| 542A0235 | PIPE CULVERTS, CLASS A, TYPE 1 30" | FOOT | | 36 |
| 542A0259 | PIPE CULVERTS, CLASS A, TYPE 1 54" | FOOT | | 168 |
| 542D0220 | PIPE CULVERTS, CLASS D, TYPE 1 15" | FOOT | | 173 |
| 542D1060 | PIPE CULVERTS, CLASS D, TYPE 2 15" | FOOT | | 215 |
| 54213450 | END SECTIONS 15" | EACH | | 14 |
| 54213663 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18" | EACH | | 2 |
| 54213675 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30" | EACH | | 1 |
| 54213699 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 54" | EACH | | 6 |
| 54215430 | CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 30" | EACH | | 1 |
| 54248510 | CONCRETE COLLAR | CU YD | | 0.8 |
| 60100060 | CONCRETE HEADWALL FOR PIPE DRAINS | EACH | | 16 |
| 60108800 | PIPE UNDERDRAINS, PERFORATED CORRUGATED STEEL PIPE 8" | FOOT | | 415 |
| 60218400 | MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID | EACH | | 1 |
| 66300105 | CALCIUM CHLORIDE APPLIED | TON | | 63 |
| 66600105 | FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS | EACH | | 6 |
| 66700095 | PERMANENT SURVEY MARKERS | EACH | | 3 |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | | 10 |
| 67100100 | MOBILIZATION | L SUM | | 1 |
| 70100450 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701201 | L SUM | | 1 |
| 70100460 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701306 | L SUM | | 1 |
| 70100500 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701326 | L SUM | | 1 |
| 70100600 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701336 | L SUM | | 1 |
| 70103815 | TRAFFIC CONTROL SURVEILLANCE | CAL DA | | 8 |
| 70300100 | SHORT-TERM PAVEMENT MARKING | FOOT | | 412 |
| 70300220 | TEMPORARY PAVEMENT MARKING - LINE 4" | FOOT | | 14,220 |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SQ FT | | 139 |
| 78001110 | PAINT PAVEMENT MARKING - LINE 4" | FOOT | | 14,220 |
| 78300200 | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL | EACH | | 53 |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

DATE-TIME: FEBRUARY 23, 2005
 *DON-SPEC: 0903502.4603502a01un32