

F.A.P. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
869	FY 06 SEEDING	SALINE	14	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO.: 98916				

### DITCH LINING SCHEDULE

LOCATION STATION TO STATION	EROSION CONTROL BLANKET		HEAVY DUTY EROSION CONTROL BLANKET	
	FOR INFO. ONLY	SQ YD	FOR INFO. ONLY	SQ YD
	WIDTH FOOT		WIDTH FOOT	
IL 34 SALINE COUNTY RURAL				
LT STA 1019+90.0 TO STA 1021+50.0			12.0	213.3
LT STA 1021+50.0 TO STA 1026+00.0	12.0	600.0		
LT STA 1026+00.0 TO STA 1027+45.0	12.0	193.3		
LT STA 1027+55.0 TO STA 1028+50.0	8.0	84.4		
LT STA 1029+28.5 TO STA 1030+50.0			12.0	162.0
LT STA 1030+50.0 TO STA 1032+50.0	12.0	266.7		
LT STA 1033+50.0 TO STA 1035+50.0	12.0	226.7		
LT STA 1035+50.0 TO STA 1037+72.2			12.0	296.3
LT STA 1037+72.2 TO STA 1038+25.0			12.0	70.4
LT STA 1038+25.0 TO STA 1039+00.0	12.0	100.0		
LT STA 1039+00.0 TO STA 1039+58.4			12.0	77.9
LT STA 1039+58.4 TO STA 1040+50.0			12.0	122.1
LT STA 1040+50.0 TO STA 1045+10.0	12.0	600.0		
LT STA 1045+10.0 TO STA 1063+50.0	12.0	2,400.0		
RT STA 1019+90.0 TO STA 1020+25.0				
RT STA 1020+25.0 TO STA 1020+60.0	11.0	42.9		
RT STA 1023+00.0 TO STA 1029+28.5	12.0	838.0		
RT STA 1029+40.0 TO STA 1029+55.0	3.0	5.1		
RT STA 1033+50.0 TO STA 1037+00.0	12.0	466.7		
RT STA 1037+00.0 TO STA 1037+72.2			12.0	96.3
RT STA 1037+47.0 TO STA 1037+72.0	4.0	9.0		
RT STA 1037+72.2 TO STA 1038+75.0	12.0	137.1		
RT STA 1038+00.0 TO STA 1039+00.0	8.0	88.9		
RT STA 1040+75.0 TO STA 1041+50.0	11.0	91.7		
RT STA 1040+75.0 TO STA 1045+10.3	12.0	580.4		
RT STA 1042+00.0 TO STA 1043+00.0	3.0	33.3		
RT STA 1045+10.0 TO STA 1045+55.0	6.0	30.1		
RT STA 1045+10.3 TO STA 1046+00.0			12.0	119.7
RT STA 1046+00.0 TO STA 1063+50.0	12.0	2,306.7		
PROJECT TOTALS:		9,101.0		1,158.0

DATE-TIME: FEBRUARY 4, 2005  
DOC-SPEC: 0002305.d002305sch.m22