

REIL INSTALLATION DETAIL

NOT TO SCALE

NOTES

- 1. VERIFY INSTALLATION & WIRING REQUIREMENTS WITH THE RESPECTIVE REIL MANUFACTURER.
- 2. REILS SHALL BE AIMED AT ANGLE 10 DEGREES VERTICALLY AND TOED OUT 15 DEGREES FROM THE LINE PARALLEL TO THE RUNWAY CENTERLINE.
- 3. REILS SHALL BE PAID FOR UNDER ITEM AR125610.

D35MYGD 0800

TAYLORVILLE MUNICIPAL AIRPORT

E 22/05

NI 02/03/05

NI 02/03/05

IL PROJ.: TAZ-3166

AJP, PROJ.: 3-17-0100-87

Hanson Professional Services Inc.

CONSTRUCT
RUNWAY 9-27
REIL INSTALLATION
DETAIL

5757 of 127 sheets

4FR 22, 2003 11:2/ AW RAW .\ARPORTS\T'VILE\ 828-03RWYGD\ ARPORT\ SHFFTS\ F--503.DWG - WA