

Å.	VAULT	LIGHTING	&	RECEPTACLE	PLAN			
SCALE 1/2"=1'-0"								
T			J 4 FEI	ET				

	LIGHTING FIXTURE SCHEDULE									
fixt. Type		MANUFACTURER & CATALOG NO.	LAMPS/ WATTS	VOLTS	MOUNTING	REMARKS				
F1	GASKETED INDUSTRIAL FLUORESCENT LIGHT FIXTURE,	DMW-2-32-AR-120-	2-32W T8 4100K 59 TOTAL INPUT WATTS			PROVIDE WET LOCATION FITTINGS INSTALLED IN TOP OF FIXTURE.				
F1A	BALLAST CAPABLE OF OPERATING 2 LAMPS FOR 90	DMW-2-32-AR-120- CW-GEB10RS-WLF	2-32W TB 4100K 59 TOTAL INPUT WATTS	120		PROVIDE WET LOCATION FITTINGS INSTALLED IN TOP OF FIXTURE.				
F2	COMPACT FLUORESCENT WALL-PAK, ONE PIECE INJECTION MOLDED UV STABILIZED POLYCARBONATE HOUSING, HIGH PERFORMANCE SPECULAR ANDDIZED SEGMENTED REFLECTOR, ONE PIECE HIGH TEMPURATURE SILCOME GASKET, MEDIUM BRONZE FINISH, HIGH POWERFACTOR ELECTRONIC BALLAST WITH LESS THAN OR EQUAL TO 10% THD, UL LISTED FOR WET LOCATIONS, FUSED.		1-42W TRT 4100K 47 TOTAL INPUT WATTS	120	SURFACE TO WALL ABOVE EXTERIOR DOOR APPROXIMATELY 4 INCHES ABOVE TOP OF DOOR FRAME.	CONNECT TO WALL SWITCH LOCATED ON THE INSIDE OF THE BUILDING.				

NOTE 15 AMP & 20 AMP BRANCH CIRCUITS FOR LIGHTING & RECEPTACLES SHALL USE #12 AWG THWN (MIN.).

TAYLORVILLE MUNICIPAL AIRPORT TAYLORVILLE, ILLINOIS

HANSON

VAULT LIGHTING AND RECEPTACLE PLAN CONSTRUCT RUNWAY 9-27

65