

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				STATE FUNDS	
				100% STATE	
				STRUCTURE	
				0040	
				RURAL	
67100100	MOBILIZATION	L SUM	1		1
70100820	TRAFFIC CONTROL AND PROTECTION, STANDARD, 701451	L SUM	1		1
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	20		20
X0325265	REMOVE ELECTRIC SERVICE	EACH	2		2
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	500		500
X8040115	ELECTRICAL CONNECTION TO SIGN STRUCTURE (TRUSS TYPE)	EACH	2		2
X7240195	REMOVE EXISTING SIGN PANEL	EACH	2		2
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	2		2
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	2		2
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	12.2		12.2
73302170	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE II-C-A (36" X 5'-6")	FOOT	60		60
73301840	OVERHEAD SIGN STRUCTURE WALKWAY, CANTILEVER, TYPE A	FOOT	28		28
X7330085	FURNISH AND INSTALL SAFETY CHAIN	EACH	4		4
X5090100	FURNISH AND INSTALL HANDRAIL	FOOT	28		28
X7200095	FURNISH AND ERECT SIGN PANEL	SQ FT	168		168
X0321984	SIGN LIGHTING UNIT COMPLETE	EACH	2		2

EACH 2 2 

Rev. 6-9-11