* SPECIALTY ITEM

SUMMARY OF QUANTITIES				CONSTRUCTION CODE																								
CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL	0003	0008	0021																			0031	0040		0043
				1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25
50200100	STRUCTURE EXCAVATION	CU YD	2,763		2,763																							
50300225	CONCRETE STRUCTURES	CU YD	798.3		798.3																							
50300255	CONCRETE SUPERSTRUCTURE	CU YD	3,480.5		3,480.5																							
50300260	BRIDGE DECK GROOVING	SQ YD	7,195		7,195																							
50300300	PROTECTIVE COAT	SQ YD	7,378		7,378																							
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1,111,880		1,111,880																							
50800515	BAR SPLICERS	EACH	2,003		2,003																							
51200959	FURNISHING METAL SHELL PILES 14" X 0.312"	FOOT	20,006		20,006																							
51202305	DRIVING PILES	FOOT	20,006		20,006																							
51203200	TEST PILE METAL SHELLS	EACH	14		14																							
Z0026407	TEMPORARY SHEET PILING	SQ FT	6,600	6,600																								
51500100	NAME PLATES	EACH	1		1																							
52000110	PREFORMED JOINT STRIP SEAL	FOOT	688.5		688.5																							
	~~BOX CULVERT END SECTIONS~~	~~CU YD~~	~~30.3~~	~~30.3~~																								
54010404	PRECAST CONCRETE BOX CULVERTS 4' X 4'	FOOT	117.5	117.5																								
54010606	PRECAST CONCRETE BOX CULVERTS 6' X 6'	FOOT	119.0	119.0																								
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	16	16																								
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	27	27																								
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	3	3																								
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	4	4																								
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	2	2																								
54213693	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 48"	EACH	2	2																								
54213717	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 72"	EACH	1	1																								
54214512	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 27"	EACH	1	1																								
X5428800	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS	CU YD	52.7	52.7																								
54247150	GRATING FOR CONCRETE FLARED END SECTION 30"	EACH	4	4																								
54247170	GRATING FOR CONCRETE FLARED END SECTION 36"	EACH	2	2																								

PATRICK ENGINEERING INC.
4970 VARSITY DRIVE
LISLE, IL 60532
patrickengineering.com
PATRICK ENGINEERING

USER NAME = Rdwy_Lisle	DESIGNED -	REVISED -
PLOT CONFIG= PDF(Grey_Large).plt	DRAWN -	REVISED -
PLOT SCALE = 1:50	CHECKED -	REVISED -
PLOT DATE = 12/3/2010	DATE - 12/3/2010	REVISED -

Illinois Department of Transportation

ILLINOIS ROUTE 53
SUMMARY OF QUANTITIES

SCALE: NA | SHEET SOQ-04 OF 20 | STA. | TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2578	532B	DUPAGE	781	7

CONTRACT NO. 60477

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT

Rev.

q:\idot\9356_a0_(1153)\drawings\cadd sheets\D19139797-sht-SOQ_004-023.dgn