* SPECIALTY ITEM

	SUMMARY OF QUANTITIES		UNIT	TOTAL (URBAN)	CONSTRUCTION CODE																								
	CODE NO.	ITEM DESCRIPTION			0003	0008	0021																		0021	0040		0043
					1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	21A	23	24	25
*	72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	2,724	2,724																								
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3,424	3,424																								
*	78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	237	237																								
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	123	123																								
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	110	110																								
*	78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	6,750	6,750																								
*	78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	55,870	55,870																								
*	78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	32,466	32,466																								
*	78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	933	933																								
*	78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	1,922	1,922																								
*	78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	2,657	2,657																								
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2,478	2,478																								
*	78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	72	72																								
*	78200410	GUARDRAIL MARKERS, TYPE A	EACH	33	33																								
*	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	8	8																								
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	31,466	31,466																								
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	852	852																								
*	80400100	ELECTRIC SERVICE INSTALLATION	EACH	2																						2			
*	80400200	ELECTRIC UTILITY SERVICE CONNECTION	LSUM	1																						1			
*	81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	21,845			492	752	504	566	796	499	871	848	552	572	281	254	195		400	569	6249	7445					
*	81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	561			5	15	13	18	32	35	16	36	54	46	50	22	112		101	6							
*	81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	822			116	33	50	17	78	53	87	43	69	78	70	40	29		44	15							
*	81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	891			50	25	25	137	263	25	45	29	25	25	77	115			25	25							
*	81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	5,026			202	618	188	123	715	388	130	501	172	144	163				72	70	988	552					
*	81018600	CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL	FOOT	75																		75							
*	81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	4,780							65														1565	3150			
*	81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	6,662			186	984	375	382	798	477	478	488	278	500	458	462	191		303	302							
*	81100600	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	30																				30					