

40603310 HOT MIX ASPHALT SURFACE COURSE, MIX "C", N50		
STATION TO STATION	TON	
RESIDENTIAL	375.09	
COMMERCIAL	269.92	
TOTAL	646	

40603340 HOT MIX ASPHALT SURFACE COURSE, MIX "D", N70			
LOCATION	STATION TO STATION	TON	
MORELAND AVE.	39+74.72 TO 40+33.03	12.7	
NORDIC RD.	08+01.45 TO 13+00.00	179.6	
BRYN MAWR	17+04.03 TO 18+81.53	54.3	
ARDMORE	12+33.16 TO 14+04.62	62.4	
EAST THORNDALE	17+45.50 TO 20+13.11	105.4	
WEST THORNDALE	11+00.82 TO 12+45.64	46.6	
NORWOOD	245+43.58 TO 246+34.76	31.6	
TOTAL		493	

40603595 POLYMERIZED HOT MIX ASPHALT SURFACE COURSE, MIX "F", N90			
LOCATION	STATION TO STATION	TON	
ARMY TRAIL RD.	07+44.61 TO 11+16.03	327.9	
IRVING PARK RD.	04+06.69 TO 06+21.53	125.8	
TOTAL		454.0	

42000501 PORTLAND CEMENT CONCRETE 10 INCH (JOINTED)			
IL RTE 53			
35+95.11	TO	37+66.47	677.5
35+66.56	TO	35+95.17	204.9
35+95.17	TO	37+69.30	498.2
37+69.30	TO	39+79.14	582.9
37+66.47	TO	39+52.55	764.5
38+49.16	TO	39+49.22	237.4
39+52.30	TO	41+39.22	727.7
39+76.09	TO	40+04.87	265.0
39+47.21	TO	39+78.16	23.1
40+04.87	TO	40+89.68	393.2
40+43.00	TO	41+38.47	276.4
40+43.00	TO	42+84.41	321.9
41+39.22	TO	42+94.48	535.3
41+38.47	TO	47+37.63	1664.3
42+94.48	TO	44+50.48	849.3
42+84.41	TO	44+39.69	103.0
44+50.48	TO	48+97.73	3031.2
44+90.28	TO	45+56.22	83.7
45+56.22	TO	46+22.16	83.7
47+37.63	TO	48+72.39	374.3
47+37.63	TO	49+04.36	102.9
48+32.62	TO	51+19.20	3316.4
49+04.36	TO	49+55.72	96.7
50+94.23	TO	54+41.17	1888.0
51+19.20	TO	52+52.52	436.5
51+53.94	TO	54+41.18	383.0
52+52.50	TO	57+52.91	1389.7
54+41.13	TO	55+95.50	737.8
54+41.17	TO	55+95.50	102.6
55+95.47	TO	57+52.24	541.0
57+52.22	TO	58+49.42	260.7
58+49.40	TO	59+82.34	1132.5
57+52.79	TO	58+79.54	349.2
59+82.28	TO	67+36.17	5122.1
67+36.04	TO	70+37.04	1905.8
67+36.17	TO	68+38.36	222.0
70+36.99	TO	71+52.77	1475.1
71+50.51	TO	74+05.27	1606.3
74+05.27	TO	75+82.33	1121.4
74+05.27	TO	75+04.31	321.7
75+82.33	TO	76+71.85	567.0
75+82.33	TO	76+71.85	141.3
76+71.85	TO	82+02.05	3357.9
82+02.05	TO	82+93.29	165.6
82+02.05	TO	87+75.44	3631.5
87+75.44	TO	88+97.15	770.4
87+75.44	TO	88+63.70	242.7
88+97.02	TO	95+86.67	4367.0
88+97.02	TO	90+10.22	250.0
95+86.54	TO	105+32.68	5991.5
95+86.54	TO	97+06.96	314.5
105+32.60	TO	116+02.45	6500.5
111+10.18	TO	112+66.18	641.1
112+66.11	TO	114+22.30	954.0
113+69.59	TO	114+90.84	277.9
116+02.42	TO	117+37.80	443.3
114+22.21	TO	117+10.93	2011.2
117+10.83	TO	118+71.28	1403.7
117+93.27	TO	120+22.85	3063.3
119+89.30	TO	127+98.66	3830.0
119+71.78	TO	127+98.66	2500.4
127+97.85	TO	129+63.94	1515.9
129+63.94	TO	143+14.23	9751.8

42000501 PORTLAND CEMENT CONCRETE 10 INCH (JOINTED)			
IL RTE 53			
135+93.42	TO	136+92.63	302.2
139+19.13	TO	140+20.29	164.3
139+09.96	TO	140+09.26	416.6
143+14.13	TO	144+43.72	934.9
144+43.54	TO	147+44.40	2449.3
147+44.29	TO	149+86.60	4444.7
149+86.12	TO	151+62.72	1506.8
151+62.24	TO	153+18.72	1231.3
153+18.32	TO	157+28.41	2958.8
170+12.31	TO	172+15.86	2609.1
172+15.86	TO	177+51.96	4196.7
177+51.96	TO	179+55.68	2252.0
179+55.68	TO	183+80.31	3066.8
183+80.31	TO	184+79.35	1003.6
184+79.35	TO	187+17.37	1719.1
187+17.37	TO	190+26.46	2232.2
190+26.46	TO	192+66.25	1731.8
192+66.25	TO	193+95.77	462.5
192+66.25	TO	193+95.53	464.4
193+95.43	TO	197+79.04	1108.3
193+95.45	TO	195+08.26	324.7
195+07.68	TO	197+79.09	1287.3
197+77.12	TO	200+75.42	1931.5
197+79.04	TO	200+85.73	960.6
200+41.53	TO	202+87.54	3711.1
202+58.52	TO	205+38.83	1738.1
202+56.71	TO	206+85.29	1319.8
205+20.20	TO	206+89.28	755.6
207+25.45	TO	207+25.45	589.4
207+68.67	TO	210+04.28	653.5
207+64.42	TO	210+26.60	1021.3
210+05.63	TO	211+95.05	973.6
210+04.00	TO	211+95.24	584.0
211+94.80	TO	213+84.82	2599.0
213+84.43	TO	222+12.21	6121.9
222+12.21	TO	224+10.05	2167.8
224+10.05	TO	227+82.10	2915.2
227+74.39	TO	229+62.85	2646.0
229+54.63	TO	237+19.79	5958.0
237+10.36	TO	239+13.16	2607.7
239+09.21	TO	240+30.00	990.1
246+40.00	TO	250+34.81	3653.7
ARMY TRAIL ROAD			
16+12.85	TO	21+81.10	3676.8
16+71.84	TO	21+81.10	2073.9
18+97.02	TO	19+84.40	145.8
11+16.03	TO	14+62.72	2084.3
10+78.83	TO	14+80.82	3069.0
09+32.24	TO	10+95.47	1010.3
LAKE STREET			
21+88.95	TO	28+21.85	3688.7
22+00.17	TO	28+21.85	2324.2
15+68.05	TO	19+86.06	2417.8
15+68.05	TO	19+85.82	1814.2
15+68.77	TO	16+68.59	229.7
12+74.60	TO	15+68.05	2013.5
IRVING PARK ROAD			
18+30.51	TO	25+00.00	2772.5
16+22.35	TO	25+00.00	2877.4
15+91.52	TO	18+30.81	1605.5
06+21.54	TO	14+17.58	3745.9
06+21.54	TO	13+79.01	2219.6
09+88.99	TO	10+81.69	200.0

42000501 PORTLAND CEMENT CONCRETE 10 INCH (JOINTED)			
BRYN MAWR AVENUE			
12+87.42	TO	14+08.42	511.3
15+92.73	TO	17+04.03	467.7
ARDMORE AVENUE			
16+03.16	TO	18+00.00	752.4
THORNDALE AVENUE			
15+72.36	TO	17+45.50	1084.0
12+45.64	TO	14+22.27	856.6
NORWOOD AVENUE			
11+00.00	TO	14+24.36	1957.7
15+74.33	TO	16+22.59	308.2
16+22.58	TO	16+81.50	336.8
TOTAL			211911

42300200 PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH			
LOCATION	STATION	LT/RT	SQ YD
IL ROUTE 53	35+61.00	LT	45.0
IL ROUTE 53	36+26.00	RT	35.1
IL ROUTE 53	36+44.00	LT	56.7
IL ROUTE 53	41+23.00	RT	66.8
IL ROUTE 53	42+04.00	RT	53.6
IL ROUTE 53	53+52.00	RT	6.3
IL ROUTE 53	54+06.00	RT	3.5
IL ROUTE 53	61+00.00	RT	32.8
IL ROUTE 53	61+39.00	RT	18.7
IL ROUTE 53	61+37.58	RT	8.3
IL ROUTE 53	62+46.15	RT	17.5
IL ROUTE 53	62+46.15	RT	15.7
IL ROUTE 53	86+00.00	RT	44.8
IL ROUTE 53	86+00.00	RT	17.0
IL ROUTE 53	98+92.00	RT	47.4
IL ROUTE 53	98+97.00	RT	13.4
IL ROUTE 53	122+26.00	LT	57.4
IL ROUTE 53	124+24.00	RT	52.9
IL ROUTE 53	124+40.00	LT	82.9
IL ROUTE 53	125+40.00	RT	104.4
IL ROUTE 53	127+98.00	RT	57.4
IL ROUTE 53	193+38.00	LT	45.6
TOTAL			884




PATRICK ENGINEERING INC.
4970 VARSITY DRIVE
LISLE, IL 60532
patrickengineering.com

USER NAME = Rdwj.Lisle
PLOT CONFIG = PDF(Greg_Large).plt
PLOT SCALE = 1:50
PLOT DATE = 12/3/2010

DESIGNED -
DRAWN -
CHECKED -
DATE - 12/3/2010

REVISED -
REVISED -
REVISED -
REVISED -



ILLINOIS ROUTE 53
SCHEDULE OF QUANTITIES

SCALE: NA SHEET SCH-03 OF 18 STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2578	532B		781	26
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO.	