

42300400 PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH			
LOCATION	STATION	LT/RT	SQ YD
IL RTE 53	47+21.00	RT	64.6
IL RTE 53	52+51.00	RT	44.5
IL RTE 53	57+00.00	RT	62.4
IL RTE 53	96+47.00	RT	74.2
IL RTE 53	96+45.96	RT	30.6
IL RTE 53	107+33.00	LT	14.1
IL RTE 53	116+54.00	RT	31.1
IL RTE 53	117+11.00	LT	123.1
IL RTE 53	121+15.00	LT	70.1
IL RTE 53	121+57.00	RT	89.5
IL RTE 53	199+50.00	RT	75.6
IL RTE 53	203+08.00	RT	79.8
IL RTE 53	204+85.00	RT	36.2
IL RTE 53	206+04.00	RT	32.1
IL RTE 53	234+01.36	LT	30.5
IL RTE 53	234+04.00	LT	49.5
IL RTE 53	236+11.00	LT	43.8
IL RTE 53	235+96.13	LT	25.9
IL RTE 53	236+22.49	LT	25.9
ARMY TRAIL RD.	12+00.00	RT	71.5
ARMY TRAIL RD.	17+20.86	LT	27.0
ARMY TRAIL RD.	17+77.17	LT	27.0
ARMY TRAIL RD.	17+59.00	RT	69.4
LAKE ST.	18+55.00	LT	67.3
LAKE ST.	19+02.00	RT	90.1
LAKE ST.	23+48.00	RT	36.5
LAKE ST.	23+85.00	LT	41.0
IRVING PARK RD.	16+64.00	LT	49.2
IRVING PARK RD.	17+28.00	RT	70.6
IRVING PARK RD.	17+58.00	LT	17.0
THORNDALE AVE.	11+65.00	RT	95.7
THORNDALE AVE.	12+55.00	RT	61.7
THORNDALE AVE.	16+50.00	LT	61.2
THORNDALE AVE.	19+48.44	LT	130.3
TOTAL			1919

42400300 PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH		
STATION	TO STATION	SQ YD
IL RTE 53		
64+70.17	TO 64+99.26	120.4
62+28.56	TO 62+63.73	254.1
66+19.18	TO 66+50.05	129.4
68+65.00	TO 68+91.86	109.3
73+39.09	TO 73+71.57	137.4
73+99.67	TO 74+62.18	287.6
76+71.54	TO 76+98.75	174.3
78+09.00	TO 78+36.42	176.5
79+34.96	TO 79+68.02	232.8
77+91.47	TO 78+59.47	315.0
79+03.17	TO 79+65.54	286.9
80+17.76	TO 80+86.16	317.0
81+59.05	TO 81+94.87	154.1
82+10.09	TO 82+43.95	144.3
83+13.47	TO 83+46.08	138.0
85+87.39	TO 86+21.51	243.4
94+63.65	TO 94+93.37	199.5
98+84.37	TO 99+09.63	208.9
206+35.76	TO 206+52.83	62.1
TOTAL		5911.0

42400500 PORTLAND CEMENT CONCRETE SIDEWALK SPECIAL		
STATION	TO STATION	SQ YD
IL RTE 53		
202+40.44	TO 203+77.64	1130.8
204+12.64	TO 204+41.02	149.7
204+81.77	TO 205+96.98	759.1
206+37.02	TO 206+56.09	104.1
201+99.82	TO 202+86.78	721.1
IRVING PARK		
13+33.47	TO 13+79.08	302.2
15+95.97	TO 16+43.86	317.2
16+79.78	TO 17+37.08	367.7
TOTAL		3852.0

42400410 PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH		
STATION	TO STATION	SQ YD
IL RTE 53		
47+74.62	TO 48+34.61	371.8
51+27.39	TO 51+88.24	526.6
52+30.04	TO 52+87.61	453.3
54+49.57	TO 55+12.73	408.5
57+01.37	TO 57+48.37	210.0
56+84.61	TO 57+24.47	322.3
62+97.96	TO 63+33.05	253.5
63+70.48	TO 64+03.73	235.3
64+28.40	TO 64+65.53	272.2
65+04.79	TO 65+67.80	473.8
66+48.09	TO 66+88.89	310.1
96+15.02	TO 96+76.90	519.9
101+07.92	TO 101+63.53	268.6
101+63.47	TO 101+76.71	56.6
104+98.25	TO 105+35.65	168.4
106+11.97	TO 106+23.34	113.7
107+17.10	TO 107+48.49	190.9
116+78.21	TO 117+37.37	366.4
116+22.82	TO 116+82.82	500.0
199+08.41	TO 199+58.82	304.3
199+71.44	TO 200+30.19	363.0
199+24.93	TO 199+75.20	310.4
202+79.77	TO 203+38.51	362.9
203+70.63	TO 204+19.63	294.0
204+34.02	TO 204+88.77	334.2
204+62.46	TO 205+11.46	294.0
205+81.04	TO 206+27.22	274.3
205+89.98	TO 206+44.02	330.2
209+85.65	TO 210+44.61	363.7
233+89.85	TO 234+12.55	108.6
235+89.46	TO 236+04.44	64.6
236+14.19	TO 236+29.17	64.6
221+86.57	TO 222+27.84	187.8
ARMY TRAIL ROAD		
17+39.14	TO 17+99.14	371.3
LAKE STREET		
23+30.66	TO 23+79.66	390.9
23+59.15	TO 24+09.57	304.0
26+18.44	TO 26+65.84	288.7
IRVING PARK ROAD		
10+74.04	TO 11+25.12	309.4
10+96.48	TO 11+22.37	124.7
11+63.88	TO 12+23.89	371.0
12+53.25	TO 12+90.62	218.5
12+32.55	TO 12+91.50	364.6
13+00.80	TO 13+38.81	223.7
13+19.73	TO 13+72.67	321.4
16+38.11	TO 16+85.54	287.5
16+96.05	TO 17+56.04	371.8
17+31.65	TO 17+80.65	299.8
18+18.92	TO 18+67.40	290.4
21+12.98	TO 21+71.49	649.9
21+23.51	TO 21+71.84	289.4
22+03.43	TO 22+54.43	308.3
BRYN MAWR AVENUE		
17+48.66	TO 17+97.66	304.9
TOTAL		15769.00

44000100 PAVEMENT REMOVAL			
STATION	TO STATION	SQ YD	
IL RTE 53			
35+66.56	TO 40+84.91	4460.2	
40+78.39	TO 45+06.95	1093.9	
40+49.23	TO 45+27.01	1721.5	
45+03.88	TO 49+25.48	2344.4	
44+86.50	TO 49+28.46	1194.7	
48+99.31	TO 50+95.52	3011.8	
50+68.39	TO 55+19.66	2232.3	
50+33.86	TO 55+12.44	1359.4	
54+94.71	TO 59+06.29	1151.2	
55+04.39	TO 59+05.94	1106.0	
58+89.68	TO 59+80.30	825.4	
59+78.37	TO 64+11.57	2691.8	
63+97.54	TO 68+63.34	2176.7	
68+61.83	TO 71+58.28	2062.0	
71+44.00	TO 76+76.44	3319.3	
76+73.62	TO 81+86.94	2046.3	
81+84.41	TO 83+52.64	998.7	
83+43.34	TO 87+95.04	1328.0	
87+93.21	TO 90+06.73	1491.0	
89+97.17	TO 98+48.98	2876.0	
98+39.69	TO 99+63.50	776.6	
103+02.12	TO 109+48.97	1560.0	
99+50.34	TO 103+06.10	961.1	
103+02.12	TO 109+28.76	1733.3	
108+91.25	TO 110+05.79	482.1	
109+91.34	TO 118+28.76	3432.9	
109+86.98	TO 118+39.09	2274.6	
117+75.81	TO 119+93.29	2114.0	
119+45.73	TO 128+75.10	3844.5	
119+18.68	TO 128+74.58	2457.2	
128+73.90	TO 129+52.74	521.5	
129+51.92	TO 136+10.51	2035.8	
136+05.82	TO 140+17.82	2294.2	
140+05.59	TO 148+61.74	3799.2	
148+26.95	TO 149+33.04	802.3	
148+93.18	TO 157+28.41	3649.9	
170+12.79	TO 172+40.28	2474.2	
172+20.70	TO 178+01.76	3022.0	
177+97.41	TO 179+49.24	1345.7	
179+49.16	TO 198+26.91	6915.5	
198+25.68	TO 201+25.76	2031.6	
201+18.50	TO 202+00.79	1149.8	
202+00.79	TO 206+87.15	3321.5	
206+86.87	TO 207+63.45	531.7	
207+62.98	TO 212+63.71	3087.9	
212+63.09	TO 213+15.62	661.1	
213+14.60	TO 223+70.62	6471.3	
223+66.69	TO 228+33.86	2635.8	
228+92.74	TO 237+83.90	5370.7	
237+83.85	TO 238+30.61	632.4	
238+30.38	TO 244+63.83	3996.8	
245+13.98	TO 250+34.81	3963.9	
244+62.13	TO 245+15.41	753.6	

44000100 PAVEMENT REMOVAL			
STATION	TO STATION	SQ YD	
ARMY TRAIL RD.			
09+32.17	TO 14+65.52	5120.9	
15+81.02	TO 21+81.10	5354.8	
LAKE ST.			
12+87.08	TO 19+83.65	2379.4	
12+74.69	TO 20+78.29	3981.5	
21+51.04	TO 28+27.86	5900.3	
NORDIC RD.			
12+99.98	TO 14+46.05	739.0	
15+41.85	TO 17+52.19	1016.6	
IRVING PARK RD.			
201+25.76	TO 203+71.55	5026.2	
199+32.14	TO 201+90.10	6377.3	
BRYN MAWR AVE.			
12+87.42	TO 14+51.03	591.5	
15+50.10	TO 17+04.03	569.7	
ARDMORE AVE.			
14+02.49	TO 14+56.06	232.8	
15+53.30	TO 17+98.63	918.3	
THORNDALE AVE.			
12+48.56	TO 14+43.37	753.9	
15+61.25	TO 17+55.37	713.5	
NORWOOD AVE.			
244+63.83	TO 247+65.85	1358.0	
244+62.13	TO 245+17.38	599.8	
TOTAL			162984