


IRVING PARK RD EARTHWORK			UNDERCUT FOR PGE REPLACEMENT			REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (6" OF TOPSOIL REMOVAL)			EARTH EXCAVATION (CUT)			EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (15%)			EMBANKMENT (FILL)			EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)			
STATION	TO	STATION	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD	
4+00.00	TO	5+00.00	0.00	0.00	0.00	19.78	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	50.69	0.00	0.00	0.00	-50.69	0.00
5+00.00	TO	6+00.00	0.00	0.00	0.00	32.68	0.00	0.00	0.00	0.00	27.81	0.00	23.64	0.00	1.26	57.83	0.00	-1.26	-34.19	0.00	0.00
6+00.00	TO	6+51.55	0.00	0.00	0.00	9.42	0.00	0.00	0.00	0.00	74.12	0.00	63.00	0.00	0.65	4.98	0.00	-0.65	58.02	0.00	0.00
6+51.55	TO	6+73.40	0.00	0.00	0.00	5.84	0.00	0.00	0.00	0.00	39.45	0.00	33.53	0.00	0.00	0.55	0.00	0.00	32.98	0.00	0.00
6+73.40	TO	7+00.00	0.00	0.00	0.00	15.79	0.00	0.00	0.00	0.00	55.53	0.00	47.20	0.00	0.00	7.17	0.00	0.00	40.03	0.00	0.00
7+00.00	TO	8+00.00	0.00	0.00	0.00	78.38	0.00	0.00	0.00	0.00	265.12	0.00	225.35	0.00	0.00	94.56	0.00	0.00	130.80	0.00	0.00
8+00.00	TO	9+00.00	0.00	0.00	0.00	77.59	0.00	0.00	0.00	0.00	251.98	0.00	214.18	0.00	0.00	122.67	0.00	0.00	91.52	0.00	0.00
9+00.00	TO	9+73.76	0.00	0.00	0.00	57.28	0.00	0.00	0.26	205.14	0.00	0.22	174.37	0.00	0.72	66.18	0.00	-0.50	108.19	0.00	0.00
9+73.76	TO	10+00.00	0.00	0.00	0.00	18.36	0.00	0.00	0.09	81.31	0.00	0.08	69.11	0.00	0.47	13.76	0.00	-0.40	55.35	0.00	0.00
10+00.00	TO	10+43.73	0.00	0.00	0.00	19.33	0.00	0.00	0.77	140.04	0.00	0.65	119.04	0.00	0.66	7.78	0.00	0.00	111.25	0.00	0.00
10+43.73	TO	11+05.00	0.00	0.00	0.00	52.61	0.00	0.00	2.74	179.78	0.00	2.33	152.81	0.00	0.87	0.00	0.00	1.46	152.81	0.00	0.00
11+05.00	TO	12+00.00	0.00	0.00	0.00	105.60	0.00	0.00	4.40	266.55	0.00	3.74	226.56	0.00	2.23	8.76	0.00	1.51	217.80	0.00	0.00
12+00.00	TO	12+72.73	0.00	0.00	0.00	100.73	0.00	0.00	3.05	176.75	0.00	2.59	150.24	0.00	2.49	6.71	0.00	0.10	143.53	0.00	0.00
12+72.73	TO	13+00.00	0.00	0.00	0.00	40.63	0.00	0.00	2.31	58.39	0.00	1.96	49.63	0.00	0.50	27.38	0.00	1.46	22.26	0.00	0.00
13+00.00	TO	13+19.16	0.00	0.00	0.00	19.94	0.00	0.00	1.81	51.67	0.00	1.54	43.92	0.00	0.13	23.20	0.00	1.40	20.72	0.00	0.00
13+19.16	TO	13+42.36	0.00	0.00	0.00	26.35	0.00	0.00	1.50	75.93	0.00	1.27	64.54	0.00	0.30	4.80	0.00	0.98	59.74	0.00	0.00
13+42.36	TO	13+79.01	0.00	0.00	0.00	44.48	0.00	0.00	2.72	165.13	0.00	2.31	140.36	0.00	0.36	8.47	0.00	1.95	131.89	0.00	0.00
13+79.01	TO	16+22.66	0.00	0.00	0.00	270.88	0.00	0.00	63.24	1126.66	0.00	53.75	957.66	0.00	0.92	78.26	0.00	52.83	879.40	0.00	0.00
16+22.66	TO	16+62.47	0.00	0.00	0.00	43.87	0.00	0.00	13.15	149.23	0.00	11.18	126.85	0.00	0.00	3.59	0.00	11.18	123.26	0.00	0.00
16+62.47	TO	17+00.00	0.00	0.00	0.00	36.82	0.00	0.00	11.40	137.37	0.00	9.69	116.76	0.00	0.00	0.00	0.00	9.69	116.76	0.00	0.00
17+00.00	TO	17+24.84	0.00	0.00	0.00	25.10	0.00	0.00	10.37	75.31	0.00	8.81	64.01	0.00	0.00	3.32	0.00	8.81	60.69	0.00	0.00
17+24.84	TO	17+54.35	0.00	0.00	0.00	34.14	0.00	0.00	14.00	75.73	0.00	11.90	64.37	0.00	0.00	3.95	0.00	11.90	60.42	0.00	0.00
17+54.35	TO	18+00.00	0.00	0.00	0.00	44.04	0.00	0.00	19.30	129.37	0.00	16.41	109.96	0.00	0.00	15.50	0.00	16.41	94.46	0.00	0.00
18+00.00	TO	18+44.00	0.00	0.00	0.00	32.24	0.00	0.00	13.67	116.10	0.00	11.62	98.69	0.00	0.00	32.68	0.00	11.62	66.01	0.00	0.00
18+44.00	TO	19+00.00	0.00	0.00	0.00	43.75	0.00	0.00	10.44	150.75	0.00	8.87	128.14	0.00	0.60	66.15	0.00	8.28	61.98	0.00	0.00
19+00.00	TO	20+00.00	0.00	0.00	0.00	88.06	0.00	0.00	8.94	260.54	0.00	7.60	221.46	0.00	1.78	159.05	0.00	5.83	62.41	0.00	0.00
20+00.00	TO	21+00.00	0.00	107.87	0.00	67.75	0.00	0.00	9.87	194.10	0.00	8.39	164.99	0.00	0.71	90.47	0.00	7.68	74.51	0.00	0.00
21+00.00	TO	21+43.46	0.00	94.68	0.00	12.21	0.00	0.00	3.48	83.27	0.00	2.96	70.78	0.00	0.76	4.02	0.00	2.19	66.77	0.00	0.00
21+43.46	TO	22+00.00	0.00	136.74	0.00	13.18	0.00	0.00	4.17	115.57	0.00	3.55	98.23	0.00	0.99	15.28	0.00	2.55	82.96	0.00	0.00
22+00.00	TO	22+32.42	0.00	85.54	0.00	16.09	0.00	0.00	3.45	67.90	0.00	2.93	57.72	0.00	0.00	11.34	0.00	2.93	46.38	0.00	0.00
22+32.42	TO	23+00.00	0.00	178.39	0.00	36.07	0.00	0.00	7.47	153.87	0.00	6.35	130.79	0.00	0.00	20.71	0.00	6.35	110.08	0.00	0.00
23+00.00	TO	24+00.00	0.00	261.66	0.00	42.33	0.00	0.00	6.23	243.88	0.00	5.30	207.30	0.00	2.28	40.37	0.00	3.02	166.93	0.00	0.00
24+00.00	TO	25+00.00	0.00	129.67	0.00	31.12	0.00	0.00	4.15	236.52	0.00	3.53	201.04	0.00	3.41	36.13	0.00	0.12	164.91	0.00	0.00
TOTALS =			0.00	994.55	0.00	1562.44	0.00	0.00	222.97	5430.86	0.00	189.52	4616.23	0.00	22.09	1086.30	0.00	167.43	3529.92	0.00	

PATRICK ENGINEERING INC.
4970 VARSITY DRIVE
LISLE, IL 60532
patrickengineering.com

USER NAME = Rdwj.Lisle
PLOT CONFIG = POF(Greg.Large).plt
PLOT SCALE = 1:50
PLOT DATE = 12/3/2010

DESIGNED -
DRAWN -
CHECKED -
DATE - 12/3/2010

REVISED -
REVISED -
REVISED -
REVISED -



IRVING PARK EARTHWORK SCHEDULE
SCALE: 1"=50' SHEET SCH-13 OF 18 STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2578	532B	DUPAGE	781	36
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
		CONTRACT NO.		