



BRYN MAWR AVE EARTHWORK			REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (6" OF TOPSOIL REMOVAL)			EARTH EXCAVATION (CUT)			EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (15%)			EMBANKMENT (FILL)			EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)		
STATION	TO	STATION	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD
12+00.00	TO	12+77.56	11.37	0.00	0.00	7.10	0.00	0.00	6.03	0.00	0.00	2.20	0.00	21.11	3.83	0.00	-21.11
12+77.56	TO	13+00.00	6.16	0.00	0.00	13.29	0.00	18.32	11.30	0.00	15.58	0.00	0.00	6.79	11.30	0.00	8.79
13+00.00	TO	14+00.00	78.95	0.00	0.00	119.72	0.00	404.10	101.76	0.00	343.49	0.00	0.00	31.88	101.76	0.00	311.61
14+00.00	TO	16+00.00	152.13	0.00	0.00	236.04	518.52	644.89	200.63	440.74	548.16	0.00	0.00	3.28	200.63	440.74	544.88
16+00.00	TO	17+00.00	56.19	0.00	0.00	130.17	333.07	0.00	110.64	283.11	0.00	0.00	19.16	0.00	110.64	263.96	0.00
17+00.00	TO	17+73.62	52.45	0.00	0.00	77.21	81.56	0.00	65.62	69.33	0.00	0.00	22.30	0.00	65.62	47.03	0.00
17+73.62	TO	18+00.00	15.39	0.00	0.00	16.29	20.01	0.00	13.85	17.01	0.00	0.00	7.74	0.00	13.85	9.28	0.00
18+00.00	TO	18+63.88	32.30	0.00	0.00	25.19	49.34	0.00	21.41	41.94	0.00	0.00	11.62	0.00	21.41	30.31	0.00
18+63.88	TO	19+00.00	15.42	0.00	0.00	11.37	13.85	0.00	9.67	11.77	0.00	0.00	7.80	0.00	9.67	3.97	0.00
19+00.00	TO	20+00.00	10.85	0.00	0.00	21.60	0.00	0.00	18.36	0.00	0.00	0.00	21.60	0.00	18.36	-21.60	0.00
TOTALS =			431.21	0.00	0.00	657.97	1016.35	1067.31	559.27	863.90	907.22	2.20	90.22	63.05	557.07	773.68	844.17

 PATRICK ENGINEERING INC. 4970 VARSITY DRIVE LISLE, IL 60532 patrickengineering.com	USER NAME = Rdwy.Lisle	DESIGNED -	REVISED -	 Illinois Department of Transportation	BRYN MAWR AVE EARTHWORK SCHEDULE			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT CONFIG= PDFIGreg_Large.plt	DRAWN -	REVISED -					2578	532B		781	37
	PLOT SCALE = 1/8"=1'	CHECKED -	REVISED -					CONTRACT NO.				
	PLOT DATE = 12/3/2010	DATE - 12/3/2010	REVISED -					SCALE: 1/4"=50'	SHEET SCH-14 OF 18	STA.	TO STA.	FED. ROAD DIST. NO.