

ARDMORE AVE EARTHWORK			REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL ( 6" OF TOPSOIL REMOVAL )			EARTH EXCAVATION (CUT)			EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (15%)			EMBANKMENT (FILL)			EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)		
STATION	TO	STATION	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD
12+00.00	TO	13+00.00	34.98	0.00	0.00	53.13	0.00	31.29	45.16	0.00	26.59	0.00	0.00	69.85	45.16	0.00	-43.26
13+00.00	TO	14+00.00	50.91	0.00	0.00	74.66	0.00	68.70	63.46	0.00	58.40	0.00	0.00	44.43	63.46	0.00	13.97
14+00.00	TO	14+10.00	6.41	0.00	0.00	7.52	0.00	16.17	6.39	0.00	13.75	0.00	0.00	3.51	6.39	0.00	10.24
14+10.00	TO	16+00.00	125.70	0.00	0.00	135.29	229.58	236.22	114.99	195.15	200.78	0.00	57.33	23.94	114.99	137.81	176.84
16+00.00	TO	16+60.00	33.63	0.00	0.00	36.11	122.72	0.00	30.69	104.31	0.00	0.00	31.98	0.00	30.69	72.33	0.00
16+60.00	TO	17+00.00	14.61	0.00	0.00	16.58	56.64	0.00	14.09	48.14	0.00	0.00	18.55	0.00	14.09	29.59	0.00
17+00.00	TO	17+45.00	13.56	0.00	0.00	15.51	52.53	0.00	13.19	44.65	0.00	0.00	15.10	0.00	13.19	29.55	0.00
17+45.00	TO	17+63.00	5.64	0.00	0.00	3.34	22.11	0.00	2.84	18.80	0.00	0.22	1.93	0.00	2.62	16.87	0.00
17+63.00	TO	18+00.00	12.88	0.00	0.00	2.84	51.45	0.00	2.42	43.73	0.00	0.85	0.65	0.00	1.56	43.08	0.00
<b>TOTALS =</b>			<b>298.33</b>	<b>0.00</b>	<b>0.00</b>	<b>344.98</b>	<b>535.04</b>	<b>352.38</b>	<b>293.23</b>	<b>454.78</b>	<b>299.52</b>	<b>1.07</b>	<b>125.55</b>	<b>141.73</b>	<b>292.16</b>	<b>329.23</b>	<b>157.80</b>

G:\IDOT\9356\_A02\LL531\Drawings\CA00 Sheets\DI9139797-aht-schedule\_029-041.dgn