



NORWOOD AVE EARTHWORK			REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL ( 6" OF TOPSOIL REMOVAL )			EARTH EXCAVATION (CUT)			EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (15%)			EMBANKMENT (FILL)			EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)		
STATION	TO	STATION	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD
11+00.00	TO	12+00.00	70.38	0.00	0.00	12.12	0.00	197.56	10.30	0.00	167.92	0.56	0.00	2.68	9.74	0.00	165.25
12+00.00	TO	13+00.00	96.63	0.00	0.00	22.78	0.00	334.69	19.36	0.00	284.48	0.97	0.00	2.79	18.39	0.00	281.70
13+00.00	TO	14+00.00	129.62	0.00	0.00	39.47	0.00	557.80	33.55	0.00	474.13	4.40	0.00	0.21	29.15	0.00	473.91
14+00.00	TO	16+00.00	230.50	0.00	0.00	54.07	214.93	615.46	45.96	182.69	523.14	131.81	142.00	0.20	-85.85	40.69	522.94
16+00.00	TO	17+00.00	45.10	0.00	0.00	2.42	107.46	0.00	2.05	91.34	0.00	62.48	71.00	0.00	-60.43	20.34	0.00
<b>TOTALS =</b>			<b>572.23</b>	<b>0.00</b>	<b>0.00</b>	<b>130.86</b>	<b>322.39</b>	<b>1705.50</b>	<b>111.23</b>	<b>274.03</b>	<b>1449.68</b>	<b>200.23</b>	<b>213.00</b>	<b>5.88</b>	<b>-89.00</b>	<b>61.03</b>	<b>1443.80</b>

 <b>PATRICK ENGINEERING</b> PATRICK ENGINEERING INC. 4870 VARSITY DRIVE LISLE, IL 60532 patrickengineering.com	USER NAME = Rdwj.Lisle PLOT CONFIG= PDFFIGray_Large.plt PLOT SCALE = 1:50 PLOT DATE = 12/3/2010	DESIGNED - DRAWN - CHECKED - DATE - 12/3/2010	REVISED - REVISED - REVISED - REVISED -	 Illinois Department of Transportation	<b>NORWOOD AVE          EARTHWORK SCHEDULE</b>			F.A. RTE. 2578	SECTION 532B	COUNTY DUPAGE	TOTAL SHEETS 781	SHEET NO. 40	CONTRACT NO.	
	SCALE: 1"=50'    SHEET SCH-17 OF 18    STA.    TO STA.		FED. ROAD DIST. NO.    ILLINOIS FED. AID PROJECT											