

STREET	* UNDERCUT FOR PGE REPLACEMENT			REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (6" OF TOPSOIL REMOVAL)			EARTH EXCAVATION (CUT)			EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (15%)			EMBANKMENT (FILL)			EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)		
	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD	PRESTAGE CU YD	STAGE 1 CU YD	STAGE 2 CU YD
ARDMORE AVE.	0.00	0.00	0.00	298.33	0.00	0.00	344.98	535.04	352.38	293.23	454.78	299.52	1.07	125.55	141.73	292.16	329.23	157.80
ARMY TRAIL RD.	0.00	4,639.77	0.00	757.31	0.00	0.00	62.69	2,244.23	0.00	53.28	1,907.60	0.00	7.71	511.15	0.00	45.57	1,396.44	0.00
BRYN MAWR AVE.	0.00	0.00	0.00	431.21	0.00	0.00	657.97	1016.35	1067.31	559.27	863.90	907.22	2.20	90.22	63.05	557.07	773.68	844.17
IL 53	0.00	6403.68	4026.02	21985.20	4447.80	3991.16	3315.22	20031.51	17492.79	2817.94	17026.78	14868.87	7161.47	21714.36	9725.67	-4343.53	-4687.57	5143.20
IRVING PARK RD.	0.00	994.55	0.00	1,562.44	0.00	0.00	222.97	5,430.86	0.00	189.52	4,616.23	0.00	22.09	1,086.30	0.00	167.43	3,529.92	0.00
LAKE ST.	0.00	0.00	0.00	926.42	0.00	0.00	90.47	2,993.63	0.00	76.90	2,544.59	0.00	7.26	1,691.12	0.00	69.64	853.47	0.00
NORDIC RD.	0.00	0.00	0.00	487.52	0.00	0.00	32.64	659.48	1007.81	27.74	560.56	856.64	132.21	130.86	137.34	-104.47	429.69	719.30
NORWOOD AVE.	0.00	0.00	0.00	572.23	0.00	0.00	130.86	322.39	1705.50	111.23	274.03	1449.68	200.23	213.00	5.88	-89.00	61.03	1443.80
THORNDALE AVE.	0.00	0.00	0.00	692.98	0.00	0.00	812.98	1798.09	913.54	691.03	1528.37	776.51	13.40	93.06	191.03	677.64	1435.31	585.48
TOTALS=	0.00	12038.01	4026.02	27713.65	4447.80	3991.16	5670.77	35031.57	22539.34	4820.15	29776.84	19158.44	7547.65	25655.62	10264.70	-2727.49	4121.22	8893.74

**** REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL= 52,217 CU YD**
EARTH EXCAVATION (CALCULATED FROM EARTHWORK TABLE) = 63,245 CU YD
EARTH EXCAVATION (ADJUSTMENT FOR 30-YEAR PAVEMENT DESIGN) = 27,381 CU YD
EARTH EXCAVATION FOR LIGHTWEIGHT CELLULAR CONCRETE FILL = 2,361 CU YD
EARTH EXCAVATION FOR SEDIMENT TRAPS = 632 CU YD
93,619 CU YD
FURNISHED EXCAVATION= 2,730 CU YD

* PGE REPLACEMENT SHALL BE PAID FOR AS POROUS GRANULAR EMBANKMENT, SUBGRADE (CU YD). SEE THE PLAN AND PROFILE SHEETS AND THE SCHEDULE OF QUANTITIES FOR LOCATIONS AND THICKNESSES.

** THIS QUANTITY INCLUDES THE VOLUMES OF UNDERCUT FOR PGE REPLACEMENT AND 6" TOPSOIL REMOVAL.