



THE FOLLOWING ITEMS SHALL BE REMOVED BY THE CONTRACTOR AND SHALL BE DISPOSED OF BY THEM OUTSIDE THE RIGHT-OF-WAY AT THEIR EXPENSE. THE SALVAGE VALUE OF THE REMOVED EQUIPMENT SHALL BE REFLECTED IN THE CONTRACTOR'S BID PRICE.

- 3 EACH SIGNAL HEAD, 1-FACE, 3-SECTION, MAST ARM MOUNTED
- 5 EACH SIGNAL HEAD, 1-FACE, 3-SECTION, BRACKET MOUNTED
- 1 EACH SIGNAL HEAD, 2-FACE, 3-SECTION, BRACKET MOUNTED
- 3 EACH TRAFFIC SIGNAL BACKPLATE

NOTE 1: THE EXISTING 3C NO. 20 CABLE SHALL BE USED FOR TEMPORARY LIGHT DETECTOR TO BE MOUNTED ON THE TEMPORARY SIGNAL AT THE EAST RAMPS FOR THE TRAFFIC SIGNAL INSTALLATION AT THE WEST RAMP. ADDITIONAL CABLE SHALL BE SPLICED AS NEEDED. AFTER THE PERMANENT TRAFFIC SIGNAL INSTALLATION AT THE EAST RAMPS AND ARMY TRAIL ROAD IS OPERATIONAL, THE EXISTING 3C NO. 20 CABLE USED AS A TEMPORARY CABLE SHALL BE REMOVED (TOTAL 1701 FT.). THE REMOVAL OF THE EXISTING CABLE SHALL BE PAID FOR SEPARATELY AS "REMOVE EXISTING CABLE FROM CONDUIT".

FILE NAME =	USER NAME = #USER#	DESIGNED - PKG	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>TRAFFIC SIGNAL MODIFICATION PLAN ARMY TRAIL RD. AT RAMP "A" (WEST RAMP)</b>				F.A.P. RTE.:	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
#FILE#		DRAWN - MAA, EA	REVISED -		SCALE: 1"=20'	SHEET NO.	OF	SHEETS	STA.	TO STA.	2578	532B	DuPage	781	512
		CHECKED - PKG, EA	REVISED -		CONTRACT NO. 60477										
		PLOT DATE = #DATE#	DATE - 5/10/2010		FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT										