

SUMMARY OF QUANTITIES
INTERSTATE 55 (I-55) AT CENTRAL AVENUE

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	FUNDING BREAKDOWN - 90% FEDERAL, 10% STATE															
				URBAN		LO1 ACIM		LIC ACBHI		LO1 ACIM									
				ROAD 0003	LAND SCAPE 0003	BRIDGE SNO16-0724	BRIDGE SNO16-3240	BRIDGE SNO16-3241	RETAIN WALLS 0040	LIGHTING 0021	TRAF. SIGNAL 0021								
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	388		388														
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	174		174														
20101000	TEMPORARY FENCE	FOOT	200	200															
20101100	TREE TRUNK PROTECTION	EACH	19		19														
20200100	EARTH EXCAVATION	CU YD	13225	13225															
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1345	1345															
20800150	TRENCH BACKFILL	CU YD	512	512															
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	46421		46421														
25000210	SEEDING, CLASS 2A	ACRE	10		10														
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	900		900														
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	900		900														
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	900		900														
Δ 25000750	MOWING	ACRE	10		10														
25100115	MULCH, METHOD 2	ACRE	10		10														
25100630	EROSION CONTROL BLANKET	SQ YD	46421		46421														
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1000		1000														
28000305	TEMPORARY DITCH CHECKS	EACH	42		42														
28000510	INLET FILTERS	EACH	149		149														
28100107	STONE RIPRAP, CLASS A4	SQ YD	288	10				278											
28200200	FILTER FABRIC	SQ YD	306					306											
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	2318.0		2318														
31101400	SUBBASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	2872		2872														
31200502	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4 1/2"	SQ YD	37089		37089														
35101500	AGGREGATE BASE COURSE, TYPE B	CU YD	308		308														
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	7.4		7.4														
40600895	CONSTRUCTING TEST STRIP	EACH	3		3														
40603085	HOT-MIX ASPHALT BINDER COURSE, IL 19.0, N70	TON	1924		1924														
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	221		221														

Δ - INDICATES SPECIALTY ITEM
 ** - SEE BILL OF MATERIALS FOR INDIVIDUAL RETAINING WALL QUANTITIES
 Δ - NON-PARTICIPATING (100% STATE)

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	FUNDING BREAKDOWN - 90% FEDERAL, 10% STATE															
				URBAN		LO1 ACIM		LIC ACBHI		LO1 ACIM									
				ROAD 0003	LAND SCAPE 0003	BRIDGE SNO16-0724	BRIDGE SNO16-3240	BRIDGE SNO16-3241	RETAIN WALLS 0040	LIGHTING 0021	TRAF. SIGNAL 0021								
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	1928	1928															
42000521	PORTLAND CEMENT CONCRETE PAVEMENT 11" (JOINTED)	SQ YD	24176	24176															
42000570	PORTLAND CEMENT CONCRETE PAVEMENT 15" (JOINTED)	SQ YD	4768	4768															
42001300	PROTECTIVE COAT	SQ YD	38676		38676														
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	3650		3650														
42100390	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT, 15"	SQ YD	3181		3181														
42100615	PAVEMENT REINFORCEMENT	SQ YD	6831		6831														
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	2768		2768														
42400800	DETECTABLE WARNINGS	SQ FT	232		232														
44000100	PAVEMENT REMOVAL	SQ YD	21065		21065														
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	19443		19443														
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	6586		6586														
44000600	SIDEWALK REMOVAL	SO FT	2582		2582														
44004250	PAVED SHOULDER REMOVAL	SQ YD	15,267		15,267														
44200614	CLASS A PATCHES, TYPE IV, 13 INCH	SQ YD	54		54														
44213000	PATCHING REINFORCEMENT	SQ YD	54		54														
44213204	TIE BARS 3/4"	EACH	18		18														
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	1035		1035														
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1		1														
50102400	CONCRETE REMOVAL	CU YD	2255			1489.5	182.4	469.7	113.4										
50104000	BRIDGE RAIL REMOVAL	FOOT	6531.7			3967.3	1292.4	953.0	319.0										
50157300	PROTECTIVE SHIELD	SQ YD	11209.5			1681.1	3886.3	5642.1											
50200100	STRUCTURE EXCAVATION	CU YD	11746.1			9570.3	196.8	956.0	1023.0										
50200300	COFFERDAM EXCAVATION	CU YD	368.3			368.3													

TYLIN INTERNATIONAL	USER NAME = #USER#	DESIGNED - AZ	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	CENTRAL AVENUE OVER I-55 SUMMARY OF QUANTITIES			F.A.I. RTE. I-55	SECTION 0711.2R & 1011.1BR	COUNTY COOK	TOTAL SHEETS 741	SHEET NO. 4	Rev. 4/23/2011 20:35:55 PM
	PLOT SCALE = #SCALE#	CHECKED - DMJ	REVISED -		SCALE: NONE	SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	CONTRACT NO. 60999			
P:\01345\ROAD\55\qual.dgn		DATE - 03/25/2011	REVISED -										