



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 6, 2011

SUBJECT: FAP Route 338 (IL 59)
Project CMF-0338 (043)
Section 7 HB-K-N
Cook County
Contract No. 60K62
Item No. 288, June 17, 2011 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Replaced the Schedule of Prices.
2. Revised the Table of Contents to the Special Provisions.
3. Revised page 20 of the Special Provisions.
4. Revised sheets 2, 3 & 4A of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Scott E. Stitt, P.E.
Acting Engineer of Design and Environment

A handwritten signature in black ink, appearing to read "Ted B. Walschleger P.E." with a small "P.E." to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Diane O'Keefe, Region 1, District 1; Mike Renner; Estimates

TBW:MS:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60K62

State Job # - C-91-536-10
 PPS NBR - 1-78088-0000
 County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - 7HB-K-N

Project Number
 CMF-0338/043/

Route
 FAP 338

* REVISED : JUNE 02, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X0322054	REM PRC FL END SEC	EACH	2.000				
X0325880	COARSE AGGREGATE CA-7	TON	350.000				
X0326148	TEMP WP 60 CL4 15 MA	EACH	7.000				
X0504200	CONCRETE HEADWALL	EACH	1.000				
X7010216	TRAF CONT & PROT SPL	L SUM	1.000				
X7030030	WET REF TEM TAPE T3 4	FOOT	3,000.000				
X8210015	TEMP LUM HPSV 400	EACH	7.000				
Z0001050	AGG SUBGRADE 12	SQ YD	1,625.000				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.000				
Z0018911	DRILL-GROUT #6 T-BAR	EACH	1,500.000				
Z0023202	SED CONT DR ST INL CL	EACH	40.000				
Z0030850	TEMP INFO SIGNING	SQ FT	52.000				
Z0033028	MAINTAIN LIGHTING SYS	CAL MO	3.000				
Z0033044	RE-OPTIMIZE SIG SYS 1	EACH	2.000				
Z0073510	TEMP TR SIGNAL TIMING	EACH	2.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60K62

State Job # - C-91-536-10
 PPS NBR - 1-78088-0000
 County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - 7HB-K-N

Project Number
 CMF-0338/043/

Route
 FAP 338

* REVISED : JUNE 02, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
20200100	EARTH EXCAVATION	CU YD	1,125.000				
20201200	REM & DISP UNS MATL	CU YD	570.000				
20400800	FURNISHED EXCAVATION	CU YD	320.000				
20800150	TRENCH BACKFILL	CU YD	65.000				
21101615	TOPSOIL F & P 4	SQ YD	4,620.000				
25000210	SEEDING CL 2A	ACRE	1.000				
25000310	SEEDING CL 4	ACRE	0.200				
25000400	NITROGEN FERT NUTR	POUND	90.000				
25000500	PHOSPHORUS FERT NUTR	POUND	90.000				
25000600	POTASSIUM FERT NUTR	POUND	90.000				
25100630	EROSION CONTR BLANKET	SQ YD	4,620.000				
25100900	TURF REINF MAT	SQ YD	725.000				
28000250	TEMP EROS CONTR SEED	POUND	100.000				
28000305	TEMP DITCH CHECKS	FOOT	500.000				
28000400	PERIMETER EROS BAR	FOOT	3,000.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60K62

State Job # - C-91-536-10
 PPS NBR - 1-78088-0000
 County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - 7HB-K-N

Project Number
 CMF-0338/043/

Route
 FAP 338

* REVISED : JUNE 02, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
28000510	INLET FILTERS	EACH	40.000				
28100105	STONE RIPRAP CL A3	SQ YD	55.000				
28200200	FILTER FABRIC	SQ YD	1,000.000				
31200502	STAB SUBBASE HMA 4.5	SQ YD	500.000				
35501308	HMA BASE CSE 6	SQ YD	20.000				
40603310	HMA SC "C" N50	TON	3.000				
42000501	PCC PVT 10 JOINTED	SQ YD	2,000.000				
42001300	PROTECTIVE COAT	SQ YD	8,000.000				
44000100	PAVEMENT REM	SQ YD	330.000				
44000500	COMB CURB GUTTER REM	FOOT	1,000.000				
44003100	MEDIAN REMOVAL	SQ FT	13,275.000				
44004250	PAVED SHLD REMOVAL	SQ YD	60.000				
44200970	CL B PATCH T2 10	SQ YD	8.000				
44201299	DOWEL BARS 1 1/2	EACH	20.000				
44213200	SAW CUTS	FOOT	54.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

60K62

State Job # - C-91-536-10
 PPS NBR - 1-78088-0000
 County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - 7HB-K-N

Project Number
 CMF-0338/043/

Route
 FAP 338

* REVISED : JUNE 02, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
48300300	PCC SHOULDERS 8	SQ YD	60.000				
50104400	CONC HDWL REM	EACH	1.000				
50105220	PIPE CULVERT REMOV	FOOT	70.000				
542A1053	P CUL CL A 2 8	FOOT	12.000				
542A1057	P CUL CL A 2 12	FOOT	170.000				
542A1069	P CUL CL A 2 24	FOOT	30.000				
542A1072	P CUL CL A 2 27	FOOT	10.000				
542A1081	P CUL CL A 2 36	FOOT	85.000				
542A1903	P CUL CL A 3 18	FOOT	120.000				
542A1921	P CUL CL A 3 36	FOOT	10.000				
54213657	PRC FLAR END SEC 12	EACH	3.000				
54213669	PRC FLAR END SEC 24	EACH	2.000				
54213681	PRC FLAR END SEC 36	EACH	1.000				
54215991	R C PIPE ELBOW 36	EACH	1.000				
54247090	GRATING-C FL END S 12	EACH	3.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

60K62

State Job # - C-91-536-10
 PPS NBR - 1-78088-0000
 County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - 7HB-K-N

Project Number
 CMF-0338/043/

Route
 FAP 338

* REVISED : JUNE 02, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
54247130	GRATING-C FL END S 24	EACH	2.000				
54247170	GRATING-C FL END S 36	EACH	1.000				
60100060	CONC HDWL FOR P DRAIN	EACH	3.000				
60107600	PIPE UNDERDRAINS 4	FOOT	1,000.000				
60108100	PIPE UNDERDRAIN 4 SP	FOOT	50.000				
60200805	CB TA 4 DIA T8G	EACH	2.000				
60201340	CB TA 4 DIA T24F&G	EACH	6.000				
60204505	CB TA 5 DIA T8G	EACH	1.000				
60237470	INLETS TA T24F&G	EACH	1.000				
60250200	CB ADJUST	EACH	2.000				
60255500	MAN ADJUST	EACH	5.000				
60300105	FR & GRATES ADJUST	EACH	3.000				
60300305	FR & LIDS ADJUST	EACH	3.000				
60406100	FR & LIDS T1 CL	EACH	2.000				
60500050	REMOV CATCH BAS	EACH	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

60K62

State Job # - C-91-536-10
 PPS NBR - 1-78088-0000
 County Name - COOK - -
 Code - 31 - -
 District - 1 - -
 Section Number - 7HB-K-N

Project Number
 CMF-0338/043/

Route
 FAP 338

* REVISED : JUNE 02, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
60500060	REMOV INLETS	EACH	1.000				
60500080	REMOV CB - MAIN FLOW	EACH	6.000				
* 60600095	CLASS SI CONC OUTLET	CU YD	6.200				
60605000	COMB CC&G TB6.24	FOOT	1,000.000				
60618740	CONC MED TM2.12	SQ FT	1,800.000				
60619600	CONC MED TSB6.12	SQ FT	2,200.000				
60622800	CONC MED TSM6.12	SQ FT	1,800.000				
67100100	MOBILIZATION	L SUM	1.000				
* DELETE 70102625	TR CONT & PROT 701606	L SUM	1.000				
* DELETE 70102632	TR CONT & PROT 701602	L SUM	1.000				
* DELETE 70102635	TR CONT & PROT 701701	L SUM	1.000				
70103815	TR CONT SURVEILLANCE	CAL DA	30.000				
70301000	WORK ZONE PAVT MK REM	SQ FT	750.000				
72400730	RELOC SIGN PANEL T3	SQ FT	150.000				
73400100	CONC FOUNDATION	CU YD	10.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60K62

State Job # - C-91-536-10
 PPS NBR - 1-78088-0000
 County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - 7HB-K-N

Project Number
 CMF-0338/043/

Route
 FAP 338

* REVISED : JUNE 02, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
73502000	REL GR MT SIN SUPPORT	EACH	4.000				
73700200	REM CONC FDN-GR MT	EACH	4.000				
78008200	POLYUREA PM T1 LTR-SY	SQ FT	610.000				
78008230	POLYUREA PM T1 LN 6	FOOT	1,450.000				
78008270	POLYUREA PM T1 LN 24	FOOT	200.000				
78100100	RAISED REFL PAVT MKR	EACH	20.000				
81000600	CON T 2 GALVS	FOOT	770.000				
81000700	CON T 2 1/2 GALVS	FOOT	60.000				
81018600	CON P 2 1/2 GALVS	FOOT	500.000				
81018900	CON P 4 GALVS	FOOT	153.000				
81400100	HANDHOLE	EACH	3.000				
81603090	UD 3#4#6GXLPUSE 1 1/4	FOOT	2,675.000				
81800300	A CBL 3-1C2 MESS WIRE	FOOT	1,700.000				
81900200	TR & BKFIL F ELECT WK	FOOT	3,021.000				
83600200	LIGHT POLE FDN 24D	FOOT	120.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

60K62

State Job # - C-91-536-10
 PPS NBR - 1-78088-0000
 County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - 7HB-K-N

Project Number
 CMF-0338/043/

Route
 FAP 338

* REVISED : JUNE 02, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
84100110	REM TEMP LIGHT UNIT	EACH	7.000				
84400105	RELOC EX LT UNIT	EACH	7.000				
85000200	MAIN EX TR SIG INSTAL	EACH	2.000				
86200120	UNINTER POWER SUPPLY	EACH	2.000				
87301255	ELCBL C SIGNAL 14 7C	FOOT	980.000				
87301305	ELCBL C LEAD 14 1PR	FOOT	675.000				
87301900	ELCBL C EGRDC 6 1C	FOOT	285.000				
87502500	TS POST GALVS 16	EACH	2.000				
87800100	CONC FDN TY A	FOOT	8.000				
87900200	DRILL EX HANDHOLE	EACH	4.000				
88030020	SH LED 1F 3S MAM	EACH	4.000				
88030050	SH LED 1F 3S BM	EACH	6.000				
88030110	SH LED 1F 5S MAM	EACH	4.000				
88030210	SH LED 2F 3S BM	EACH	2.000				
88030220	SH LED 2F 5S BM	EACH	2.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60K62

State Job # - C-91-536-10
 PPS NBR - 1-78088-0000
 County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - 7HB-K-N

Project Number
 CMF-0338/043/

Route
 FAP 338

* REVISED : JUNE 02, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
88200210	TS BACKPLATE LOU ALUM	EACH	8.000				
88600100	DET LOOP T1	FOOT	240.000				
89502300	REM ELCBL FR CON	FOOT	340.000				
89502350	REM & RE ELCBL FR CON	FOOT	3,976.000				
89502375	REMOV EX TS EQUIP	EACH	2.000				
89502380	REMOV EX HANDHOLE	EACH	4.000				
89502385	REMOV EX CONC FDN	EACH	2.000				

TABLE OF CONTENTS

LOCATION OF PROJECT 1

DESCRIPTION OF PROJECT 1

MAINTENANCE OF ROADWAYS 1

STATUS OF UTILITIES TO BE ADJUSTED 2

AGGREGATE SUBGRADE, 12" (300 MM) 2

COARSE AGGREGATE FOR HOT-MIX ASPHALT (HMA) (D-1) 3

FINE AGGREGATE FOR HOT- MIX ASPHALT (HMA) (D-1) 6

RECLAIMED ASPHALT PAVEMENT (RAP) (BMPR) 7

RECLAIMED ASPHALT SHINGLES (RAS) (BMPR)..... 14

TEMPERATURE CONTROL FOR CONCRETE PLACEMENT (DISTRICT ONE) 18

EPOXY COATING ON REINFORCEMENT (DISTRICT ONE) 18

CLEANING EXISTING DRAINAGE STRUCTURES 18

TRAFFIC CONTROL PLAN 19

TRAFFIC CONTROL AND PROTECTION (SPECIAL) 20

TYPE III TEMPORARY TAPE FOR WET CONDITIONS 20

TEMPORARY INFORMATION SIGNING 20

GENERAL ELECTRICAL REQUIREMENTS..... 22

MAINTENANCE OF LIGHTING SYSTEMS..... 25

FOUNDATIONS 28

TRENCH AND BACKFILL FOR ELECTRICAL WORK 28

UNIT DUCT 29

UNDERGROUND RACEWAYS..... 30

WIRE AND CABLE 31

TRAFFIC SIGNAL SPECIFICATIONS..... 32

ALKALI-SILICA REACTION FOR CAST-IN-PLACE CONCRETE (BDE) 80

ALKALI-SILICA REACTION FOR PRECAST AND PRECAST PRESTRESSED CONCRETE (BDE) 83

APPROVAL OF PROPOSED BORROW AREAS, USE AREAS, AND/OR WASTE AREAS (BDE) 85

CEMENT (BDE) 86

CONCRETE ADMIXTURES (BDE) 88

CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE)..... 90

CONSTRUCTION AIR QUALITY - DIESEL VEHICLE EMISSIONS CONTROL (BDE) 92

CONSTRUCTION AIR QUALITY - IDLING RESTRICTIONS (BDE)..... 93

DETERMINATION OF THICKNESS (BDE)..... 94

DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE) 104

ENGINEER’S FIELD OFFICE TYPE A (BDE) 112

Revised 06/06/2011

EQUIPMENT RENTAL RATES (BDE)..... 114
 FLAGGER AT SIDE ROADS AND ENTRANCES (BDE) 115
 FRICTION AGGREGATE (BDE) 115
 HOT-MIX ASPHALT – ANTI-STRIPPING ADDITIVE (BDE) 117
 HOT-MIX ASPHALT - DENSITY TESTING OF LONGITUDINAL JOINTS (BDE) 118
 HOT-MIX ASPHALT – DROP-OFFS (BDE) 119
 LIQUIDATED DAMAGES (BDE)..... 119
 MULCH AND EROSION CONTROL BLANKETS (BDE)..... 119
 NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM / EROSION AND SEDIMENT
 CONTROL DEFICIENCY DEDUCTION (BDE) 122
 PAVEMENT PATCHING (BDE)..... 123
 PAYMENTS TO SUBCONTRACTORS (BDE) 124
 PIPE CULVERTS (BDE) 125
 POST MOUNTING OF SIGNS (BDE)..... 128
 PRECAST CONCRETE HANDLING HOLES (BDE) 128
 RAISED REFLECTIVE PAVEMENT MARKERS (BDE)..... 129
 SEEDING (BDE) 130
 SELF-CONSOLIDATING CONCRETE FOR PRECAST PRODUCTS (BDE)..... 132
 SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) 133
 TEMPORARY EROSION CONTROL (BDE) 134
 TRAFFIC CONTROL SURVEILLANCE (BDE)..... 137
 TRUCK MOUNTED/TRAILER MOUNTED ATTENUATORS (BDE) 137
 UTILITY COORDINATION AND CONFLICTS (BDE)..... 137
 WORKING DAYS (BDE) 142
 BACKFILLING STORM SEWER UNDER ROADWAY 143
 STEEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID) 143
 STORM WATER POLLUTION PREVENTION PLAN..... 147
 404 PERMIT..... 156

Revised 06/06/2011

TRAFFIC CONTROL AND PROTECTION (SPECIAL)

Effective: February 1, 1996

Revised: March 1, 2011

Specific traffic control plan details and Special Provisions have been prepared for this contract. This work shall include all labor, materials, transportation, handling and incidental work necessary to furnish, install, maintain and remove all traffic control devices required as indicated in the plans and as approved by the Engineer.

When traffic is to be directed over a detour route, the Contractor shall furnish, erect, maintain and remove all applicable traffic control devices along the detour route according to the details shown in the plans.

Method of Measurement: All traffic control (except Traffic Control and Protection (Expressways)) and temporary pavement markings) indicated on the traffic control plan details and specified in the Special Provisions will be measured for payment on a lump sum basis.

Basis of Payment: All traffic control and protection will be paid for at the contract lump sum price for TRAFFIC CONTROL AND PROTECTION (SPECIAL).

Temporary pavement markings will be paid for separately unless shown on a Standard.

TYPE III TEMPORARY TAPE FOR WET CONDITIONS

Effective: February 1, 2007

Description. This work shall consist of furnishing, installing, maintaining and removing Type III Temporary Pavement Marking Tape for Wet Conditions.

Type III Temporary Tape shall meet the requirements of Article 1095.06 of the Standard Specifications. Initial minimum reflectance values under dry and wet conditions shall be as specified in Article 1095.06. The marking tape shall maintain its reflective properties when submerged in water. The wet reflective properties shall be verified by a visual inspection method performed by the Department. The surface of the material shall provide an average skid resistance of 50 BPN when tested according to ASTM E 303.

Prior to application a surface preparation adhesive shall be applied to a clean, dry road surface. The pavement marking tape shall have a pre-coated pressure sensitive adhesive and shall require no activation procedures.

Basis of Payment. This work will be paid for at the contract unit price per foot (meter) for WET REFLECTIVE TEMPORARY TAPE TYPE III of the line width specified, and at the contract unit price per square foot (square meter) for WET REFLECTIVE TEMPORARY LETTERS AND SYMBOLS.

TEMPORARY INFORMATION SIGNING

Effective: November 13, 1996

Revised: January 2, 2007

Description.

This work shall consist of furnishing, installing, maintaining, relocating for various states of construction and eventually removing temporary informational signs.

Revised 06/06/2011