

GENERAL NOTES

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 800-892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS FACILITIES. (48 HOUR NOTIFICATION IS REQUIRED)

THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES AND KANE COUNTY.

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.

BUTT JOINTS WILL BE INSTALLED AT THE ENDS OF ALL RESURFACING (WHERE RESURFACING MEETS EXISTING PAVEMENT), IN ACCORDANCE WITH THE "BUTT JOINT AND HMA TAPER DETAILS" SHEET INCLUDED IN THE PLANS, UNLESS OTHERWISE SPECIFIED.

WHEN MILLED PAVEMENT IS OPEN TO TRAFFIC THE MAXIMUM GRADE DIFFERENTIAL BETWEEN PASSES OF THE MILLING MACHINE SHALL NOT EXCEED 1 1/2 INCHES (40MM) WHERE THE SPEED LIMIT IS 45 MPH (80KM/H) OR LESS AND 1 INCH (25 MM) WHERE THE SPEED LIMIT IS GREATER THAN 45 MPH (80 KM/H), WITH WRITTEN APPROVAL FROM THE ENGINEER, A MAXIMUM GRADE DIFFERENTIAL OF 3 INCHES (75 MM) MAY BE ALLOWED IF THE EDGE OF THE MILLING IS SLOPED A MINIMUM 1:3 (V:H).

ALL PAVEMENT MARKINGS SHALL BE PLACED THROUGHOUT THE IMPROVEMENT ACCORDING TO DISTRICT 1 TYPICAL PAVEMENT MARKING.

THE RESIDENT ENGINEER SHALL CONTACT MR. DON CHIARUGI, AREA TRAFFIC FIELD ENGINEER AT (847) 741-9857 (OFFICE) OR (847) 715-8416 (CELL), A MINIMUM OF 2 WEEKS PRIOR TO PLACEMENT OF PERMANENT PAVEMENT MARKINGS.

THE STOP SIGNS SHALL REMAIN THE PROPERTY OF THE STATE. THE RESIDENT ENGINEER SHALL CONTACT MR. DON CHIARUGI AT (847) 741-9857 (OFFICE) TO NOTIFY HIM THAT THE STOPS SIGNS HAVE BEEN TAKEN DOWN AND ARE READY TO BE PICKED UP.

RAISED REFLECTIVE PAVEMENT MARKERS SHALL BE PLACED ALONG IL 38 ACCORDING TO THE DISTRICT STANDARDS AS NOTED IN THE DETAIL.

PRIOR TO EMBANKMENT PLACEMENT, ALL VEGETATION, LOOSE MATERIAL, AND UNSTABLE MATERIAL SHOULD BE REMOVED TO DEPTH ENCOUNTERED AND REPLACED WITH SUITABLE EMBANKMENT MATERIAL. ANY EMBANKMENT WIDENING ON EXISTING SLOPES SHOULD BE BENCHED IN ACCORDANCE WITH ARTICLE 205.04 OF THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION.

THE UNIT WEIGHT (CONVERSION FACTOR) QUOTED IS FOR THE ESTIMATING PLAN QUANTITIES ONLY. ACTUAL QUANTITIES TO FULFILL CONTRACT REQUIREMENTS WILL BE DETERMINED BASED ON UNIT WEIGHT OF APPROVED MIX DESIGN, PLAN DIMENSIONS, AND DENSITY LIMITATIONS. MAXIMUM PAYMENT WILL BE COMPUTED BASED ON WEIGHT AVERAGE DENSITIES OF THE IN-PLACE MIXTURE.

THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE ARTERIAL TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470, A MINIMUM OF 72 HOURS PRIOR TO BEGINNING WORK.

KANE COUNTY NOTES

KANE COUNTY WILL REMOVE ALL EXISTING AND INSTALL ALL NEW SIGNING FOR MEREDITH ROAD. RAY JOHNSON (630) 406-7356 SHALL BE CONTACTED A MINIMUM OF 72 HOURS IN ADVANCE OF ANY NECESSARY REMOVAL AND A MINIMUM OF THREE WEEKS FOR THE INSTALLATION OF NEW SIGNING.

RECESSED REFLECTIVE PAVEMENT MARKERS SHALL BE PLACED ON MEREDITH ROAD ONLY.

URETHANE PAVEMENT MARKINGS SHALL BE PLACED ON MEREDITH ROAD ONLY.

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	INDEX OF SHEETS, STATE STANDARDS, AND GENERAL NOTES
3-4	SUMMARY OF QUANTITIES
5-7	TYPICAL SECTIONS
7A	VARIABLE DEPTH MILLING CHART
8-11	SCHEDULE OF QUANTITIES (EARTHWORK)
12-13	ALIGNMENT, TIES, AND BENCHMARKS
14-18	SUE INVESTIGATION
19-22	EXISTING & PROPOSED ROADWAY PLAN
23	EROSION CONTROL NOTES
24-25	EROSION CONTROL PLAN
26	DRAINAGE DETAILS/ TABLES
27-30	DRAINAGE AND UTILITY PLAN
31-35	PLAT OF HIGHWAYS
36-37	PAVEMENT MARKING AND LANDSCAPING PLANS
38-41	TRAFFIC SIGNAL PLANS
42-47	DISTRICT 1 STANDARD TRAFFIC SIGNAL DESIGN DETAILS (TS-05)
48	DRIVEWAY DETAILS-DISTANCE BETWEEN R.O.W. AND FACE OF CURB AND EDGE OF SHOULDERS >= 15' (4.5 M) (BD-01)
49	PAVEMENT PATCHING FOR HOT-MIX ASPHALT SURFACED PAVEMENT (BD-22)
50	BUTT JOINT AND HOT-MIX ASPHALT TAPER DETAILS (BD-32)
51	BENCHING DETAIL FOR EMBANKMENT WIDENING (BD-51)
52	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS (TC-10)
53	TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS (SNOW PLOW RESISTANT) (TC-11)
54	TYPICAL RECESSED REFLECTIVE PAVEMENT MARKERS (KC781001-03) KANE COUNTY STD.
55	DISTRICT ONE TYPICAL PAVEMENT MARKINGS (TC-13)
56	PAVEMENT MARKING LETTER AND SYMBOLS FOR TRAFFIC STAGING (TC-16)
57	ARTERIAL ROAD INFORMATION SIGNING (TC-22)
58-77	CROSS-SECTIONS

LIST OF STANDARDS

000001-06	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
280001-05	TEMPORARY EROSION CONTROL SYSTEMS
442201-03	CLASS C AND D PATCHES
482011-03	HMA SHLD. STRIPS/SHLDS. WITH RESURFACING OR WIDENING AND RESURFACING PROJECTS
542301-03	GRATING FOR CONCRETE FLARED END SECTION FOR 600MM (24") THRU 1300MM (54") PIPE
542311-02	PRECAST REINFORCED CONCRETE FLARED END SECTIONS
701201-04	LANE CLOSURE, 2L, 2W, DAY ONLY, FOR SPEEDS ≥ 45 MPH
701301-04	LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
701306-03	LANE CLOSURE, 2L,2W, SLOW MOVING OPERATIONS DAY ONLY, FOR SPEEDS ≥ 45 MPH
701326-04	LANE CLOSURE, 2L, 2W, PAVEMENT WIDENING, FOR SPEEDS ≥ 45 MPH
701901-01	TRAFFIC CONTROL DEVICES
720001-01	SIGN PANEL MOUNTING DETAILS
814001-02	CONCRETE HANDHOLES
814006-02	DOUBLE HANDHOLES
857001-01	STANDARD PHASE DESIGNATION DIAGRAMS AND PHASE SEQUENCES
877001-04	STEEL MAST ARM ASSEMBLY AND POLE
878001-08	CONCRETE FOUNDATION DETAILS
880006-01	TRAFFIC SIGNAL MOUNTING DETAILS
886001-01	DETECTOR LOOP INSTALLATIONS
886006-01	TYPICAL LAYOUT FOR DETECTOR LOOPS

FILE NAME =	USER NAME = abreuah	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	ILL 38 AT MEREDITH ROAD INDEX OF SHEETS			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
cr:\pw\work\p\idot\abreuah\d8139632\PI1538-Design.dgn		DRAWN -	REVISED -					567	5 R-N-1	KANE	77	2
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -		CONTRACT NO. 60K65							
PLOT DATE = 2/1/2011		DATE -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO	STA.	ILLINOIS FED. AID PROJECT