



NOTE: REFER SHEET TS-01 FOR TEMPORARY TRAFFIC SIGNAL NOTES.

RESTORATION OF WORK AREA. RESTORATION OF THE TRAFFIC SIGNAL WORK AREA SHALL BE INCIDENTAL TO TEMPORARY TRAFFIC SIGNAL INSTALLATION AND NO EXTRA COMPENSATION SHALL BE ALLOWED. ALL ROADWAY SURFACES SUCH AS SHOULDERS, MEDIAN, SIDEWALKS, PAVEMENT ETC. SHALL BE REPLACED IN KIND. ALL DAMAGE TO MOWED LAWNS SHALL BE REPLACED WITH AN APPROVED SOD, AND ALL DAMAGE TO UNMOWED FIELDS SHALL BE SEEDED IN ACCORDANCE WITH STANDARD SPECIFICATIONS 252 AND 250 RESPECTIVELY.

I.D.O.T. TRAFFIC SIGNAL INSTALLATION ELECTRICAL SERVICE REQUIREMENTS					TOTAL WATTAGE
TYPE	NO. LAMPS	WATTAGE INCAND	WATTAGE LED	% OPERATION	
SIGNAL (RED)	12	135	17	0.50	102.0
(YELLOW)	12	135	25	0.25	75.0
(GREEN)	12	135	15	0.25	45.0
ARROW	8	135	12	0.10	9.6
PED. SIGNAL		90	25	1.00	
CONTROLLER	1	100	100	1.00	100
ILLUM. SIGN		84	35	0.05	
VIDEO SYSTEM	1	150		1.00	150
FLASHER		135	25	0.50	
TOTAL =					481.6

ENERGY COST TO: Illinois Department of Transportation
 Division of Highways / District I
 201W Center Court, Schaumburg, Illinois 60196-1096
 ENERGY SUPPLY: CONTACT: VALARIE MURPHY
 PHONE: 708-235-2346
 COMPANY: ComEd

FILE NAME =	RV	USER NAME = #USER#	DESIGNED - AS	REVISED -
#FILE#	AS		DRAWN - RV	REVISED -
		PLOT SCALE = #SCALE#	CHECKED - MSA	REVISED -
		PLOT DATE = #DATE# NONE	DATE - #DATE#	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**TEMPORARY CABLE PLAN
DIXIE HIGHWAY @ FLOSSMOOR RD**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2843	3249-1-2	COOK	25	10
CONTRACT NO. 60L1B				
ILLINOIS FED. AID PROJECT				

TS-02
AMES Engineering, Inc.
 Consulting Engineers
 1341 Warren Avenue
 Downers Grove, IL 60515